SCIENTIFIC AMERICAN

NEW YORK
1898—1908
ENGINEERING NUMBER

DECEMBER 5, 1908
VOL. XCIX.—No. 23

PUBLISHED BY
MUNN AND COMPANY
NEW YORK

COPYRIGHT 1908 BY MUNN & COMPANY

PRICE TEN CENTS

© 1908 SCIENTIFIC AMERICAN, INC



The Foundation of

BORDEN QUALITY

is

Purity at the Dairy

EAGLE BRAND
CONDENSED
MILK
"THE ORIGINAL"

PEERLESS BRAND
EVAPORATED
MILK
(UNSWEETENED)

Borden's Milk products are manufactured under a system of Sanitary Regulations which are so rigidly observed that Purity is assured. This system does not only obtain during the process of manufacture, but it goes back to the Dairy Farm where the raw milk is produced, embracing the care and feeding of cattle, proper construction, lighting and ventilation of barns and location of milk houses, and minute details governing the handling of the milk at every stage.

EAGLE BRAND Condensed Milk as an infant food has no equal. Experience has established the fact that Eagle Brand Condensed Milk is acted upon by the infant stomach substantially the same as mother's milk, which makes it a superior food for infants.

PEERLESS BRAND Evaporated Milk (unsweetened) is simply pure cow's milk reduced in vacuo to a creamy consistency by the Borden Process and preserved by sterilization only. It is rich in cream and meets every requirement for rich milk or cream. It has all the advantages of fresh fluid milk and none of its disadvantages.

BORDEN'S MALTED MILK

BORDEN'S MALTED MILK is valuable not only for children and the aged but also for invalids and dyspeptics as well as those in normal health. Easily prepared and quickly assimilated, it restores energy and affords proper nourishment with minimum tax on digestion. Write for Malted Milk Book.

Est. 1857 BORDEN'S CONDENSED MILK CO. New York
"Leaders of Quality"



U. S. War College, Washington, D. C. One of a group of United States Government Buildings constructed throughout by the Kahn System of Reinforced Concrete

Better Buildings, Fire-Proof Buildings at Lower Cost

THE KAHN SYSTEM of Reinforced Concrete Construction appeals to conservative and progressive men because of permanency and low cost of maintenance. All buildings so constructed are as absolutely fire-proof as human skill can make them, and this without sacrificing architectural beauty or practical utility.

The United States Government in the construction of public buildings adopts only established and successfully tested methods.

The United States Government has adopted KAHN SYSTEM in the following buildings (and other Government construction work KAHN SYSTEM is continually going on): Academic Group for United States Navy, Annapolis, Md., 8 buildings. Cadet, Artillery and Cavalry Barracks and Officers' Quarters, West Point, N. Y., 10 buildings. Army Barracks, War College, Agricultural Building, Naval Hospital, Municipal Building and Government Hospital for Insane, Washington, D. C. Government Hospitals, Ellis Island, N. Y. Storehouse, Charleston, S. C. Arsenal, Frankford, Pa. Post Offices at Mitchell, S. D., St. Charles, Mo. and Battle Creek, Mich.

KAHN SYSTEM assures the utmost speed in erection. This is important because it insures quick returns on the capital invested in buildings. It eliminates expense of repairs, reduces insurance.

KAHN SYSTEM is adapted to every type of building. We mail, free, on request, seperate catalogs, describing: (1) Reinforced Concrete in General; (2) Mills and Factories; (3) Warehouse and Storage Buildings; (4) Hotels, Apartment Hous s, Schools, Residences, (5) Office Buildings; (6) Hospitals, Libraries and Public Buildings; (7) Bridges and Viaducts; (8) Record of Results; (9) Rib Lath for Homes. Preliminary designs and estimates free of charge. We cooperate with your architect or contractor if desired.

Behind the KAHN SYSTEM is a $1,250,000 organization, with the equipment to handle every detail in building with maximum engineering skill, speed and economy.

If you are going to build it is only good business that you should inform yourself of the superior merits of the KAHN SYSTEM. We promptly supply you with complete information free of cost. When you build, build KAHN SYSTEM, and thereby insure the permanence and profitableness of your investment.

TRUSSED CONCRETE STEEL CO.

502 Trussed Concrete Building **DETROIT, MICH.**

KAHN SYSTEM



A Definite Plan

IF you get right down to the practical and consider what is best for you, you will realize that the Navy affords an opening NOW and, moreover, a definite plan for your FUTURE. These great battleships, cruisers and torpedo boats, with their splendid machinery (under electrical, pneumatic and hydraulic control) require hundreds of expert mechanics and artificers. The new vessels building will give chances for advancement for years to come to the young men who enter the Navy this winter.

¶ A young man who has a talent for mechanics may be given instruction he needs at a Navy training station; and be assigned to duty on board a vessel after a few months. He will work with other ambitious men who started as he did, under men who have themselves worked up, and, therefore, encourage conscientious work.

¶ Promotions and increased pay, when earned; opportunities to learn and to save money; leisure for study, reading and recreation; frequent shore leave when in port; the free use of libraries and gymnasium at the training stations—these are a few of many inducements you can learn about if you will call at a Navy recruiting station. Write to-day for booklet and address of nearest recruiting office to Box 39, Bureau of Navigation, Navy Department, Washington, D. C.



The Development of the

Remington

is the History of the Writing Machine

NEW MODELS, 10 and 11 --- NOW READY

MODEL 10
With Column Selector

MODEL 11
With Built-in Tabulator

REMINGTON TYPEWRITER COMPANY
(Incorporated)
NEW YORK AND EVERYWHERE

© 1908 SCIENTIFIC AMERICAN, INC

W. & L. E. GURLEY

TROY, N. Y., U. S. A.



Civil Engineers' and Surveyors' Instruments, Current Meters, Leveling Rods, Chains, Tapelines and Draughtsman's Supplies.

Write for Catalogue "G"



Standard Weights and Measures, Sealers' Apparatus

Write for catalogue "S"

Physical and Scientific Apparatus for schools, colleges and private laboratories. Electrical Test Instruments.

Write for catalogue "P"

Accurate Mercurial Thermometers.

Write for catalogue "W"

Please mention the Scientific American when writing

Branch factory, Manufacturers' Exchange Building, Seattle, Wash.



© 1908 SCIENTIFIC AMERICAN, INC

The Very Newest Idea in

PRUDENTIAL

Life Insurance



A Statement by the President:

THERE is no other business which bears so important a relation to the welfare of the family as that of Life Insurance. The Prudential's object is to provide for the men and women of the United States the most practical form of Life Insurance Protection – that which will contribute most completely to the welfare of those for whose benefit Life Insurance is taken.

With this sincere purpose in mind, The Prudential is issuing a Life Insurance Policy which, it is believed, meets more closely the necessities of the family—those who are left behind when the breadwinner dies—than any other form of Life Insurance before the American people to-day.

It is called the **Monthly Income** Policy, from the fact that the proceeds, instead of being payable in one sum, are paid to the family in a **series of checks** on the first of each month—and continue for a period of 20 years or for the lifetime of the Beneficiary if it has been so selected.

The great advantages of this plan are apparent. Think of being able to leave your wife a **Monthly Income**—a guaranteed sum which nothing can disturb—not affected by hard times, bad judgment in investments—which cannot be lost, depreciated or stolen—but which will come to her regularly **every month for twenty years, or her lifetime**—thus enabling her to adjust the family expenditures, relieving her from all worry and putting poverty out of reach.

This is just what the new Monthly Income Policy accomplishes—it pays the rent, the household bills, provides food, clothing, education for the children—perpetuates your salary in fact – all by a monthly Income which cannot fail.

THE COST of this policy is low. For example, if you should be 30 years old you could, by paying the Prudential $167.35 per year (which means a saving of only $13.95 per month, or about $3.50 per week), assure to your family after your death—**$50 Every Month for 20 years,** or $12,000 in all! At slightly higher cost, you could make this Income payable to your wife or daughter **for her entire lifetime.** This is called the Whole Life Plan.

You can also arrange to confine all your payments to the Company to the first 20 years after taking out the Policy. This is called the 20 Payment Life Plan.

Now suppose you would like to arrange to **protect your own old age**—to assure yourself of an Income which would start 20 years from to-day, if living, and last for 20 years longer, or—for you as long as you live and your wife as long as she lives if she survives you. This can be done too, under the Endowment Plan.

Suppose you and your wife were both 40 years of age: $214.20 per year (a saving of $4.12 weekly) paid to the Company for 20 years would provide a **guaranteed Income** of $25 per month, beginning at age 60 and **continuing as long** as **either you or your wife should live**—and in any event for not less than 20 years.

Every rate and value in this Policy is absolutely guaranteed—in the Policy itself—while back of it are the great resources of The Prudential.

The success already attending this new **Monthly Income Policy proves that** it is striking the keynote of popular demand. You cannot afford to ignore a method of providing for your family or for your own old age a protection so sensible, so sure, so convenient, and so inexpensive. We wish to tell you what The Prudential can do for **You** in this matter. Write now while the subject is fresh in your mind. We will furnish you full Information—just adapted to **Your** particular case.

Remember, we believe this to be the greatest plan for the protection of your family ever devised—marking an epoch in Life Insurance. **You** should take advantage of it, for your family's sake. **Write Now** to

The Prudential Insurance Co.
OF AMERICA

Incorporated as a Stock Company by the State of New Jersey.

Home Office: Newark, N. J.

John F. Dryden

President.

In order that we shall know where you read this we would appreciate it if you would mention this publication in your letter.

© 1908 SCIENTIFIC AMERICAN, INC

SCIENTIFIC AMERICAN

[Entered at the Post Office of New York. N. Y.. as Second Class Matter. Copyright, 1908, by Munn & Co.]

Vol. XCIX.—No. 23. ESTABLISHED 1845. | NEW YORK, DECEMBER 5, 1908. | 10 CENTS A COPY $3.00 A YEAR.

The problem of transportation in the city of New York is rendered extremely difficult and costly by the fact that 2,000,000 of the people live upon, and as many more daily enter or leave, a long, narrow island, which is separated from the mainland by broad and deep rivers. To overcome this isolation public and private enterprise has built, during the past decade, no less than fourteen tunnels and three of the greatest long-span bridges of the world.

BIRD'S EYE VIEW OF MANHATTAN ISLAND, SHOWING NEW YORK'S ELABORATE SYSTEM OF BRIDGES AND TUNNELS.

© 1908 SCIENTIFIC AMERICAN, INC

SCIENTIFIC AMERICAN

ESTABLISHED 1845

MUNN & CO. - - Editors and Proprietors

Published Weekly at

No. 361 Broadway, New York

CHARLES ALLEN MUNN, *President*
361 Broadway, New York

FREDERICK CONVERSE BEACH, *Sec'y and Treas.*
361 Broadway, New York

TERMS TO SUBSCRIBERS.

One copy, one year, for the United States or Mexico $3.00
One copy, one year, for Canada 3.75
One copy, one year, to any foreign country, postage prepaid, 18s. 6d. 4.50

THE SCIENTIFIC AMERICAN PUBLICATIONS.

Scientific American (established 1845) ..... $3.00 a year
Scientific American Supplement (established 1876)..... 5.00 "
American Homes and Gardens ..... 3.00 "
Scientific American Export Edition (established 1878). ..... 3.00 "

The combined subscription rates and rates to foreign countries, including Canada, will be furnished upon application.

Remit by postal or express money order, or by bank draft or check.
MUNN & CO., 361 Broadway, New York.

NEW YORK, SATURDAY, DECEMBER 5, 1908.

The Editor is always glad to receive for examination illustrated articles on subjects of timely interest. If the photographs are *sharp*, the articles *short*, and the facts *authentic*, the contributions will receive special attention. Accepted articles will be paid for at regular space rates.

THE ETHICS OF CRITICISM.

Honest criticism is one of the most healthy tonics that can be given to an institution during the period of its development and growth; but criticism that is dishonest may work an unlimited amount of injury. We have always believed that the attack upon the designs of our battleships and upon the responsible Bureaus was prompted, at its inception, by a sincere desire on the part of some of the younger men of our navy to improve conditions in certain particulars where they believed they could be bettered; but we noted with considerable regret, that when the charges were taken up by the Bureaus, and proved to be either absolutely wrong, or true only in a limited degree, the critics and their advocates in the press began to resort to the expedient of throwing dust into the eyes of the public, by quoting those half truths, which frequently convey an impression entirely at variance with the actual facts. One leading daily journal in this city, indeed, seems to have deliberately set itself the task of so manipulating official and semi-official reports of naval proceedings, as to give the public a false impression of what has taken place.

In proof of what we have said, it will be sufficient to mention ne of the most glaring instances of this persistent misleading of the public. We refer to that part of the findings of the Newport Conference (which, it will be remembered, was called by the President for the purpose of thoroughly thrashing out the whole question of battleship defects) in which, by an overwhelming majority, it was decided that in future battleships the lower edge of the armor belt should be placed twelve inches lower than it is on existing ships, and that the top edge of the belt should be placed four inches higher. Now, any schoolboy can see that the *total* effect of adding four inches above the waterline and twelve inches below the waterline is to move the whole body of the plate four inches lower with regard to the waterline than it was before. This means that it was the opinion of the Naval Conference, not that the armor belt in our existing ships was too low (which was the contention of the critics), but that, if anything, it was too high. Had they considered that the armor belt was too low, several feet too low, as the critics contend, the Conference would have added the whole increase in the width of the belt to the upper edge and raised it, not four inches, but sixteen inches higher. Yet, in spite of this obvious intention on the part of the C nference, the daily paper in question came out with a headline announcement to the effect that the Newport Conference indorsed the naval critics by deciding that the upper edge of the belt should be raised four inches higher. This is but one glaring instance out of many, of the way in which our contemporary is endeavoring to mislead the public upon a highly technical subject, in the mazes of which the average layman may only too readily become confused.

The Scientific American will probably have something more to say on this subject in a later issue; but for the present we beg to assure our readers that the findings of the Newport Conference constitute a strong indorsement of the ships of the United States navy. At the same time, it is only fair to the critics to state that the Conference approved of several valuable suggestions regarding the emplacement and protection of the battery of torpedo guns and the protection of the uptakes to the smokestacks.

SOME EARLY LIGHT-WEIGHT MOTORS.

Langley was told by steam engineers that he could not produce an engine and boiler that would weigh less than 100 pounds to the horse-power. He knew nothing about the subject of steam engineering, and was obliged to study the thing up and work it out for himself. He made many experimental engines, very tiny affairs, and eventually he produced one that, with the boiler, weighed only 7 pounds to the horse-power without water. The engine alone weighed 26 ounces, and developed 1¼ horse-power. The gasoline engines used on the models, and also on the full-sized machine, were made by Charles M. Manly. The model was air-cooled, with five cylinders, developed three horse-power, and weighed 10 pounds. The aeroplane was one-quarter the size of the man-carrying aeroplane. The engine of the latter was identical, except that it had water-cooled cylinders. The engine itself weighed 125 pounds, and with 25 pounds of water, radiator, batteries, spark coils, and all accessories, weighed just under 200 pounds. It developed 52 horse-power for ten hours continuous running at 930 revolutions per minute. The bore was 5 inches, and stroke 5½ inches. This engine was produced in 1901. There are very few motors at the present time that can equal it.

SCHOONERS FOR INTERNATIONAL YACHT RACING.

It begins to look as though future interest in international yachting would be transferred from the large single-stickers of the type of "Reliance" and "Shamrock" to the schooners. The revival of interest in this noble type is due to the success of that splendid yacht "Germania," which our esteemed contemporary, the Yachtsman, of England, designates as "the grandest schooner that ever sailed in British waters." The "Germania" is owned by a German yachtsman, and was built at the Krupp yards from plans of a German designer. During last year's racing season in the Solent, the new yacht made practically a clean sweep of all the schooners opposed to her, among which were included the best of the English yachts and the German Emperor's yacht "Meteor." The success of "Germania" naturally aroused great enthusiasm, and it has led to the placing of an order by the Emperor for the construction of a large schooner to race against the new craft next year. This, in its turn, has stimulated a leading English yachtsman to place an order for a schooner, which is to be built during the coming winter, and be ready in time for the opening gun of the yacht season of 1909. There was a time when schooner racing was the favorite sport of British yachtsmen, and we understand that every effort will be made to regain the supremacy which once was theirs. It now remains for one of our yachtsmen to build a crack racing schooner and send her to the Solent, to insure that the summer of 1909 will see some of the most brilliant and exciting international racing of the present century.

THE GRAND PRIZE AUTOMOBILE ROAD RACE AND ITS PROBABLE SUCCESSOR.

The Grand Prize race of the Automobile Club of America, which was held upon a specially-prepared 25.13-mile circuit at Savannah, Georgia, on Thanksgiving Day, was the second great international road race to be held in America this year. Against the six foreign firms that were represented by one, two, or three cars each, America had but six entries of as many different machines. Three of these machines—the Acme, Chadwick, and National—were fitted with 6-cylinder engines, while the Lozier, Simplex, and Buick had the usual 4-cylinder type of motor used upon all the foreign cars.

Twenty machines started in this 402.8-mile race, which consisted of sixteen circuits of the course. France was represented by a De Dietrich, two Clement, and two Renault cars; Germany by three Benz; and Italy by three Fiat and three Itala machines. From the start the Fiat and Benz cars led, and at the end of the tenth round the first five places were held by these two makes, the former being second and third. During the next lap a tire came off of one of the German machines and struck the driver's head, causing him to lose control and strike a tree. Fortunately neither Erle nor his mechanic was seriously injured. Nazzaro's Fiat, after leading from the twelfth round, was delayed by tire trouble in the last one, and thus lost the race to Wagner's Fiat. Hemery's Benz was second, it being beaten by but 56 seconds, and Henriot's Benz fourth. Eighth and ninth places went to Itala and Fiat cars, while Clement, Renault, and Clement machines were fifth, sixth, and seventh respectively. The French De Dietrich and American Simplex were making their fifteenth rounds and the National and Lozier their twelfth and eleventh, when the race was called off.

The time of the winner was 6 hours, 10 minutes, and 31 seconds, which corresponds to an average speed of 65.11 miles an hour. De Palma's Fiat twice covered the course in 21:36—an average speed of 70½ miles an hour. On a measured mile on one of the 3-mile straightaway stretches, several of the cars made over 100 miles an hour. Considering the number of turns in the course (thirty-seven), the average speed was even more remarkable than that of 70¼ miles an hour averaged two months ago by Nazzaro in the Florio cup race in Italy, which had only four turns per circuit. The road was oiled and in excellent condition, the seven sharp turns being well banked. The course was rigidly policed by soldiers, and there was not the crowding upon it of spectators that took place in the recent Vanderbilt cup race on Long Island. In the latter race, despite the fact that nearly half the course was formed by the cement motor parkway, an average of but 64.39 miles an hour was made by the winning Locomobile.

This recent great road race has again caused the question to be raised whether or not such races are not a thing of the past. They have served a useful purpose in developing and improving the machines; but now there is little chance for improvement in cars for touring purposes, and huge racing machines are not in favor.

In view of the flights made by the Wright brothers with their aeroplanes, and especially of the long-distance flights across country made in France by Farman and Bleriot, we believe that the Automobile Club of America should take up the subject of mechanical flight, as it has done recently in the case of motor boating; and, if possible, that it should organize a long-distance aeroplane race, to be held next summer above Long Island. Prizes of sufficient amount should be offered to attract the foreign aviators and to make it worth the while of the many American inventors now working on the problem to complete machines for the event.

By making such a move, the club would give the cause of aviation in America an impulse that is greatly needed and that it seems impossible to impart in any other way. With the Wrights to show us, we have a great advantage over the foreigners, and there is no reason why we should not at once take the lead in every respect in this new form of locomotion.

As a result of the numerous cash prizes for aeroplane flights abroad—prizes which aggregate now over $250,000—there is a very great amount of experimenting going on there at the present time, and a new industry has been created. Nurtured by the French government and by the new prizes that are constantly being offered, this industry is rapidly growing and assuming a commercial aspect. All that is needed in order to duplicate this new industry in America is the interest and support of those moneyed men who, ten years ago, gave the initial impulse here to the development of the automobile.

That a race such as we suggest would be popular can be seen from the crowds that have traveled by special trains and automobiles from Paris to Le Mans to see Wilbur Wright fly, and also from the crowd that visited Morris Park race track on Election Day to witness the exhibition of the Aeronautic Society. The American public is waiting and eager to see flying machines in action, and no more popular event could be organized than a point-to-point race of aeroplanes.

Lightning striking the earth leaves traces which vary with the character of the soil and rocks. On compact rocks it often leaves a blackish incrustation, in sand hills it produces ful urites. These are nearly vertical channels, usually simple but sometimes branched, which are lined with vitrified silica. The outside of the tube is crumbly and usually blackened. Fulgurites are found in all countries, but most abundantly in regions of frequent thunderstorms. They are particularly abundant in some districts of the Pyrenees. The electrical origin of fulgurites has been put beyond question by the production of artificial fulgurites by the discharge of highly-charged condensers of great capacity through heaps of sand. Artificial fulgurites may also be produced by accident. In December, 1907, one of the wires of a triphase electrical circuit in Catalonia, Spain, broke a few miles from its terminus at Girone. The accident occurred at night and the passengers of a passing diligence were terrified by flames which appeared at many points of the ground. The two parts of the broken section of wire had fallen in a field of lucerne, where each part lay in contact with the ground over a length of about 45 paces. Throughout this distance and to four inches on each side of the wire the lucerne was killed. Scattered along this furrow in the vegetation were found many spongy, black, vitreous objects, resembling scoriæ. Some of these objects ended in polished balls and nearly all were hollowed out lengthwise and crumbled between the fingers. They were found most abundantly near the ends of the broken wire where some of the balls were two inches in diameter. A rough analysis of the soil showed that it was composed chiefly of sand with a little clay and limestone and traces of iron.

© 1908 SCIENTIFIC AMERICAN, INC

ENGINEERING.

It is probable that the four tunnels of the Pennsylvania Railroad Company between Manhattan and Long Island will adopt a track system consisting of treated red oak blocks, set in the concrete lining, on 20-inch centers. The blocks will be anchored to the concrete by expansion bolts; and the 100-pound rails, 60 feet in length, will be laid on 7-inch by 12-inch plates, 5/8 of an inch in thickness. The plates will be fastened to the blocks by two lag screws and the rails will be held down by clips and screw spikes.

The recent declaration of Prime Minister Asquith that in the future the British government will accept the two-power standard of naval strength as implying a preponderance by ten per cent over the two next strongest navies, has aroused no little interest in naval circles. If the "two next strongest navies" is intended to include that of the United States, which stands second in power to the British navy, the government is committed to a very large increase over its normal rate of construction, involving an additional outlay of from $25,000,000 to $30,000,000 annually.

A statement recently issued by the Pennsylvania Railroad Company shows that over $25,000,000 has been paid out by the employees' relief funds of the Pennsylvania Railroad system since their organization. Since July, 1889, on the lines west of Pittsburg, and since February, 1886, on the lines east of that city, over $15,000,000 has been paid to members who, because of illness or accidents, have been incapacitated for work. The remaining $10,250,000 has been paid to the families of members who have died.

Recognizing that the steel beams used in grillage foundations for tall buildings, because of their being concealed from examination, should be absolutely protected from corrosion, the firm of Milliken Brothers have been conducting experiments in the galvanizing of the beams after the shopwork upon them has been completed. By using the hot process in a large bath, they have succeeded in galvanizing not only I-beams, but a complete riveted-up steel column. Experimental grillages, containing galvanized steel, were broken open after they had been in the ground for six months, and the concrete was found to be in close and firm contact at every point.

The proposal to improve the efficiency of the steam-turbine propelled vessel by interposing electric generators and motors between the turbine and the propellers, is being made the target for much spirited criticism. Although it must be admitted that the higher speed of rotation which is necessary when a steam turbine drive is used causes some loss of efficiency, it has yet to be proved that the conversion of mechanical into electrical energy, and of the electrical energy back into mechanical energy, will not involve losses greater than those which it is sought to avoid.

The new Washington Street subway, Boston, which passes through the heart of the shopping district, is considered to be the most costly mile of underground railway in the world. Its construction and equipment has cost $10,000,000, or about $2,000 per lineal foot. The first section of Boston's modern system of rapid transit, consisting of subway tunnels, was opened about fourteen years ago. This was followed by the erection a few years later of the elevated road; and subsequently to that, the system was extended by the construction of the East Boston tunnel under the harbor. The opening of the Washington Street tunnel marks the latest, and one of the most important, extensions.

The next Congress will be asked to appropriate $11,341,730 for work in the navy yards during the coming year. Rear Admiral Holliday, Chief of the Bureau of Yards and Docks of the Navy, dwells, in his annual report, upon the pressing need for more drydocks, and for the construction of barracks at Philadelphia and Mare Island, capable of housing large numbers of men. The sum needed for the League Island navy yard is $721,500, and for the New York navy yard, $693,830, of which $300,000 is for work on the new granite and concrete drydock, which is to be one of the largest in the world. Admiral Holliday calls attention to the need for a drydock at Guantanamo, Cuba, to cost $2,250,000, and one at Pearl Harbor, Hawaii, to cost $2,000,000.

Speaking at the recent meeting of the Society of Naval Architects and Marine Engineers in New York city on the subject of the relation of the merchant marine to the navy, J. C. Butler, president of the Merchant Marine League, said: "To my mind, it is a disgrace to all of us that our huge battleship fleet, the pride of the nation, is convoyed and nursed around the world by a crowd of slow and shabby commercial hoboes, well named "tramps"—foreign colliers flying half a dozen foreign flags, cheaply built, with crazy hulls and rattletrap engines, and manned by the refuse of humanity. It is no wonder that these tramps have failed again and again to arrive on time, and to deliver their coal where it was expected and where it was required."

ELECTRICITY.

The use of electricity in construction work is largely increasing in this city. The current is utilized for the operation of electric hoists, pumps, and the like. The caisson work of a large new building is to be done with air compressors operated by electricity. Naturally, there is some apprehension of serious consequences, in case the current should fail while the work in the caisson is in progress, but special precautions will doubtless be taken to prevent any such accident.

A table giving statistics of single-phase electric railways in this country and in Europe has recently been prepared by the Westinghouse Electric and Manufacturing Company. According to this table, there are 28 roads (two still under construction) in America with line voltages ranging from 1,200 volts to 1,000 volts. Thirteen of the roads are equipped to use either direct-current or single-phase alternating current. The total number of locomotives used on these lines is 64. In Europe there are 34 single-phase roads using line voltages ranging from 500 to 20,000 volts, and they are equipped with 44 locomotives.

In order to determine whether electricity will convey any material particles with it when flowing through a conductor, Mr. J. Kinsky, writing in London Engineering, has made the following experiment: He took a cylinder of aluminium and placed it between two copper cylinders, subjecting the three cylinders axially to a considerable pressure. For an entire year current was passed through the series of cylinders, to see whether any particles of copper would be carried into the aluminium, or *vice versa*; 958 ampere hours were passed through the cylinders without the slightest evidence of any transfer of the metals.

Some interesting conclusions have been arrived at by the Swiss commission for studying electric operation of railways. According to this report, the maximum acceleration at starting should be 0.2 meter per second per second for express trains, 0.3 meter for passenger trains, and 0.1 meter for freight trains. The retardation should be 0.5 meter per second per second for passenger and express trains. The maximum speed of the electric train should be no greater than that now allowed, namely, 90 kilometers per hour (about 60 miles per hour) on trains with automatic brakes, and 45 kilometers per hour (about 30 miles per hour) on other trains.

An electric barometer has recently been invented, which depends for its operation upon the short-circuiting of a U-shaped carbon filament by means of a barometric mercury column. The filament dips into the top of the column, and as the atmospheric pressure increases, the mercury rises in the tube, cutting down the length of the exposed part of the filament, and thus reducing the resistance. As the mercury is also affected by temperature, a second filament and mercury column is provided. In this column the tube is sealed, so that the mercury will not be affected by atmospheric conditions. As the filament is more or less covered by the thermometric column, the resistance correspondingly varies, and this variation in resistance is introduced in the circuit of the barometric filament, so as to counteract the temperature variations in the latter.

A combined carbon-filament and mercury-vapor lamp is being introduced in Germany. The filament is inclosed in a U-shaped tube in which is a drop of mercury. The air in the tube is exhausted, and in its place an inert gas is introduced, to permit the conduction of heat from the filament to the mercury. The U-shaped tube is inclosed in a bulb similar to the ordinary incandescent electric lamp bulb. When the current is turned on, the carbon filament is immediately rendered incandescent and the mercury gradually vaporizes, increasing the light intensity to more than double the value of that of the filament. A maximum intensity is obtained in about five minutes. The lamp consumes from 1.5 to 1.6 watts per candle-power, and its life is from 600 to 1,000 hours. The light it yields is perfectly white, containing none of the blue-green rays of the ordinary mercury-vapor lamp.

The first popular application of electric heating for household use was in connection with the electric sadiron. Now there are a large number of heating apparatus in use, which are proving very successful for occasional use or in certain special circumstances, although not in the least competing with coal for ordinary heating purposes. In a paper presented at the recent meeting of the American Institute of Electrical Engineers by Mr. W. S. Hadaway, Jr., on electric heating, he estimates that one watt will heat one square foot of common radiator surface through 1.26 deg. F. The cost of a kilowatt-hour he places at 6.7 cents, and the cost of one steam-heating unit at 40 cents. On this basis, electric heating would be fifty times as expensive as steam heating. No doubt the time will come, however, when the current which is generated from heat at the power station can be reconverted into heat at the house with sufficient economy to compete with the coal furnace.

AERONAUTICAL AND AUTOMOBILE.

The Automobile Club of France has taken up the subject of aviation and announced $40,000 in prizes for aeroplane races next year. The French government has also appropriated $20,000 for aeronautics.

On November 18 Wilbur Wright, while teaching Capt. Gerardville how to operate the aeroplane, had an accident that might have resulted as seriously as did that experienced by his brother two months before, had it not been for the celerity and coolness of the famous American aviator. In the third flight of that day, the aeroplane had been aloft for 19 minutes, when the right propeller driving chain parted, and the propeller stopped. Mr. Wright shut off the motor immediately, and glided safely to earth. It is probable that the chain had become worn through constant rubbing in the guiding tube, until one of the rivets gave way.

The Aero Club of America is soliciting subscriptions from its members for the two gold medals which were voted recently to Wilbur and Orville Wright. These medals will be worth about $1,000 each, and will be commemorative of the flights executed both here and abroad this year. As Mr. Wilbur Wright has arranged to continue his experiments for some time in the South of France, it is probable that only his brother Orville will be able to attend the banquet of the Aero Club to be given the first part of next year, when the medals will be presented. The Wright brothers have also been awarded gold medals by the Aero Clubs of both France and Great Britain.

Dr. Alexander Graham Bell's Aerial Experiment Association is busily engaged conducting a test of Dr. Bell's tetrahedral-cell aeroplane, which he has constructed at his summer home near Baddeck, C. B. A year ago the late Lieut. Selfridge made a successful ascent in the former aeroplane of this type, which had 3,392 tetrahedral cells. The present aeroplane has 5,000 cells and a spread of 42.65 feet at the top and of 32.8 feet at the bottom. Its height is 9.84 feet, and its fore-and-aft length at the bottom is the same. There is an open space about 6 feet square in the center for the aviator and the motor. The machine will first be tested by towing as a kite above the Bras d'Or Lake by means of two powerful racing motor boats. The association is also experimenting at Hammondsport, N. Y., with a new aeroplane mounted upon two light canoes. It is believed that it will be possible to attain sufficient speed to rise from the water, which would be required of an aeroplane for naval use.

Two attempts have been made recently to beat the record for long-distance ballooning, but neither of them was successful. On the 15th ultimo a transcontinental race was to start from Los Angeles, but on account of adverse winds only one balloon, the "America," ascended. This came down a few hours later on the coast some miles south of Los Angeles, after having gone out a considerable distance over the ocean. The second balloon, the "United States," started the next day, and remained up one night in a vain attempt to get over the mountains. A descent was made the following day at Corona. On November 23 the "United States" ascended at 10 A. M., and succeeded in crossing the mountains and traveling a distance of 312 miles to within 15 miles of Ehrenburg, Arizona. The balloon passed high above San Jacinto Peak, which is a mountain more than 11,000 feet high. The trip was made at a speed of more than 50 miles an hour, and by it Capt. Mueller demonstrated that a transcontinental trip is a possibility. The second attempt at beating the long-distance record was made by the huge balloon owned by the London Daily Graphic. Carrying three men, this aerostat ascended from London on November 17, and descended in a gale near Novoalexanderovsk, Russia, the evening of the following day, after having traveled a distance of about 1,150 miles. The long-distance record of Count De la Vaulx (1,193 miles), therefore, was not broken.

The day before the Grand Prize race of the Automobile Club of America, at Savannah, a 198-mile race for small cars was run successfully. This race consisted of twenty circuits of a 9.8-mile course. There were 12 American cars, consisting of 1 Cameron, 3 Chalmers, 4 Maxwells, and 4 Buicks, while the Italians were represented by a Lancia and Isotta, and the French by an S. P. O. The S. P. O. dropped out of the race after completing four rounds, but the Italian machines ran fast and consistently, the Lancia finally winning in 3 hours, 43 minutes, and 33 seconds, an average rate of 52.6 miles an hour. Burman, in a Buick, was second some six minutes later, and a Chalmers-Detroit, driven by L. B. Lorimer, was third. A second Buick took fourth place, and Poole, on the Isotta, secured fifth. Two 2-cylinder Maxwells were six and seventh. Two other Maxwell runabouts were running in the eighth and ninth places when the race was called off. This race demonstrated very thoroughly the speed capabilities of the small car. It is remarkable that machines of one-fourth the power of the huge racers were able to maintain a speed but 12 miles an hour less than that maintained by the latter in a long-distance race.

© 1908 SCIENTIFIC AMERICAN, INC

WATER SUPPLY

DEVELOPMENT OF THE CROTON WATERSHED.

It was not until the middle of the last century that New York city undertook the construction of a system of water supply on a scale of any magnitude. After an investigation of the available watersheds, it was decided to develop a system of reservoirs in the valley of the Croton River, which flows into the Hudson from the east at a point about 35 miles distant from the City Hall. A dam 50 feet in height was built across the Croton River at a distance of about four and a half miles from its mouth, and the fresh-water lake about four miles in length thus formed, provided a supply of about two billion gallons of water. From the lake an aqueduct 8 feet 5½ inches high by 7 feet 5 inches wide and 33 miles long was built to carry the water to the city, where it was delivered to a distributing basin known as the Murray Hill reservoir, located on Fifth Avenue, between 40th and 42d Streets, which had a capacity of 24 million gallons. This work included the construction of a noble aqueduct across the Harlem River at Highbridge, which forms one of the most interesting engineering monuments in this city to-day. In its 1,450 feet of length are fifteen 80-foot and seven 50-foot arches, the under side of which is 100 feet above tide level. The new works were formally opened June 27, 1842. At that time the population of the city was only 350,000, and the consumption was 12 million gallons a day. As the aqueduct had a capacity of 90 million gallons, it must have looked to the good citizens of those days as though provision had been made for a future far removed. New York city, however, grew apace; and to meet the increased demands new reservoirs were built from time to time farther up the valley of the Croton and its tributaries. Before another half century had passed the water consumption had increased to a point where the authorities were confronted with the necessity for constructing another aqueduct. It was decided to build the new conduit of such a size that in conjunction with the old aqueduct it would be capable of delivering an amount of water about equal to the annual average daily flow of the Croton River. The New Aqueduct, as it was henceforth to be known, is built of brick. It is of a horseshoe section, measures 13 feet 6 inches in height by 13 feet 3 inches in width, and it is capable of delivering 300 million gallons of water daily. It was opened in June, 1890.

At this stage of development of the water supply the capacity of the aqueduct was, of course, greatly in excess of the capacity of the reservoirs in the Croton watershed; although these were continually increased in number to meet the growing demands of the city. About twenty years ago, however, it was realized that a large addition must be made to the existing reservoirs to meet the growth of population,



The line of the 1,000-foot spillway is seen on the far side of the lake. This panorama was taken with a Cirkut camera.

CROTON RESERVOIR FROM THE HILLS TO THE SOUTH OF THE DAM.



VIEW LOOKING DOWN THE VALLEY FROM THE SPILLWAY.



LOOKING UP THE SPILLWAY FROM THE NEW BED OF CROTON RIVER, BELOW THE DAM.



Width at base, 216 feet. Depth of base below bottom of reservoir, 140 feet. Height from bottom of foundation to crest, 297 feet. Water impounded, 30,000,000,000 gallons.

VIEW OF THE CROTON DAM AND LAKE FROM DOWNSTREAM.

© 1908 SCIENTIFIC AMERICAN, INC

which was advancing at a rapidly increasing rate. After a thorough investigation of the problem, it was decided to build an enormous dam of unprecedented height across the lower Croton valley, at a point about two miles from the mouth of the river, and create a large artificial lake about 20 miles in length, capable of impounding 30 billion gallons of water. Ground was broken in 1902, and after thirteen years of work, in which several years' delay was caused by a revision of the plans when the dam was partially completed, this great structure was opened (or, to speak more strictly, the gates were closed) and the dam began to fill on January 28, 1905.

The construction of the dam necessitated an enormous amount of excavation before rock bottom of a sufficiently solid character to support a structure of this size, and preclude the possibility of seepage below the dam, could be found. A huge trench was dug across the valley and carried down to a maximum depth of 131 feet below the original bed of the river, the width of the trench at the lowest point being about 250 feet. The work of excavating was commenced in 1892 and completed in 1896, and during this period 1,175,000 cubic yards of material was taken out. The dam as originally designed consisted of three portions. The first 400 feet on the southern side of the valley was to be an earth dam with a masonry core wall; then was to follow 650 feet of masonry which was to be continued upstream parallel with the side of the valley to form 1,000 feet of spillway. Subsequently, when the dam was approaching completion, it was decided to substitute solid masonry for the earth-and-core-wall section, and make the dam a homogeneous structure of masonry throughout its whole length. As finally constructed and shown in the accompanying engravings, the dam proper extends across the valley for a distance measured on its crest of 1,168 feet, until it is within about 200 feet of the southern side of the valley. Here it swings around and is continued up the valley for a further distance of 1,000 feet; finally turning in to a junction with the native rock of the hillside.

It is when we come to examine the cross section of the dam that its colossal proportions are manifest. Its foundations, at the widest part, are 216 feet in width, and the height from the foundation rock to crest is just under 100 yards, or, to be exact, 297 feet. The upstream face has a slight batter. The downstream face curves upwardly from the bottom width of 216 feet to a width at the top of 18 feet. The lowest point of the foundation is 131 feet below the bed of the river, and the top of the dam is 166 feet above the river bed. When the dam is full the depth of the water at the upstream face of the dam is 160 feet. The gap between the masonry dam proper and the side of the valley, forming the spillway channel discharge, is spanned by a handsome steel arch bridge, which serves to carry one branch of the system of roads which has been built around the reservoir, an important link in which is the driveway which extends across the valley along the crest of the dam. The overflow from the reservoir flows into a channel which has been blasted out between the masonry of the spillway and the rock of the hillside, and is conducted down to the old bed of the river below the dam over a series of roughly hewn steps in the rock, the water falling in a great cascade, 140 feet in height and issuing into the lower valley beneath the steel arch above referred to.



This huge conduit, 17 feet 6 inches high by 17 feet wide and 90 miles long, will convey 500,000,000 gallons of mountain water per day from the Catskills to New York City.

CONSTRUCTION OF THE CATSKILL AQUEDUCT.

At the point in the main dam where it begins to curve into the spillway is located a gate house, in which are three 48-inch pipes controlled by gates which, during the construction of the dam, were left open to permit the Croton River to flow through, and in future will be used to draw off the waters of the dam for purposes of inspection and cleaning.

It will readily be understood that the work of building the enormous mass of masonry represented by this mammoth structure was a slow and costly work. An excellent quality of rock was found a few miles up the valley, from which the quarried rock was brought down on cars and delivered along the whole site of the dam either by overhead cableways or by means of derricks distributed in large numbers over the whole face of the work. The greater part of the dam was built of large rock weighing up to five tons apiece, the interstices between which were filled in with smaller rock and cement laid by hand. The southerly end of the dam, which replaced the earthen core-wall dam first proposed, was built by a new method, in which the large masses of rock are dropped into a bed of liquid concrete, the concrete taking the place of the hand-laid smaller rock as used in constructing the earlier portion of the dam. The total amount of masonry in the finished dam is 850,000 cubic yards; and as the preliminary excavation of the trench involved taking out 750,000 cubic yards of earth and 425,000 cubic yards of rock, the magnitude of the work will be appreciated. As the masonry rose in the trench, the better quality of earth which had been excavated was brought back and filled in against the dam on both upstream and downstream faces, the downstream side being finished off in broad, easy slopes, and an attempt at landscape gardening being made by the erection of a fountain and the construction of winding roads. This last work, however, is somewhat crude, and it is to be hoped that at some future day the city will take this matter in hand, smooth down the unsightly banks of excavated material, plant the hillsides with trees and shrubbery, and render the approach to this truly magnificent structure worthy of its dignity and importance.

At high water level the crest of the old Croton dam, built in 1843, is buried 30 feet deep by the reservoir formed by the new dam; and at this point is located the principal gate house through which the water is led into the old and the new aqueducts. The creation of a lake that backs 20 miles up the Croton Valley



During construction the flow of the river is conducted across the site of the dam in two 8-foot steel pipes.

PREPARING THE FOUNDATIONS FOR THE ASHOKAN DAM, WHICH WILL IMPOUND 179,000,000,000 GALLONS OF WATER.

© 1908 SCIENTIFIC AMERICAN, INC

necessitated an entire relocation of the systems of roads and the construction of a large number of costly bridges to carry these roads over various arms of the lake. These crossings include a 124½-foot bridge; two spans of 217 feet; one of 310 feet, one of 396 feet, and

MAP OF CATSKILL AND CROTON WATERSHEDS, SHOWING THE NEW CATSKILL AQUEDUCT.

a handsome cantilever structure with a central span of 384 feet. The system of new roads extends for 50 miles around the lake. These supplemental works, together with the cost of the real estate, etc., brought the total cost of the whole scheme up to a round sum of about $12,000,000.

During the construction of the new Croton dam the city undertook the building of the Jerome Park reservoir, lying near the northerly limits of New York city, which is designed to act as a storage and distributing reservoir within the city limits. The reservoir as designed has an area of 239 acres and a depth of 26½ feet. The excavation involved the taking out of about 11 million cubic yards of material, most of it rock. It is divided by a wall that runs through it in a north and south direction; and the easterly half, which has been completed and entirely lined of concrete, has a maximum full capacity of 773,400,000 gallons.

Subsequently to the completion of the Croton dam a large reservoir known as Cross River, holding 10,308 million gallons, has been completed, and another, the Croton Falls reservoir, with a capacity of over 14 billion gallons, is under construction. When the last-named is completed there will be ten separate dams in the Croton watershed, with an aggregate capacity of 104,530 million gallons.

During last winter, from November 6 to March 15, all the reservoirs on the watershed were full and overflowing, and during this period over 80 billion gallons of water ran to waste over the spillway of the new Croton dam. With a view to storing a portion of such waters as would overflow in the future, it is proposed to build one more dam in the upper reaches of the watershed, which will have a capacity of 20 billion gallons and will be known as the Patterson reservoir.

From what has been said it will be seen that the limit of the storage capacity of the Croton watershed has about been reached. The daily average flow of the Croton River during the past forty years has been 402,330,000 gallons. The present daily consumption of water in New York city is about 325,000,000 gallons. Taking into consideration the increasing rate of growth of population of the city, and the fact that the annual increase in water consumption is at present at the rate of 15 million gallons daily per year, it can be seen that within a few years' time the consumption of the city will have exceeded the daily river flow and the capacity of 380 million gallons of the two aqueducts leading from Croton reservoir to New York. As the result of an exhaustive examination by various boards of engineers, it was found that the nearest available source for a new water supply was to be found in the region of the Catskill Mountains; and a gigantic scheme has been approved and is now being carried through for bringing a supply of fresh mountain water into New York city from the Catskills, to the extent of 500 million gallons daily, at a total cost of $161,000,000.

THE CATSKILL WATER SUPPLY.

In selecting a new source of water supply the engineers of the board realized that the conditions surrounding New York city were unusually perplexing. To the east the city is shut in by the Atlantic Ocean and to the west it is excluded by the laws of New Jersey from tapping any of the water sources of the State. A most excellent supply might have been drawn from the sources of the Housatonic River, had the district not been excluded from consideration because of its location in the State of Connecticut. Hence, the city has been driven by its geographical and legal restrictions to go far afield in its search, even to the regions of the Catskill Mountains. The disadvantages of distance, however, are compensated by the fact that the watersheds are sparsely inhabited, and that the water supply is not only abundant but is of excellent quality. By reference to the accompanying map, it will be seen that when the whole scheme has been developed water will be taken from four separate districts. The first of these, the Esopus Creek watershed, has an area of 255 square miles. Its waters will be impounded by the construction of a huge dam 220 feet in maximum height and 5,650 feet in length, which will be built across the valley of the Esopus at what is known as the Olive Bridge site. The dam will create what will be known as the Ashokan reservoir, which will be 2½ miles in width, with a full level capacity of 170 billion gallons, and will be capable of supplying the city with 250 million gallons of water a day.

The rate of growth of Greater New York is so rapid that it cannot be many decades before the watersheds of the Rondout, the Schoharie, and ultimately of the Catskill rivers will in turn be brought into service. The Rondout watershed covers 176 square miles, and would be capable of yielding 130 million gallons daily. This water will be stored in what will be known as the Napanoch reservoir, from which its waters will be led by an aqueduct into the main Catskill aqueduct a couple of miles below the Ashokan reservoir. Later, the Schoharie watershed will be brought into service by the construction of the Prattsville reservoir, its waters being brought into Esopus Creek by means of a tunnel through the divide. Lastly, the Catskill water will be impounded in several reservoirs located along that stream, and brought into the Ashokan reservoir by an aqueduct whose location is shown on the accompanying map. Altogether, when the whole scheme is completed, New York city will have at command over 700 million gallons daily water supply from the Catskill Mountain watershed in addition to the 375 million gallons daily already available in the Croton watershed.

The Ashokan dam, like the Croton dam above described, will take rank as one of the greatest structures of its kind in existence. It will be built partly of solid masonry and partly of earth. The masonry portion, which will extend for about 1,000 feet and occupy the center of the dam, will be built of the general cross section shown in the accompanying engraving. The width of the base will, of course, vary with the depth of the foundations; but at the center it will be not far from 200 feet. Its height taken at the same point will be 220 feet. The earth-and-corewall portions of the dam will extend from the masonry middle section to a junction with the valley on one side, and some high ground on the other. The total length of the dam will be 5,650 feet. In addition to the dam there will be a series of dikes which will be built across depressions in the country and serve to hold the water at the desired level. Beyond the dikes will be a large waste weir. The dikes will constitute a very important work, for together with the waste weir they will have a total length of 3.8 miles. One of our illustrations shows the preliminary excavation work for the dam and the means adopted for by-passing the flow of the Esopus Creek during construction, which is being done by means of two 8-foot steel pipes which will be sufficient to accommodate the creek at its ordinary level. Subsequently, as the excavation is carried further down, the water will be diverted through a channel formed along the side of the valley. Ultimately, during the erection of the masonry of the dam, the water will flow through a tunnel, which will be left open for that purpose and closed when the dam is completed.

From the dam the water will flow by gravity through a huge steel-and-concrete aqueduct 17 feet in the clear

(*Continued on page 414.*)



1. Cross-section of masonry portion of dam. 2. Cross-section of earth-and-corewall dam. 3. Horizontal section through an expansion joint in dam.

PLAN AND DETAILS OF THE ASHOKAN RESERVOIR AND DAM.



DIAGRAM SHOWING ELEVATION AND CAPACITY OF CROTON RESERVOIRS.



PLAN OF THE CROTON WATERSHED, SHOWING LOCATION OF THE RESERVOIRS.

© 1908 SCIENTIFIC AMERICAN, INC

THE CITY'S GIANT BRIDGES

Although the famous Brooklyn suspension bridge was built a quarter of a century ago, and, therefore, cannot legitimately be included in a review of the engineering work of the past decade, we have given it a place among our illustrations, first because of its great historical interest, and secondly because it forms such an important member of the quartette of giant bridges which span the broad waters of the East River, and afford the principal means of communication between New York and Brooklyn.

The wire suspension bridge is essentially an American production; for although chain suspension bridges, in which the main supporting members consisted of flat iron bars linked together by pins, had been built in some numbers in England and on the Continent, the use of wire cables is one of the original and distinguishing characteristics of American long-span bridges. When Col. Roebling first promulgated his plans for spanning the broad expanse of the East River with a wire cable suspension bridge of the enormous span of 1,595 feet, the scheme was regarded with no little apprehension. The longest existing bridges were of less than 1,000 feet span; and it was considered that there were insufficient reliable data available to guarantee an advance to proportions of the unusual magnitude proposed. Great honor, therefore, is due to Mr. Roebling for the courage with which he staked his reputation upon the venture, and the indomitable pluck with which he and his associates carried it through to successful completion. The foundations for the towers were prepared by sinking two huge timber caissons to the rock underlying the river mud and sand. Upon these were erected two massive masonry towers which were carried up to an extreme height of 272 feet above the river. Meanwhile the anchorages, consisting each of a mass of solid masonry, were constructed on either shore, at a distance of 930 feet from the towers, and deep within this masonry were imbedded the huge anchor plates and anchor bars to which the wire cables were attached. Originally it was planned to make these cables of iron wire; but by the time the bridge was ready for their erection, the advance in the manufacture of steel had been such that it was found possible to use steel in place of iron, and thus secure much stronger cables without any increase of weight. It is to the wisdom shown in the adoption of this stronger material that the city is indebted for the ability shown by the bridge, in the later years of its life, to carry loads greatly in excess of those for which it was originally designed. There is no foundation for the popular belief that the bridge is to-day "greatly overloaded." As a matter of fact, the steel wire cables are perfectly well able to carry their present burden. The so-called weakness of the bridge is due to the comparative weakness of the floor system, and particularly of the stiffening trusses, which on several occasions have been buckled or broken. Of late years, however, the bridge has been subjected to careful and continued scrutiny by competent engineers; and, so long as this is done, no fears need be entertained for the safety of the structure. Plans have been prepared by the Bridge Department, moreover, for the reconstruction and stiffening of the bridge, which include the erection of deeper and stronger stiffening trusses and a complete rebuilding of the floor system. This work will be undertaken as soon as the adjoining Manhattan Bridge has been completed, and when it is completed, the bridge will be good for many centuries of useful service, and will last just as long as it is safeguarded against rusting and decay by frequent painting and careful all-round maintenance.

THE WILLIAMSBURG SUSPENSION BRIDGE.

In the closing years of the last century the city undertook the construction of another wire cable suspension bridge. The location of the crossing was laid from Delancey Street, Manhattan, to Broadway, in Brooklyn. The main span is slightly longer than that of the Brooklyn Bridge, the clear width from tower to tower being 1,600 feet. The shore spans, however, are only 596½ feet, as against 930 feet, which is the length of the shore spans of the older structure. In point of weight and carrying capacity, the Williamsburg Bridge, as it is called, is a vastly greater structure; for whereas the floor of the Brooklyn Bridge is only 80 feet wide, with provision for two elevated tracks, two trolley tracks, two 18-foot roadways with two trolley tracks upon them, and a footwalk, the Williamsburg Bridge is 120 feet wide and carries two elevated tracks, four trolley tracks, two 18-foot passenger footwalks between the trusses and two 20-foot roadways on the outside of the trusses, carried on cantilever extensions of the floor beams. The lack of stiffness of the floor of the Brooklyn Bridge is due to the light construction and shallow depth of the trusses, two of which are 8 feet 9 inches and four 17 feet in depth. This was remedied in the Williamsburg Bridge by the provision of two unusually heavy trusses, each 40 feet in depth, extending continuously from anchorage to anchorage. The steel towers are erected upon heavy masonry piers beneath which are huge caissons which were sunk to the underlying bedrock. The steel towers are carried to a total height of 335 feet above the river. The four cables, each of which is 18¾ inches in diameter, are connected at their ends to heavy cast steel shoes which are pinned to a series of steel anchorage eye-bars imbedded in the masonry of the anchorages. The steel used in constructing these cables is of unusually high tensile strength, the best specimens showing a breaking strength, in some cases, as high as 210,000 pounds to the square inch. The cables for supporting the roadway are attached to the main cables by means of heavy cast-iron saddles, and at their lower ends they are looped around cast-steel shoes, from which the floor beams of the bridge are hung by four heavy steel bolts. It will be noticed from our illustration that there are no suspender cables for the shore spans of the bridge, the main cables serving to carry the weight of the central 1,600-foot spans only. The shore spans consist of extensions of the stiffening trusses; and the load of each of these spans is carried by the tower, the anchorage, and a steel pier located at the center of the truss. The total cost of the bridge, including the approaches and purchase of real estate, was about $22,000,000.



This view shows the cables in course of construction. One end of the wire from a reel is passed around the sheave shown near left-hand corner of engraving, which is drawn across the bridge, thus stringing two lengths of wire at each journey.

ONE OF THE MANHATTAN BRIDGE ANCHORAGES.

THE MANHATTAN SUSPENSION BRIDGE.

The third of the great crossings of the East River, known as the Manhattan Bridge, which is located about a quarter of a mile to the east of the old Brooklyn Bridge, is now in process of erection, and will probably be opened in 1909-10. Originally designed as a stiffened chain-cable bridge, the plans were subsequently changed by the substitution of wire for chain cables. Upon its completion the bridge, in respect of its carrying capacity, will be the largest suspension bridge in existence, provision having been made for eight railroad and surface tracks, a 35-foot roadway, and two passenger footwalks, each 11 feet in width.

No small part of the cost of building a bridge of this character is due to the difficult nature of the foundations. The caissons for the Williamsburg Bridge were four in number, there being two for each tower; an arrangement which was necessitated by the rather steep slope of the underlying rock at the site of the towers on each side of the river. The borings for the Manhattan Bridge piers showed the surface of the underlying rock to be fairly level, and hence it was decided to construct a single huge caisson for the foundations of each tower. The dimensions of the caissons were necessarily large. They measured 78 feet in the direction of the axis of the bridge by 144 feet transversely to the axis. The caisson proper on the Brooklyn side was 55 feet 6 inches in depth and above this was built a temporary cofferdam, which was erected to prevent the water from flowing into the work during the process of sinking. The total depth of this huge box, when it finally reached bedrock, was about 100 feet. The walls of the caisson were built of two layers of 12 x 12-inch timbers, the outer one laid horizontally, and the inner vertically; while on the outside of this was a double layer of 2-inch planking, the inner one laid diagonally, and the other vertically. Six feet from the bottom cutting edge, which was shod with steel, there was built over the whole caisson a solid roof of timber 2 feet 9 inches in thickness stiffened by heavy trusses. The space beneath this watertight roof, known as the working chamber, was divided into three longitudinal sections, and in this chamber the excavation was done by a large army of "ground hogs," as the men who perform the work of excavation are called. From the working chamber there extended to the surface of the cofferdam nine steel shafts for material, and one elevator shaft. The material at the river bottom was found to be almost pure sand; and it proved possible to blow out the excavated material by means of compressed air which was forced into the working caisson for the workmen. This was done by means of fourteen 4-inch wrought-iron pipes, which extended from the roof of the working chamber to the surface. At the bottom of each of the 4-inch pipes was a length of hose, which reached from the roof of



Each cable consists of 37 strands in each of which is 250 wires.

THE CONNECTION OF THE WIRE STRANDS TO THE ANCHOR BARS.

© 1908 SCIENTIFIC AMERICAN, INC



Copyright 1908 by George P. Hall & Son.

Length of main span, 1,595½ feet; side spans, 930 feet. Total length, including approaches, 6,016 feet. Width of bridge, 85 feet. Height of towers, 272 feet above the water. Diameter of cables, 15¾ inches. Capacity: Two rapid transit tracks; two surface tracks on two 18-foot roadways; one 15-foot footwalk. Total cost, $16,000,000.

BROOKLYN BRIDGE. CONSTRUCTION COMMENCED 1870. OPENED 1883.



Length of main span, 1,600 feet. Side spans, 596½ feet. Total length, including approaches, 7,279 feet. Width, 114 feet. Height of towers above high water, 335 feet. Diameter of cables, 18¾ inches. Capacity: Two rapid transit tracks; four surface tracks; two 20-foot roadways; two 17½-foot footwalks. Total cost, $22,000,000.

WILLIAMSBURG BRIDGE. CONSTRUCTION COMMENCED 1896. OPENED 1903.

© 1908 SCIENTIFIC AMERICAN, INC



Two channel spans, 1,182 feet and 984 feet; one island span, 630 feet; two anchor spans, 469½ feet and 459 feet. Total length, including approaches, 8,600 feet. Maximum depth of trusses, 185 feet. Width of bridge, 88 feet. Capacity as planned: Four rapid transit tracks; four surface tracks; one 34-foot roadway; two 14-foot footwalks. Because this bridge is overstressed it is under consideration to remove all or part of the rapid transit tracks. Cost $20,000,000.

QUEENSBOROUGH (BLACKWELL'S ISLAND) BRIDGE. CONSTRUCTION BEGUN 1901. TO BE OPENED 1909.



Length of main span, 1,470 feet. Side spans, 725 feet. Total length, including approaches, 6,855 feet. Width, 120 feet. Height of towers above high water, 322 feet. Diameter of cables, 21¼ inches. Capacity: Four rapid transit tracks; four surface tracks; one 35-foot roadway; two 11-foot footwalks. Total cost, $26,000,000.

MANHATTAN BRIDGE. CONSTRUCTION COMMENCED 1901. TO BE OPENED 1909-1910.

© 1908 SCIENTIFIC AMERICAN, INC

the working chamber to the bottom of the excavation. A 4-inch water pipe also passed through the caissons, and supplied water at 100 pounds pressure to six jets. One of these jets was directed at the sand around the bottom of each blow-pipe, and served to loosen it so thoroughly that the air pressure in the caisson proved sufficient to blow the sand up through the pipe and out over the edge of the caisson. When the caisson reached solid rock, the whole interior of the working chamber was filled in with tightly rammed concrete, the interior of the caissons above the roof being also filled with the same material, thus providing a solid concrete and timber mass from the rock below the bed of the river to the top of the caisson, which stands at a level of 37 feet below mean high water. Above the caissons was built a solid masonry pier whose coping is 23 feet above mean high water, the total depth from coping to the caissons being 60 feet. The construction of the foundation and piers on the Manhattan side was practically identical, the only difference in dimensions being that due to the difference in depth to rock bottom.

Upon the top of each of the masonry piers were built four massive steel footings, and upon these were erected the plate-steel legs or columns of the steel towers. Each tower consists of four apparently slender but actually exceedingly heavy and stiff columns that rise 322 feet above the water level. Each pair of columns is braced together by a truss system, which extends continuously from base to top, except where it is omitted in two panels to provide for the passage of the lines of railway track. Each pair of columns, as thus connected, is braced together by transverse trusses, one below the floor of the bridge, another at the level of the upper deck and a third at the top of the tower.

In previous suspension bridges it was customary to cradle the main cables, but in the Manhattan Bridge the cables lie in the same vertical planes as the respective legs of the towers over which they pass. In respect of its carrying capacity, the Manhattan Bridge is the largest of the four great bridges across the East River. The suspended roadways are carried on two decks. Upon the lower deck provision is made for four surface tracks, a 35-foot roadway, and two 11-foot passenger walks; while upon the upper deck there will be four elevated railway tracks. To carry so great a load, the dimensions of the cables and anchorages are necessarily very large. The anchorages measure 175 feet in width by 225 feet in length, and the cables reach the unprecedented diameter of 21¼ inches, as compared with the diameter of 18¾ inches on the Williamsburg Bridge and 15¾ inches on the Brooklyn Bridge. The necessary stiffness will be given to the suspended roadway by four heavy riveted nickel-steel trusses, lying in the planes of the four cables and suspended from them.

For the construction of the cables four temporary cables, each consisting of four 1¾-inch diameter steel ropes, were strung from anchorage to anchorage over the towers. Upon them were laid four working platforms for the accommodation of the workmen. The stringing of the wires in each cable is accomplished by means of two traveling sheaves, carried on opposite legs of an endless steel rope reaching from anchorage to anchorage. Each sheave consists of a 3-foot grooved wheel, attached to the hauling rope by brackets. The hauling rope runs on heavy rollers supported on uprights on the temporary foot-bridges. The wire is delivered to the bridge on enormous reels weighing 3 tons each, half of them being placed on each anchorage. The end of the wire from a reel at each end of the bridge is put over the hauling sheave at that end and fastened to the anchorage, and each hauling rope is driven by a 50-horse-power, 220-volt Crocker-Wheeler form W motor. The hauling machinery is then started, and, as the sheaves move across the bridge, they unwind one wire from each reel, and two wires are thus strung by each sheave every time it makes the trip across the bridge. There are 256 wires in each strand, and as the strands are completed they are lifted from the temporary saddles in which they rest and placed in the permanent saddle. Each cable contains 37 strands of 256 wires each, so that there is a total of 9,472 wires in each cable. The total length of single wire in all four cables will be 23,100 miles. The wire has a breaking strength of 215,000 pounds to the square inch. The weight of the four cables in their completed condition will be 8,600 tons. The side spans of the bridge are 725 feet and the central span is 1,470 feet in length. When the bridge is completed the total weight of steel in the structure will be 42,000 tons.

THE QUEENSBOROUGH CANTILEVER BRIDGE.

The Queensborough cantilever bridge, formerly known as the Blackwell's Island Bridge, is the latest of the four great bridges across the East River. Commencing from the Manhattan shore, the dimensions and positions of the successive spans of the bridge are as follows: First there is an anchor span 469 feet long; then a channel span 1,182 feet long, followed by what is known as the Island span crossing Blackwell's Island, which is 630 feet long. Then comes a 984-foot span over the east channel of the river, and a 459-foot anchor span extending over the Long Island shore. The total length of the bridge, including the approaches, is 8,600 feet. The maximum depth of the trusses at the towers is 185 feet, and the extreme width of the bridge is 88 feet. As originally planned, the bridge was designed to carry a maximum congested live loading of 12,600 pounds per lineal foot, on four surface trolley tracks, two elevated railway tracks, a roadway, and two footwalks. Following a change of administration and engineers, it was decided to add two additional elevated railroad tracks on the upper deck of the structure, and a heavier congested loading was adopted of 16,000 pounds to the lineal foot. When the bridge was nearing completion, the engineering world was startled by the fall of that other great cantilever structure, the Quebec Bridge; and it was natural that considerable anxiety should be aroused regarding the Queensborough Bridge, since it was not only designed on the same general principles, but was a heavier structure in itself and was to be subjected to a heavier load than the bridge that went down. Two separate investigations of the strength of the bridge were made for the Bridge Department; and in both cases it was found that not only was the bridge over weight, but that if it were loaded according to the requirements of the specifications the stresses in some of the members would exceed the specified stresses by from 25 to 47 per cent. One of the consulting engineers recommends the taking of considerable dead load from the bridge and the removal of two of the elevated railway tracks. The other report advises the removal of all elevated tracks.

The fall of the Quebec Bridge and the conditions existing in the Queensborough Bridge cannot fail to raise a doubt in the minds of engineers as to the suitability of the cantilever system to the construction of heavily-loaded bridges of over 1,000 feet in length of span; and this, in spite of the fact that troubles in both cases were due chiefly to faulty design. The Queensborough Bridge is an enormously heavy structure, the weight of the whole mass from abutment to abutment of the cantilevers being 52,000 tons. The 630-foot span across the Island alone weighs 10,400 tons, or 16½ tons to the lineal foot. The trusses are built partly of a special nickel steel and partly of the ordinary commercial structural steel, the latter being used generally for the compression members and floor system and nickel steel for the eye-bars or tension members. In the structural steel the specifications called for an elastic limit of 28,000 pounds, and an ultimate strength of 56,000 pounds. The requirement of the nickel-steel eye-bars are an elastic limit of 48,000 pounds and an ultimate strength of 85,000 pounds, from which it will be seen that the nickel-steel bars are from 40 to 50 per cent stronger than ordinary structural bars of the same weight.

The erection of the bridge was done by the overhang method. First the anchor arms on the Manhattan and Long Island shores and the span across the island were erected on steel falsework. Then the four river arms of the cantilevers were built out by overhang to a junction in midstream by means of two massive travelers each 120 feet in height. This traveler was in itself a huge and costly affair weighing 500 tons and capable of handling a load of 70 tons. It is probable that the bridge will be opened during the year 1909. In closing our article on the long-span bridges of New York, mention should be made of the fact that the plans have been drawn for a massive 1,000-foot steel arch bridge which is to carry a four-track railroad across the East River at Hell Gate, and form part of an important link connecting tracks of the New Haven Railway with those of the Pennsylvania Railway on Long Island.

In a remarkable paper read at the meeting of the American Philosophical Society in Philadelphia, Dr. Alexis Carrel of the Rockefeller Institute showed how the kneejoint of a dead man has replaced the injured joint of a living person; how the arteries of husband and wife have been successfully joined, so that the wife might endure the shock of a surgical operation; how an infant's blood has been revitalized by the blood of its parent; how a human artery and jugular vein have been interchanged and are fulfilling each the other's function; how the kidneys of one cat were substituted for the corresponding organs of another, and how a living fox terrier now frisks about upon the leg of a dead companion. "In my experiments to preserve arteries," states Dr. Carrel, "I found that desiccation would not do, but produced a state of absolute death. Then I put the arteries in refrigerators and kept them inclosed in hermetically sealed tubes, at a temperature a little above freezing. I found that an artery could be kept alive for sixty days and substituted for the artery of a living animal." Clearly, the day is not far off when the perfect organs of a man who in life had been free from disease may be kept in cold storage after his death and used to replace diseased organs in living men.

TALL BUILDINGS OF NEW YORK

Although New York city was not the first to possess a mammoth office building of the modern "skyscraper" type, the growth of such buildings in number and size during the past few years has been so rapid as to render lower New York distinctively a city of towers. To the wonderful skyward growth of this city, several causes have contributed. Chief among these, and closely related, are the circumscribed limits of the site on which the city is built, and the high cost of the land. The high price of real estate and the restricted area of desirable sites, it is true, have served to promote the construction of lofty buildings in other cities besides New York; but nowhere have these proved such powerful and impelling motives as here. The desire on the part of large business interests to be located as closely as possible to the financial center, moreover, has helped to produce that huge pile of lofty buildings which makes lower New York, in the neighborhood of Wall Street, look from a distance as though it were a city built upon a hill. Below Chambers Street the prices of real estate will run from $30 to $40 per square foot, near the water, to $200 and $300 per square foot in the Wall Street district. The highest price ever realized was that paid for a small corner plot at the southeast corner of Wall Street and Broadway, which recently sold for $700,000 or at the rate of $600 per square foot. This is the highest price ever paid for real estate in any city of the world. It is not at all unusual for the cost of the site of a building in this city to exceed the cost of the structure itself. This was the case with the Fuller Building, popularly known as the Flatiron Building, whose triangular site cost $2,500,000. Where such vast sums are paid for the building site, it becomes necessary to add story to story until sufficient rentable floor space has been secured to guarantee a reasonable profit upon the cost both of the site and the building.

The development of the lofty office building is one of those modern engineering achievements which were rendered possible by the introduction of Bessemer steel. The limit of height for an ordinary brick or stone building of the older kind, is reached when the thickness of the lower walls becomes such as to seriously encroach on the usable floor space of the building. The tallest structures of this kind have stopped at a height of twelve to fourteen stories; this last being the height of the Singer Building, before its recent reconstruction. The walls of this structure in the lower stories are nearly three feet in thickness. With the introduction of steel columns, girders, and stringers in building construction, it became possible to transfer the loads of each story of a building directly to vertical columns, by which they were carried direct to the foundations; and the intermediate spaces between the columns required only a sufficient thickness of wall to serve the purposes of inclosure. The introduction of steel thus served the double advantage of reducing the thickness and weight of the walls and of enabling the loads to be concentrated on a specified number of vertical members, whose supporting power it was possible accurately to determine. Not only was a great reduction made in the weight, but there was a corresponding increase in the elements of safety and durability. The stresses in a tall building can be calculated with accuracy; and by introducing the proper amount of wind bracing, these structures may be made absolutely secure against being overthrown by storm, and reasonably secure against earthquake. Furthermore, the skeleton steel building is a form of construction that lends itself admirably to fireproofing; and, if the columns and beams be thoroughly protected by good terra cotta or concrete, and metal be used for the construction of doors, window sashes, frames, and, as far as possible, for the furniture, a modern office building may be rendered practically proof against fire—so far proof, indeed, that if a fire starts among the contents of an office, it will be localized for want of any combustible material upon which to seize in the building itself. The San Francisco fire proved that, where the most modern methods of fireproofing were used, a tall building could go through even such a fierce conflagration as that, and yet remain so far intact as to be capable of speedy repair. The question has often been asked, particularly since the San Francisco disaster, as to how the tall buildings in this city would be affected by earthquake shock. Judging from the results at San Francisco, they would pass through an earthquake with surprisingly little damage. This is explained by the fact that the shock is taken care of by the elastic properties of the steel frame; and where the walls and panel work have been attached to the frame by the most approved methods, the worst that can happen is a slight cracking of the masonry.

The steady increase in height of tall buildings has raised the question in the minds of many people as to

© 1908 SCIENTIFIC AMERICAN, INC

how high it would be possible to go in safety. In an investigation of the problem made by Mr. O. F. Semsch, who was responsible for the design of the steel work of the Singer tower, it was found that under the restrictions of the building code as to load on foundations, it would be possible to put up a structure 2,000 feet in height on a lot 200 feet square. The building would weigh over 500,000 tons, and its weight would be so great that, in spite of the vast height, there would be a factor of safety of 8 against overturning by wind pressure, even in a stiff gale. If the tower were constructed and equipped similarly to the Singer Building, the cost would be $60,000,000. As a matter of fact, the limit upon the height of tall buildings is to be found neither in the inherent weakness of the structure, nor in the danger of upsetting in a gale of wind. The limit is determined by a clause in the Building Code of the city of New York, which says that the maximum pressure on the rock below the foundations, if caisson foundations are used, must not exceed 15 tons per square foot. As a matter of fact, the practical limitations upon height would come from the increasing thickness of the lower walls; for the Building Code states that the walls of the steel and masonry type of building must be 12 inches thick for the uppermost 75 feet of their height, and must be increased 4 inches in thickness for every 60 feet below that. Structurally considered, this provision of the Building Code is unnecessary, since the weight of the walls at each story is carried directly upon the steel framework at the base of that story; and there is, therefore, no structural necessity for making the walls at the base of a 20-story building more than 12 to 18 inches thick.

There is a movement among our architects to limit the height of buildings in such a way as to permit the erection of tall buildings only under restrictions which will insure that they do not unduly exclude the light from the streets or from one another. This desirable object is to be secured by a law making it necessary, after a building has been run up so many stories on the building line, to step back a specified distance before erecting the next series of stories, the offsetting being repeated as often as is necessary to admit the desired amount of light to the adjoining street. The center of the building plot is to be reserved for the main, tower-like, portion of the building, which may be carried up as high as the owner may wish. The question of the architectural treatment of tall buildings is one of the most difficult problems that has ever presented itself to the profession. In the earlier structures the architects made the mistake of trying to mitigate the appearance of height by introducing heavy horizontal elements in the way of cornices and offsets; but the results were not pleasing architecturally. The modern office building is first and last a tower, and as a tower it should be treated. Those architects who have recognized this fact, and have emphasized the vertical as against the horizontal lines, have produced the most successful buildings. Our illustrations include two buildings, the Singer and the Metropolitan Life, whose capacity has recently been enlarged by the erection of additions, in the form of towers of unprecedented proportions.

Although the Singer tower measures only 65 feet on each side, the top of the dome stands 612 feet above the sidewalk. It is erected upon thirty-four caissons sunk to bedrock, which, in some cases, lay 90 feet below the street level. From an engineering point of view, the most interesting feature is the method of framing the steel skeleton to enable it to resist the heavy wind pressure, when the thunder squalls of summer and the heavy gales of winter sweep over Manhattan. It was impossible to run continuous diagonal truss members across the building from wall to wall, because such an arrangement would have encroached upon the window space. Therefore it was decided to consider the structure as being built up of four square corner towers, and a central tower forming the elevator well, with wind bracing running continuously through each wall of each tower from top to bottom, the five towers being tied together in lateral planes at the various floors. The corner towers are 12 feet square from center to center of columns. This arrangement provides an open space 36 feet in width, free from diagonal bracing, extending down the center of each face of the building, and these faces are occupied by large bays filled in with glass, as shown in the accompanying illustration. This method of bracing involved high stresses in the chords of the trusses which, in this case, are the vertical columns of the tower, and the latter are of unusually heavy construction. The wind pressure at 30 pounds per square foot exercises a total overturning moment on the whole tower of 128,000 foot tons. Although the total weight of the tower is 23,000 tons, the wind pressure would have a tendency to lift the windward side of the building, the total uplift on a single column amounting, for maximum wind pressure, to 470 tons. To provide against this the columns are anchored to the caissons, and the margin of safety against lifting is in no case less than 50 tons to the column. The effect of the wind pressure on the leeward side of the building also affords some interesting figures. Thus, the total dead load at the foot of one of the leeward columns is 289.2 tons, which represents the weight of the steel work and masonry. The live load, which includes furniture, fittings, and the maximum crowd of occupants, totals, at the foot of this column, 131.6 tons. The downward pressure on the leeward side of the building due to wind pressure is 758.8 tons, and this, added to the dead and live loads, brings the total load on these columns up to 1,179.6 tons. The architectural treatment of the building is decidedly pleasing, and Mr. Ernest Flagg, the architect, is to be congratulated in having done so well in a field for which there was no precedent.



Showing the diagonal wind bracing at each corner. The tower is 612 feet high; its total weight is 23,000 tons.

CONSTRUCTION OF THE SINGER TOWER.

Rises 363 feet above a triangular base. There are 23 stories in the tower. Total floor space, 117,000 square feet.
Copyrighted 1905 by Irving Underhill.

THE TIMES BUILDING

Popularly known as the "Flatiron." This building, 310 feet high, stands on a triangular base measuring 215 feet on Broadway, 198 feet on Fifth Avenue, and 86 feet on 22d Street. The site cost $2,500,000.
Copyrighted 1903 by Irving Underhill.

THE FULLER BUILDING.

© 1908 SCIENTIFIC AMERICAN, INC

Copyright 1908 by Munn & Co.

Tower measures 75 feet by 85 feet, extends 700 feet above sidewalk, contains 50 stories, includes 8,100 tons of steel in its framework, and weighs 38,022 tons. In the building and tower combined there are over 25 acres of floor space.

THE METROPOLITAN LIFE TOWER, 700 FEET IN HEIGHT; THE LOFTIEST BUILDING IN THE WORLD.

© 1908 SCIENTIFIC AMERICAN, INC

The City Investing Building, 485 feet high, contains 31 rentable stories. It covers a lot 124 feet by 308 feet, and its total floor area is 670,000 feet.



One of the first steel-and-masonry buildings; erected 1897. Height, 317 feet. Washington was a frequent worshiper in the old church.

THE CITY INVESTING BUILDING AND THE SINGER TOWER.

ST. PAUL BUILDING AND THE OLD ST. PAUL S CHURCH.

The combination of red brick and buff stone with the bronze and copper finish of the windows and dome is decidedly pleasing, and the disposition of the windows throughout the vast reach of forty-two stories proves that it is possible to get away from that pepper-box appearance which is one of the unsightly features of the façade of the average tall building.

Unquestionably the most striking of the lofty buildings of New York city is the stupendous steel-and-marble campanile which is being erected at the northwest corner of the Metropolitan Life Insurance Company Building, between Fourth and Madison Avenues and Twenty-third and Twenty-fourth Streets. The present building, which is ten stories in height, has a frontage of 200 feet by 425 feet. The tower has a base measurement of 75 feet by 85 feet, and extends a clear 700 feet above the sidewalk. The whole building is treated in the pure early Italian Renaissance style, which has been used also in the tower; and both tower and building are finished in Tuckahoe marble.

It takes but a glance at our illustration of this stupendous marble shaft to feel assured that when it is completed, it will be an object of decided architectural grandeur and beauty. Its height is so great that fully one-half of its bulk will rise absolutely clear of the cornice lines of New York city's 20-story buildings. The highest point of the tower will overtop the highest point of the Montclair Hills in New Jersey by about 30 feet; and when the shadows of evening are falling upon the street below, the summit of the tower will be crimsoned with the rays of the sun that has already set behind the Orange Mountains. The most lofty rentable offices will be those of the forty-first story, whose floor will be 526 feet above the sidewalk. The windows of these offices will be at the same elevation as the lookout windows at the top of the Washington Monument. The table of dimensions and weights as obtained from the architects, Messrs. M. Lebrun & Sons, runs into large figures. In the tower there will be fifty stories, and in the tower and the main building combined there will be a total floor space of 25 acres. The steel framework of the tower alone weighs about 8,100 tons, and the weight of the steel work, masonry, etc., combined is 38,022 tons. When the building is occupied, the estimated live load will be 5,591 tons, bringing up the total weight of the whole building to 43,613 tons.

We have seen that in the Singer tower the wind stresses are resisted by means of continuous trusses extending throughout the whole height of the building. In the Metropolitan tower the frame is stiffened against distortion by means of heavy knee braces at the intersection of the vertical columns and the horizontal floor beams. The stresses due to wind pressure reach a very high figure, and call for a large increase in the sections of the columns, etc., to provide for them. In the principal columns on the leeward side of the tower, the load due to dead and live loads combined is 7,500,000 pounds; and the load due to wind pressure is 2,900,000 pounds, which brings the total load up to 10,400,000 pounds. Similarly, the corresponding columns on the windward side are relieved of pressure, the maximum load being reduced from 7,500,000 pounds to 4,600,000. This shows that even under the heaviest storms that may blow against it, there will at no time be any tendency on the part of the building to turn over on its foundations.

Limitations of space prevent our pursuing this subject any further than to give some particulars of a few of the most recent and notable buildings. The Metropolitan Building just described is the largest single office building in the world, containing, as we have seen, over 25 acres of floor space. The next to that is the City Investing Building, with thirty-three stories and a total height of 485 feet. The total floor space is 670,000 square feet, and it can accommodate 6,000 people. The Terminal Building is in two sections, on of which has 26,000 square feet of available area on each floor, and the other 18,000 square feet. This huge building is erected upon a coffer dam of concrete, whose 8-foot-thick walls extend down 75 feet to bedrock. The basement is occupied by the terminal station of the Hudson Companies' tunnels. The two buildings together form the largest combined office building in the world. Probably the most expensively finished office buildings in the city are the combined Trinity Building and United States Realty Building, whose total floor space is over 550,000 square feet. The land for these buildings cost $6,500,000, and the buildings themselves cost $10,000,000. The main roof is 300 feet above the street, and the tower 360 feet. There are twenty-two floors, with five in the tower, and 5,000 people can be accommodated in the two buildings. For the particulars of other notable buildings, reference may be made to the descriptive matter given beneath the cuts on pages 401-3.

In closing this chapter, emphasis must be laid upon the fact that, had it not been for the development of that distinctively American device, the high-speed elevator, the present skyward growth of our modern cities could never have taken place. In one single building, the City Investing Building, there is a row of no less than twenty-one elevators for passenger service alone. The speed of travel has risen to 400 feet a minute for the local and 700 feet a minute for the express elevators.

The necessity of increasing the number of docks continues to be felt at Hamburg no less than at other ports abroad, in spite of the already extensive accommodation for shipping existing there. Since the last considerable extension took place, viz., in 1897-8—though two new docks have been opened since then—the aggregate tonnage of sea-going vessels visiting this port has increased from about 7,500,000 to 12,040,000 register tons in 1907. In consequence of this remarkable development, and although two new docks were opened in 1903, the want of sufficient room for quay berths has been acutely felt.

© 1908 SCIENTIFIC AMERICAN, INC

TUNNELS AND SUBWAYS

The fact that the most important section of New York city is located on a long and narrow island, flanked by broad and deep rivers and waterways, is largely responsible for the present activity in the construction of subways and tunnels. In the earlier days of the history of the city, passenger traffic was taken care of by lines of surface cars and ferries. These were supplemented, about thirty years ago, by the construction of four lines of elevated railways running the entire length of Manhattan Island. The Brooklyn Bridge, opened some five years later, afforded a greatly needed relief to the rapidly growing travel between New York and Brooklyn. The next step in the development of facilities was the electrification of the surface roads, which was followed in its turn by a change from steam to electric traction on the elevated system. Concurrently with these last developments, the construction of three additional bridges of unusually large capacity was commenced across the East River. One of these, the Williamsburg Bridge, was opened some four or five years ago; the Blackwell's Island Bridge will be opened as soon as the necessary changes to render it usable have been made; and the Manhattan Bridge should be thrown open to the public within the next two years.

In spite of the greatly increased accommodations provided by these enterprises, it became evident, even before they were completed, that the rapid growth of the city, and the even more rapid growth of travel, would necessitate the provision of additional means of transportation; and that any future roads which might be built must be placed below street level. It was realized, moreover, that the construction of bridges across the Hudson River was too difficult and costly for the city to depend upon any relief in this direction. After a protracted discussion of its feasibility, the question of constructing a subway system was submitted to the public vote, and a decision was given in its favor. A Rapid Transit Commission, consisting of leading men of affairs in the city, was formed and under their very able direction a comprehensive scheme of subways was laid out, and the portion of it which is now in operation constructed. The first section to be completed extends from the City Hall, New York, to Kingsbridge beyond the Harlem River, with a branch running from Ninety-sixth Street northeasterly to the Bronx. From City Hall Park to Ninety-sixth Street there are four tracks, the two outer tracks for local service, and the two inner tracks for express trains. North of Ninety-sixth Street, on the westerly branch of the road, the Subway contains, first three tracks and then two; the easterly branch from Ninety-sixth Street contains two tracks. Subsequently, a two-track Subway was constructed from City Hall Park to Flatbush Avenue, Brooklyn, the route lying below Broadway to the Battery and then under the East River in two tube tunnels. The section of the road from City Hall northward was opened in 1904, and the section from City Hall to Flatbush Avenue in Brooklyn, in 1907. The contract for the first section was let for $35,000,000; the equipment, power station, purchase of the real estate, etc., cost an additional $12,000,000, bringing the total cost up to $47,000,000. From the very first the Subway has proved an unqualified success. The express trains on certain sections of the line reach a speed of 45 miles an hour between stations, and run at an average speed, including stops, of between 25 and 30 miles an hour, the average depending upon the delay at stations. Express trains are made up of eight cars, of which five are motor cars. Local trains, which have a speed of about 16 miles an hour, including stops, are made up of six cars, four of which are motors. Before the opening of the line, it was hoped by the most optimistic that the system would develop a maximum capacity of from 375,000 to 400,000 passengers a day. As a matter of fact, on holidays and other special occasions, over 600,000 have been carried. The opening of the Brooklyn tunnel afforded greatly needed relief to the Brooklyn Bridge. It became immediately popular, and the city, as soon as funds are available, will build a branch line through southern Brooklyn to Coney Island. At present, there is under construction a loop-line which will connect the Manhattan terminals of the Williamsburg and Brooklyn bridges. In the first section to be completed the tunnels were built chiefly by the cut-and-cover method, and, except where they pass through rock, they are built of steel I-beams and structural shapes imbedded in concrete. For the later construction reinforced concrete was used. In view of the speed and rapidity of the service and the enormous volume of traffic handled, the New York Subway must be regarded as the most successful, as it is the largest and most important underground railway in the world. It is operated on the third-rail system.



Showing projecting roof for protecting workmen while blasting out a projecting reef of rocks.

SECTIONAL VIEW OF HUDSON RIVER SHIELD.



These caissons, 45 feet wide, 45 feet deep, and 106½ feet long, the largest ever constructed, are built of reinforced concrete. They provide a double-deck system which eliminates dangerous crossovers between trains running in opposite directions.

HUGE DOUBLE-DECK CAISSONS AT JUNCTIONS OF HUDSON RIVER TUBES WITH THOSE ALONG THE JERSEY SHORE.

One who has never visited a plant of this character can have no idea of the imposing appearance presented by the long line of engines and generators in the engine room. In the present case the equipment consists of nine reciprocating engines, the largest of their type ever built, and three steam turbines. The reciprocating engines are of the well-known type developed by the Allis-Chalmers Company of Milwaukee, Wis., and they are superb specimens of the engine builder's art. Because of the advent of the steam turbine with its peculiar fitness as a drive for large generator units, it is probable that these engines will stand as the "last word" in the history of the development of the reciprocating engine. When standing in the gallery at the power station and looking down the long perspective of the engine room, one cannot but feel that, whatever advantages of an economical kind the steam turbine has introduced, it has robbed the engine room of much of its spectacular features. New York city was already familiar with the Allis-Chalmers engines of this type because of their installation in that other great power plant, at Seventy-fourth Street and the East River, which provides power for the operation of the elevated roads. The Fifty-ninth Street engines are generally similar to these; but they include certain improvements in valve gear and in some minor details. The engines are rated at 8,000 horse-power, with a maximum overload of 12,000. Each consists of two compound condensing engines, one at each end of the crankshaft, with the alternator carried at the center of the shaft between the engines. The 44-inch high-pressure cylinder is placed horizontally, and the 88-inch low-pressure cylinder vertically, with the two connecting rods of each engine taking hold of a common crankpin. The stroke is 60 inches. The two cranks are set at an angle of 135 degrees to each other, an arrangement which gives eight impulses to the shaft at equal intervals in each revolution. The crankshaft has a diameter of 37 inches at the center and 34 inches at the bearings. The crankpins measure 18 inches by 18 inches, and the crosshead pins are 12 x 12 inches. The weight of

© 1908 SCIENTIFIC AMERICAN, INC

each pair of engines is 720 tons. The steam pressure is 175 pounds, and the steam consumption at the rating of 8,000 horse-power is about 13 pounds per horse-power per hour. At the far end of the station are three Westinghouse turbines of 1,250 kilowatts rating. The maximum horse-power of this station, under overload, is about 130,000 horse-power.



This power station, the largest for traction purposes in the world, is 200 feet wide by 790 feet long It contains nine reciprocating Allis-Chalmers engines of 12,000 overload horse-power and three steam turbines of 1,800 horse-power.

THE NEW YORK RAPID TRANSIT SUBWAY POWER STATION AT FIFTY-NINTH STREET.

Next in importance to the Rapid Transit Subway, which, it should be mentioned, is owned by the city, is an elaborate system of subways and tunnels, constructed by an independent concern known as the Hudson Companies, to afford direct rail communication between Jersey City and New York. For the beginnings of this enterprise we have to go back twenty-five years, to the time when Mr. De Witt Clinton Haskin, one of the active spirits in the building of the Union Pacific Railway, commenced the construction of a tunnel for the use of steam trains. The scheme met with many difficulties and disasters. It was abandoned in 1882; started again in 1890 by an English company; and ultimately was taken in hand by a corporation known as the New York and New Jersey Railroad Company; which, ultimately, under the successive names of the Hudson Companies and the Hudson and Manhattan Railway Company, succeeded in pushing the great scheme through to completion. The credit for this enterprise is chiefly due to President McAdoo. The great value of the road lies in the fact that it intersects the trunk roads which have their termini in New Jersey, and enables passengers to transfer, under cover, to trains which carry them direct to the shopping, hotel, and financial districts on Manhattan Island.

The system consists in Jersey City of a two-track road, placed in two separate 15-foot tubes, which extends from the Delaware, Lackawanna & Western Railroad terminal south to the terminal station of the Pennsylvania Railroad. Ultimately, it will be carried down to connect with the terminal of the Central Railroad of New Jersey. At Fifteenth Street it is intersected by twin tunnels which pass beneath the Hudson, and are carried up Sixth Avenue to Twenty-third Street, and ultimately will be extended to Thirty-third, where they will be in touch with the Pennsylvania Railroad terminal. A branch line will be constructed at Ninth Street to connect with the Rapid Transit Subway. Below the Pennsylvania station, at a depth of 80 feet, there has been constructed a large station, access to which will be had by elevators from the Pennsylvania terminal. From this station twin tubes extend below the Hudson River and Manhattan Island to a large terminal station between Cortlandt and Fulton streets, above which has been constructed the large terminal office building to which reference is made elsewhere in this issue.

Because of the difficulties encountered in passing beneath the Hudson River, and the novel methods which were adopted to meet them, the engineering features of this system are particularly interesting. All four tunnels were driven by the shield method, which is too well known to call for any description at the present time. The tunnels are 15 feet in diameter internally, and it was originally intended to line them entirely with concrete. After they had been driven, however, it was found that they presented such absolute stability as to render the use of concrete unnecessary. Instrumental observations have failed to show any signs of settlement; and, as far as their stability is concerned, the tubes may be pronounced a decided success. Records for rapidity in driving were broken during the prosecution of the work, the rapid advance being due to the adoption of a method altogether novel and bold. In previous work with

(*Continued on page 414.*)



If we include the footwalk across the elevated tracks, there are six separate levels for travel shown in the above view of conditions as they will ultimately exist at 33d Street.

SECTIONAL VIEW SHOWING HOW NEW YORK USES BOTH ELEVATED, SURFACE, AND TUNNEL ROADS IN PROVIDING FOR ITS EVER-GROWING TRAFFIC.



External diameter, 23 feet; internal diameter, 19 feet. Driven by the shield method. Maximum rate of advance through mud and silt, 37½ feet per day.

THE PENNSYLVANIA RAILROAD TUNNEL TUBES BELOW THE HUDSON RIVER.

© 1908 SCIENTIFIC AMERICAN, INC



From a photograph owned by the Otis Elevator Co.

LOWER NEW YORK AS IT APPEARED IN 1875. REPRODUCED FROM A PHOTOGRAPH TAKEN FROM



Copyright 1908 by George P. Hall & Son.

SKYLINE OF LOWER NEW YORK AS IT APPEARS TO-DAY WHEN VIEWED FROM

© 1908 SCIENTIFIC AMERICAN, INC



THE TOP OF THE BROOKLYN TOWER DURING THE CONSTRUCTION OF THE BROOKLYN BRIDGE.

THE TOP OF THE BROOKLYN TOWER OF THE NEW MANHATTAN BRIDGE.

© 1908 SCIENTIFIC AMERICAN, INC

HARBOR AND DOCK IMPROVEMENTS

The commanding position held by the port of New York on the seaboard of the United States is shown by the fact that out of a total foreign commerce of the United States of $3,581,000,000, $1,613,000,000 represents the foreign trade of the port of New York alone. These are the figures for the year 1907; and the money value of New York's foreign commerce translated into tonnage means that no less than 13,000,000 tons of freight passed in or out of the harbor entrance at Sandy Hook, and was handled at the multitudinous docks which line the far-reaching shore line of the city.

The proud commercial position held by New York, as shown by the fact that the city handles nearly one-half of the nation's foreign commerce, is due to its commanding geographical position and to the unusual extent and excellent character of its harbor facilities. The total frontage of the city on the water is 444.80 miles, and of this 125.10 miles is available for shipping. The available frontage is divided as follows: 5.33 miles is used by the various steam railroads; 3.61 miles is devoted to foreign steamship service; 3.11 miles to domestic steam service; 23 miles of frontage is owned by the United States government; the various parks of the city have a frontage of 23 miles; and 47.28 miles of frontage may be described as miscellaneous.

In an analysis of the accommodations of the port of New York for water carriers in relation to railroads, warehouses, and the active business of the city, dealing with the North River south of Seventy-second Street, and the East River south of Forty-fourth Street, it was recently shown by Mr. W. G. Wilgus that fourteen of the piers are devoted to railroads, exclusive of ferries; thirteen piers to the accommodation of foreign steamships; twenty-three piers are used for coastwise, river, and Sound lines; twenty-two for ferry purposes; and fifteen for municipal purposes.

It must be confessed that much of the pier and dock construction of the city falls lamentably below the standard for a port of the vast importance of New York. This is particularly true of the older docks, ferry houses, pier sheds, etc., built at a time when capital was not so plentiful, and engineering construction was hampered by considerations of economy. The disparity between the magnificent scale upon which the office buildings, bridges, tunnels, and waterworks of this city have been built, and the flimsiness and generally disreputable appearance of many of the docks and pier sheds, is something which astonishes every observant engineer who visits this city from abroad.

In making this criticism, however, we hasten to pay tribute to the excellent character of the work done on the new docks and pier sheds, which have been built of late years by the Department of Docks and by some of the leading steamship companies. Particular credit is due to the German and other foreign steamship companies for the handsome docks which they have built during the last decade along the Jersey shore of the Hudson River at Hoboken. The Department of Docks also has reason to be proud of the long stretch of new docks and pier houses extending north from Christopher Street. The size of these last-named piers, and the excellent character of the double-deck sheds erected upon them, are fully commensurate with the dignity of the great port of New York.



WELDED WIRE CLOTH AND CONCRETE SYSTEM OF FLOORING USED IN THE FLOORS OF THE NEW CITY DOCKS.

We present illustrations of Pier 56, one of several now being built by the Department. It is 100 feet wide, 825 feet long, and is covered for its whole width by a two-deck steel-frame pier shed of absolutely first-class construction. The substructure of the pier is of the prevailing type in New York harbor, being carried upon piling driven into the silt of the river bottom to a firm foundation, the piling being heavily cross-braced in both directions. The lines of piles down the sides of the dock are cut sufficiently lower than the piles under the body of the dock to allow of the placing of a side cap. Above the piles are placed the cross caps, and above these again are the rangers, or stringers. On the stringers are laid two thicknesses of creosoted planking. This is followed by a layer of armored concrete, and above this a finishing layer of asphalt. The pier-shed building is of thoroughly fireproof construction, the framework of the walls, floors, and roofs being of steel, and the floors and the roof covered with armored concrete. This armored concrete is of what is known as the Clinton welded-wire type, in which the necessary tensile strength is afforded by embedding in the concrete a heavy wire mesh, made of steel wire drawn under a tensile strain of 60,000 pounds per square inch. Of late years it has come to be recognized that the value of steel wire reinforcement in concrete depends upon the quality of the bond between the wires at their intersections, and between the surface of the steel and concrete. Where the bond is imperfect, there would be a tendency to movement between the adjacent materials and, of course, such movement means an enormous loss of strength. In the ideal armored concrete, there should be no movement of the steel in the concrete, nor of the separate members of the steel reinforcement in regard to one another, and this is particularly true of wire-mesh reinforcement as used in slab flooring. To guard against such movement, the Clinton wire cloth is welded at every intersection. This has the double advantage of preventing movement of the wires upon one another, or movement of the whole mesh within the mass of inclosing concrete. The combination of concrete deck, floor, and roof with walls of structural steel covered with corrugated iron, provides an absolutely fireproof construction, and this fact, taken with the broad dimensions and lofty headroom of these piers and sheds, renders them comparable with the best construction at the first foreign seaports.



This view represents one of several new piers built by the Dock Department. They are 100 feet wide by 800 feet long. The pier sheds, constructed of steel and armored concrete, are thoroughly fireproof.

NEW PIER SHED OF PIER 57, BUILT AND OWNED BY THE CITY.

The last report of the Bureau of Construction and Repair, dated September 10, 1908, shows the vessels building for the United States navy to be in the following state of completion: Of the new battleships, the "South Carolina," building by William Cramp & Sons, was 58.1 per cent completed, and the sister ship "Michigan," building by the New York Shipbuilding Company, was 65.1 per cent completed. Of the two 20,000-ton "Dreadnoughts," the "North Dakota," building by the Fore River Ship and Engine Building Company, maintains its long lead over the "Delaware," building by the Newport News Company, the "North Dakota" being 50.1 per cent, and the "Delaware" 40.5 per cent completed. The five new destroyers are from 20 to 49 per cent completed, and the seven new submarines from 46.8 to 55.7 per cent completed.

© 1908 SCIENTIFIC AMERICAN, INC

RAILWAY TERMINALS

It is a curious anomaly that the leading city in the United States should, at the present time, have but a single trunk line terminal station within its borders; yet it is a fact that of all the great systems, the New York Central & Hudson River Railroad Company, alone, is in a position to run its trains directly into the city itself, the trains of the New York, New Haven & Hartford Railroad entering the same terminal under a rental agreement over the New York Central's tracks. The insular position of the major portion of New York city is responsible for this condition of affairs, the broad waters of the Hudson River having served, up to the present time, as an effectual barrier to prevent the other trunk roads from building their terminal stations on Manhattan Island. The most important of these, the Pennsylvania Railroad Company, after seriously considering the construction of a large railroad bridge across the Hudson with such assistance as it might be able to get from its smaller rivals, finally decided to carry its lines into Manhattan Island by tunnel instead of by bridge, and to build a large terminal station of sufficient capacity to handle the present traffic of the road and allow a considerable margin for future development.



SECTIONAL VIEW OF THE STATION ON A LINE RUNNING EAST AND WEST.

PENNSYLVANIA RAILROAD TERMINAL STATION.

The work of building a Manhattan terminal station and the necessary connections was planned on the invariably generous scale with which this railroad undertakes work of the kind, the total estimated cost of the approaches, tunnels, and station, etc., being between ninety and one hundred millions of dollars. The tunnel section of the scheme has been handled in a previous chapter on Tunnels and Subways, and the present article will be given up mainly to a description of the great terminal yard and station.

The excavation for the new Pennsylvania terminal station as originally planned had a total width of about 500 feet and an extreme length of slightly over 2,000 feet. Roughly, it included four large city blocks. Much additional space was subsequently included for the accommodation of a power plant and the tunnel approaches to the station. The present site, which has reached the total area of 28 acres, is bounded by Seventh Avenue on the east, Tenth Avenue on the west, and on the north and south respectively by Thirty-third and Thirty-first Streets. The whole of this area will be covered at the lower level by the station tracks. At the easterly end, the tracks converge from twenty-one to four, and they extend beneath New York city, two of the tracks below Thirty-second and two below Thirty-first Street, ultimately passing in four separate tubes under the East River to Long Island City. At the westerly end, the tracks converge to two tracks, which pass beneath the North River in two separate steel-and-concrete tubes.

From what has been said above, it will be seen that the site of the station and yard is intersected by two important thoroughfares, namely, Eighth Avenue and Ninth Avenue. Eighth Avenue divides the site into two equal portions, the westerly half constituting the station yard, while the easterly half constitutes the station proper; and here it is that the imposing structure which forms the subject of our engravings is being erected. It has a frontage on the avenues of 433 feet, and on the streets of 774 feet, the sides of the building forming a perfect parallelogram. Below the surface of the street, and within the area covered by the building, the station will be divided into three levels, on the lowest of which will be the tracks at a depth of 40 feet below street grade.

The question of the architectural treatment of a building of this magnitude, and to be used for this special purpose, was one that called for the most careful consideration, and New York city is to be congratulated on the fact that the Pennsylvania Railroad Company were willing to forego the opportunity to erect a huge office building above the station site, and preferred to memorialize its entrance into New York city by the erection of a magnificent and purely classic structure, commensurate with the importance of the company and the dignity of the great city in which it has at length found a fitting terminal.

The architectural design of the entire exterior is a Doric colonnade 35 feet in height, surmounted by a low attic, the average height of the elevation being 69 feet. In the center of the building, however, in order to accommodate the great waiting room, the roof of the structure reaches a height of 153 feet. The unusual extent of the building in area and its general type are suggestive of the great baths of ancient Rome; in fact, the architects of the building, McKim, Meade & White, took the baths of Caracalla, which are still magnificent in their ruins, as the inspiration of this architectural plan. The dignity and beauty of the building are enhanced by the contrast of the lofty "skyscraper" buildings of the vicinity; and when



Length of station building, 774 feet; width, 433 feet; 69 feet in height. The handsome façade is faced with granite.

VIEW OF THE NEW PENNSYLVANIA TERMINAL STATION FROM SEVENTH AVENUE.

© 1908 SCIENTIFIC AMERICAN, INC

the structure is completed, the eye will turn with a sense of relief from the exaggerated perpendicular lines of the modern office building to the long, low perspective of this station, relieved at its mid-length by the lofty walls and roof of the waiting room. The exterior construction is of pink Milford granite, similar to the building stone of the Boston Public Library and the University Club in New York. This is a particularly effective structural stone, and its soft shades of color are decidedly pleasing to the eye.



VIEW OF THE NEW GRAND CENTRAL STATION FROM FORTY-SECOND STREET.

The main entrance to the station for foot passengers will be at the center of the Seventh Avenue façade and opposite the intersected end of Thirty-second Street. Once inside the building the passenger will find himself in a noble arcade, 45 feet in width and 225 feet in length. On either side will be shops where will be displayed wares suitable to the needs of the traveler. At the further end of the arcade the intending traveler will pass the entrance to two large restaurants, one to the left, the other to the right, and will then find himself at the head of a broad flight of stairs leading down to the floor of the general waiting room. This vast hall will be 103 feet in width, 277 feet in length, and will have a clear height from floor to ceiling of 150 feet. Within its spacious walls will be located ticket offices, parcel rooms, telegraph and telephone offices, and baggage checking windows, all so disposed that a passenger may proceed from one to the other in their logical order. Adjoining the general waiting room on the west will be two subsidiary waiting rooms, corresponding in their relation to the main hall to the two restaurants. Each waiting room will measure 58 x 100 feet. One of these is reserved for men, the other for women, and each will be provided with every convenience for comfort. The entrances for carriages will be by way of pavilions located at the corners of Thirty-first and Thirty-third Streets and Seventh Avenue. The carriages will descend on a slight gradient until they reach the level of the station proper. Entrance will be had by the Thirty-first Street incline, and the carriages will leave by the Thirty-third Street ascent as an exit.

To the east of the general waiting room is the main baggage room with its 450 feet of frontage. The baggage will be delivered and taken away by a special subway, 30 feet wide, which will extend under and along the entire length of Thirty-first Street and Seventh and Eighth avenues. From the baggage room trunks will be taken to the tracks below by motor trucks and elevators. Cab-stands will also occupy this level.

The passenger, after securing his ticket, checking his baggage, etc., passes through between the smaller waiting room entrances onto the great station concourse, an iron-and-steel-covered area over 100 feet wide, which extends across the entire width of the building. Crossing the concourse he will be confronted by a series of gates, bearing signs announcing the destination and time of departure of the trains on the various platforms below at the track level. The concourse and the adjacent areas are open to the tracks, and together they form a great courtyard 340 feet in width by 210 feet broad, roofed in by a lofty trainshed of iron and glass similar in design to the famous trainsheds of the new stations in Frankfort and Dresden, Germany. In addition to the entrances to the concourse from the waiting room, there are also direct approaches from Thirty-first Street, Thirty-third Street, and Eighth Avenue. Below the main concourse, and located between it and the tracks below, is a sub-concourse, 60 feet in width, which will be used for exit purposes only. From the sub-concourse staircases and inclines will lead to the streets and avenues and to future rapid transit stations under Seventh or Eighth Avenue. Direct connection may also be made, in due time, with the proposed subway station of the Hudson Companies' subway running up Sixth Avenue from the North River tunnels of that company. The northern side of the station, paralleling Thirty-third Street, will be assigned to the suburban service of the Long Island Railroad. The third level, which will be at a depth below the surface of the street corresponding to the height of an ordinary four-story building, will be entirely covered below the station building with twenty-one parallel tracks and their respective platforms. Within the station area, covering 28 acres of ground space, there will be 16 miles of tracks. A trackage area of this amount will afford ample facilities for the easy movement by electric power of the many hundreds of trains per day that will use this station. Through trains from the West, after discharging passengers, will proceed at once to Long Island City, where the main train yard and terminals will be located, thus leaving the station tracks clear of any idle equipment. In like manner, the westbound through trains, which will be made up at the Long Island City terminal, will pass through the station, stopping only to take up their quota of passengers. The suburban service of the Long Island Railroad will be operated on the "shuttle" plan. The planning of the station, with its numerous entrances and exits independent of each other, and separating the incoming from the outgoing throng, was worked out to facilitate, in greatest measure, the prompt and uninterrupted movement of the traffic. The exposure of the building on all four of its sides to main arteries of street traffic gives the plan a flexibility which is rarely obtainable and also insures easy connections by underground subways with the future extensions of the city's rapid transit system. The station will probably be opened for service early in 1910.



The grand concourse on the upper floor will be 160 feet wide, 470 feet long, and 150 feet from floor to roof. To the right will be the entrance gates to the express tracks. On the lower floors will be waiting rooms, ticket booths, etc., and the loop and stub tracks for the local trains.

SECTIONAL VIEW OF THE NEW GRAND CENTRAL TERMINAL STATION.

NEW GRAND CENTRAL TERMINAL STATION.

Of equal importance to the Pennsylvania terminal above described is the reconstruction of the terminal station of the New York Central & Hudson River Railroad Company at Forty-second Street, familiarly known as the Grand Central. Briefly summarized, this work includes the removal of the old train shed (which was done a few months ago); the pulling down of the present terminal and office building; a great enlargement of the present station yard, and its excavation to an average depth of about

© 1908 SCIENTIFIC AMERICAN, INC

40 feet below the old level, the work involving the removal of over 2,000,000 yards of material; the erection of new terminal buildings and offices on a greatly enlarged scale; and the electrification of this terminal and the main line of the road for thirty-five miles out from the city. Incidentally, this work has also involved the electrification of the main line of the New York, New Haven & Hartford Company, whose trains enter the Grand Central station, from Stamford, thirty-five miles distant, to the junction of that company's lines with the New York Central system, at Woodlawn.

The station building proper, together with the general offices of the company and the post office and express buildings, will cover the blocks lying between Vanderbilt and Lexington avenues from Forty-fifth to Forty-third Street, inclusive, and the block fronting on Forty-second Street between Vanderbilt Avenue and Depew Place. The main architectural features are governed strictly by the ground plan, the dominant architectural elements being determined in every case by the structural engineering necessities of the station. The southerly façade will stretch for 300 feet on Forty-second Street, and the westerly façade, including the broad approach on Forty-second Street, will reach for 680 feet on Vanderbilt Avenue. The building will extend 625 feet on Forty-fifth Street, 400 feet on Lexington Avenue, 275 feet on Forty-fourth Street, and 260 feet on Depew Place. The southerly half of the building incloses the station proper, this portion extending as far north as the northerly side of the great arched roof, seen in our sectional view. The northerly part of the building is given up to the offices of the company.

The imposing main entrance to the station on Forty-second Street is composed architecturally of three massive arches, each 33 feet wide and 60 feet in height. On entering, the passenger will find himself on a broad gallery, which runs around three sides of the grand concourse. From the gallery, passengers will descend by broad staircases to the floor of the grand concourse, which, by the way, is considerably



This view shows on the right the present level of the old station yard; on the left the lower and upper levels of the new yard, and the new Post Office building, whose architecture conforms to that of the new station building.

The completed portion of new yard. The new Post Office. Site of the train shed.

GENERAL VIEW OF THE NEW YORK CENTRAL YARD, SHOWING PRESENT CONDITION OF WORK.

the largest of its kind in the world. Its width is 160 feet, its length 470 feet, and the height from the floor to the top of the domed roof is 150 feet. The noble arched and domed roof of the concourse will extend entirely across the full width of the station building, a distance of 300 feet, or from Vanderbilt Avenue to Depew Place; but the concourse floor will be carried westerly under Vanderbilt Avenue for a distance of 170 feet. Back of the concourse, and located under the broad approach on Forty-second Street, will be the ticket booths and main waiting room, which will have twice the area of the present one. Surrounding it will be several retiring rooms, telephone and telegraph booths, and the various other conveniences of a modern station. Back of the waiting room will be a large restaurant. Across the northerly end of the concourse will extend the customary line of gates admitting to the express platforms. Beyond the gates will be located no less than thirty-four stub tracks, with broad platforms between them, the average width being about 16 feet, extra space being provided, in order to avoid the excessive crowding which is such a troublesome feature under existing conditions. Of these thirty-four tracks, the westerly eight or ten will be reserved preferably for incoming trains, and the arriving passenger, on passing through the gates onto the concourse, will find himself opposite a large cab stand, and with conveniences right at hand for securing his trunk and driving away with it with as little delay as possible. In addition to leaving directly by cab, he has the choice of four other means of exit from the station; for he may pass by a covered walk directly to the Subway, or by a 25-foot stairway to the concourse gallery and so to the street, or he can pass out



VIEW OF THE SUBSTRUCTURE OF NEW PENNSYLVANIA TERMINAL STATION, SHOWING THE CONVERGENCE OF THE YARD TO THE TUNNELS LEADING TO LONG ISLAND.



VIEW OF PORTION OF THE HUGE EXCAVATION FOR THE PENNSYLVANIA TERMINAL, SHOWING BAGGAGE SUBWAYS.

© 1908 SCIENTIFIC AMERICAN, INC

to Madison Avenue and Forty-third Street by a covered subway, or crossing the concourse, he may leave by another covered subway to Lexington Avenue. It will be understood, of course, that the thirty-four tracks extend the full width of the concourse, the most easterly track abutting on Depew Place and the most westerly on Vanderbilt Avenue, and this, of course, necessitated some careful engineering work in supporting above these tracks the immense weight of the northerly half of the station building, containing the company's offices. Care has been taken to so arrange the supporting columns that none of them shall interfere with the passenger platforms.

The plans for the new station involved, as an absolute prerequisite to success, that the suburban travel should be entirely separated from the express; and it was considered that the best way to insure this was to place the suburban tracks below the express tracks and provide a suburban concourse, waiting rooms, and other conveniences on this lower level. Moreover, it was decided that, with a view to further separating the two classes of travel, separate entrances and exits should be provided, so that the suburban passengers could enter or leave the lower level from the street or the Subway without meeting the long-distance travel. Access to the suburban tracks and station is obtained by gradually depressing the two outside tracks in the entrance tunnel below Park Avenue until they reach the lower level. In the rush hours the suburban trains will pass into the station and around a loop which will extend beneath the restaurant on the express level, the trains passing out again without breaking bulk. Toward the close of the rush hours, alternate trains will discharge their passengers from the series of seven stub tracks, which occupy the train space within the loop and in front of the suburban concourse. Trains will be stored here and in the station yard until the evening rush hour, when they will be switched out into service again. Provision is made at the inner end of the loop for connection direct to the tracks of the Rapid Transit Subway below Fourth Avenue; and it is a fortunate circumstance that the Chief Engineer of the Subway, by moving the two tunnels below Park Avenue over toward the curb line, made provision for this connection with the New York Central system, although, at that time, the New York Central Company was not disposed to consider any such connection.

In conclusion, it should be mentioned that the capacity of the Park Avenue tunnel has been increased at least one hundred per cent by the great enlargement of the station yard. One of the most serious obstacles to a further increase in the number of passenger trains under existing conditions, is the fact that the storage yard for express trains is at present located at Mott Haven, and every express train that enters New York has to make the trip through the tunnel four times, twice in entering and leaving the station with passengers, and twice in making the round trip to the yard for cleaning purposes. With the enlarged area of yard provided in the new arrangement, the storage of express trains will take place at Forty-second Street, and the tunnel will be relieved proportionately. The excavation of the yard involves, as we have noted above, the removal of over 2,000,000 cubic yards of material. The express and local service will be separated, the former using the upper and the local the lower deck of the station. The upper level will be depressed some 15 feet below the present yard level, and Park Avenue and the various cross streets will be carried over the yard on steel viaducts.

The New York Central lines are operated on the third-rail direct-current system. The third rail is carried on brackets supported on extensions of the ties, the contact rail being under-hung, and the shoes on the electric locomotive bearing against the under side of the rail, which is protected by wooden sheathing on the top and sides of the rail. This sheathing has been found to afford not only a most excellent safeguard to employees and foot passengers, but has proved to be an excellent construction for preventing clogging of the rail by snow and ice in the winter time. The long distance trains are operated by electric locomotives of about 2,300 rated horse-power which weigh 100 tons. They have proved to be capable of handling the heaviest express trains of the system with a considerable margin of power to spare. The local trains, operated by the multiple-unit system, have shown in actual service a great advance on the old steam-operated trains on every point of comparison. Current is generated in two identical power stations, one at Yonkers, and the other at Port Morris. When the complete plant has been installed each station will have a capacity of 40,000 horse-power, and each has sufficient capacity to operate the whole system. The plant was built in duplicate, with a view to having a complete reserve plant at command in case of breakdowns. The whole of the equipment of New York Central lines was built by the General Electric Company; and they are to be congratulated on the fact that from the very inception of the service it has been operated with a remarkable freedom from breakdowns or interruptions of any kind.

The locomotive, which weighs 100 tons, can develop a maximum of over 3,000 horse-power.

START OF THE FIRST ELECTRIC TRAIN FROM THE NEW YORK CENTRAL STATION.

The equipment of the four-track road of the New York, New Haven & Hartford Railroad Company from Stamford to Woodlawn possesses unusual interest from the fact that this represents the first attempt to operate a heavy trunk railroad by the alternating current. Among the theoretical advantages of this system over the direct-current system, is the fact that sub-stations are done away with, and their heavy expenses due to initial cost and the maintenance of skilled staffs of operators are saved. The current is generated at a power station located at Cos Cob, and is delivered to the overhead line at 11,000 volts. Each locomotive carries its own transformers, of which there are two to each locomotive. This adds greatly to the weight, which reaches the high figure of 95 tons for a rated horse-power of about 1,000. An interesting feature of these machines is that they are arranged to take either single-phase current from the overhead lines or direct current from the third rail. The overhead

(*Continued on page 417.*)



THE OVERHEAD LINE OF THE NEW YORK, NEW HAVEN AND HARTFORD RAILROAD, WHICH CARRIES CURRENT AT 11,000 VOLTS.



Weight, 95 tons. Horse-power, rated, 1,000. Two locomotives are coupled up for the operation of express trains.

THE NEW HAVEN RAILROAD ELECTRIC LOCOMOTIVES.

© 1908 SCIENTIFIC AMERICAN, INC

FREIGHT DISTRIBUTION BY SUBWAY

The city of New York contains within its cramped area 5 per cent of the nation's population, produces 11 per cent of the manufactured products, and serves as an outlet for nearly one-half of the country's foreign commerce. Stated more in detail, this means that the imports and exports alone, which in 1907 passed through the city, amounted to 13,000,000 tons, valued at $1,600,000,000. According to testimony given before the New York Commerce Commission in 1900, the annual tonnage of all kinds exceeds 100,000,000. One would suppose that for the handling of this huge amount of freight the most efficient and splendidly equipped transportation system would be found in the metropolis of the western hemisphere. As a matter of fact, probably no large city of the world handles its freight so clumsily and expensively as this same metropolis. At present the New York Central and Hudson River Railroad is the only line that has direct rail access to Manhattan Island, and there have been repeated attempts in recent years to abolish the terminals of that road within the city and to compel it to devise other means of handling the 5,000,000 tons of freight that now enter New York at Spuyten Duyvil. Because the New York Commerce Commission and the New York Chamber of Commerce have laid down a policy which forbids an increased use of waterfront space, any attempt to utilize the waters around New York instead of the railway mentioned would be frustrated.

Freight is now brought to New York city by the transatlantic and coast steamship lines, by several railways which terminate on the New Jersey bank of the Hudson River, by the New York Central freight line with yards lying within the city and in the Borough of the Bronx.

The steamship lines loaded and unloaded 9,400,000 tons of freight on New York or New Jersey docks in 1906-1907. A portion landed in New Jersey and intended for New York had to be brought across the Hudson River and carted off; another portion, landed in New York and intended for other cities, was unloaded and ferried across the Hudson to the railway terminals on the Jersey shore; and a third portion was carted to the New York Central freight yards for further shipment. The reverse process was carried out when goods were shipped out of the city by steamer.

The freight which arrives at the railway terminals on the Jersey and Long Island shores and which is intended for New York must be brought across the river in car-ferryboats and eventually distributed by drays.

All the freight which is brought to the city by the New York Central lines terminating in the Borough of Manhattan is cumbrously and expensively conveyed in trucks. There is also a large amount of merchandise which is similarly carted to the steamship lines and to the New York Central freight yards for shipment to other points. All this unloading, carting, and loading again has resulted in packing the business streets of New York with a dense mass of vehicles, each crawling to its destination as best it may in thoroughfares laid out for five-story buildings and gorged with the outpourings of twenty-story structures. Anyone who has ever seen West Street, South Street, and Broadway on a week day can realize that the conditions pictured are not exaggerated.

The cost of handling the 23,200,000 tons of freight brought into and shipped out of New York city by railways and steamships is enormous. With the exception of that portion of the New York Central's tonnage which is drayed to and from its terminals, all railroad freight requires lighterage and break of bulk at the waterfront. The cost of lighterage varies from 83 to 88 cents per ton. The cost of cartage on city streets varies from 60 cents to $1.25 a ton, depending on the haul and the character of the freight. It is not astonishing that in a single year the merchants of the city of New York pay $33,570,000 for hauling 23,200,000 tons of freight through the streets.

With the available water frontage on the commercial portion of Manhattan Island incapable of enlargement, and with an urgent demand by the water carriers for more room, some method of land cartage must obviously be devised that will decrease rather than increase the need for railroad space on the waterfront. Mr. William J. Wilgus, an engineer whose wide experience in adapting the New York Central's passenger terminals to the ever-growing needs of the city has admirably equipped him for the task, has made a painstaking study of this peculiar problem, and offered to the Public Service Commission, on behalf of the Amsterdam Corporation, a solution which apparently secures the benefits of rail connection not only with the New York Central's freight terminals, but also with all the other railroads now terminating on the New Jersey side of the Hudson River and in the Borough of the Bronx. Moreover, he has devised an improved method of distributing freight, whereby the time for delivery is lessened, the present high terminal charges reduced, and the harbor and the city streets relieved of congestion. Briefly stated, Mr. Wilgus proposes the construction of a system of cartage subways which will tap both sides of the principal business streets below Forty-second Street, and which will be surrounded by a high-speed belt line connected with railroads terminating on the west side of the North River, with the Sixtieth Street yard of the New York Central on Manhattan Island, and with the railroad terminals in the Bronx. Provision is also made for tunnel extensions to Long Island City and Brooklyn and along the Jersey waterfront. The transshipment of freight is to be made at remote points where space is less congested and costly than along the waterfront. The subways are to be of such dimensions that they will be able to handle at least 90 per cent of the commerce of lower Manhattan Island, and that, moreover, with but one change of bulk at points remote from the congested portions of the city. A special type of standard-gage car is to be used for steep grades, curves, and for elevators in the shipping and commercial districts. The type of car to be used is to have sufficient capacity to accommodate the largest package of merchandise and still economize space, so as to permit the delivery of cars directly to the water carrier, merchant, and manufacturer, free from contact with the surface of the city streets and removed from the expenses, uncertainties, and delays of harbor navigation. Such a car can run on the tracks of connecting trunk lines, over which it can be sent to points at a considerable distance from New York. Elaborate as such a system of subways must necessarily be, Mr. Wilgus claims that it will not prevent the construction of future subways nor interfere seriously with sewers. The streets will be cleared of the boxes and bales that obstruct the sidewalks. As the accompanying illustration shows, the relief of the marginal way from trucking will render the thoroughfare along the waterfront available for an elevated passenger railway and for light vehicular traffic between the business and residential sections of the island.

Mr. Wilgus places the approximate cost of such a system between a minimum of $80,000,000 and a maximum of $100,000,000. If the plan is carried out, he believes that it will solve the West Side problem; that it will relieve the streets of their present dense traffic; that it will render Manhattan Island directly accessible to all shippers who use the railroads; and that it will release docks and piers from railroad uses and permit the expansion of legitimate water-carrier traffic.

The present congestion is causing a gradual decrease of the city's rate of growth, and we are undoubtedly confronted with the necessity of improving transportation facilities if New York is to hold its pre-eminent position. In 1899 the foreign commerce of the port of New York was 50 per cent of the total for the United States; last year it was but 45 per cent. Similarly, the value of production has fallen from 12 to 11 per cent of the national total. From these data it must be concluded that any improved method of freight transit is worthy of serious consideration, particularly since the first requirement of this great port is ample space for the accommodation of water carriers in close relation to railroads, warehouses, and the active business district of the city.



New York spent in the year 1906 to 1907 about $37,000,000 for carting freight through its streets to and from steamship docks and railroad terminals. This system of subterranean cartage subways, with a railway belt tunnel extending around the city and communicating with the steamship docks and with the railway terminals lying both within the city and along the New Jersey shore, is designed to handle 90 per cent of this freight at a small cost, so as to leave the streets clear and allow the waterfront to be used more or less exclusively for legitimate purposes.

PROPOSED SYSTEM OF FREIGHT SUBWAYS FOR NEW YORK CITY.

The Abrasive-Resisting Qualities of Conveyer Belts.—Strips of seven materials, mounted on a board and subjected to the uniform action of a sand blast for 45 minutes, show the following relative abrasive-resisting qualities, rubber belting being taken as the standard: Rubber belt, 1; rolled steel bar, 0.66; cast iron, 0.28; balata belt, including gum cover, 0.2; woven cotton belt, high grade, 0.16; stitched duck, high grade, 0.13; woven cotton belt, low grade, 0.06 to 0.11.—T. A. Bennett, in the discussion of papers on Conveying of Materials, read at the Detroit meeting of the A. S. M. E.

© 1908 SCIENTIFIC AMERICAN, INC



Machine Shop & Tool Room

are not perfectly equipped without our

"STAR" Foot and Power Screw-Cutting Automatic Cross-Feed **LATHES**

Best for all classes of fine and accurate work. Indispensable to the advanced mechanic. Catalog "B."

THE SENECA FALLS MFG. CO.
695 Water St., Seneca Falls, N. Y.

B 18

Engine and Foot Lathes

MACHINE SHOP OUTFITS, TOOLS AND SUPPLIES. BEST MATERIALS. BEST WORKMANSHIP. CATALOGUE FREE

SEBASTIAN LATHE CO., 120 Culvert St., Cincinnati, O.

Veeder Counters

Price $1.00

to register reciprocating movements or revolutions. Cut full size.

Booklet Free.

VEEDER MFG. CO.
18 Sargeant St., Hartford, Conn.

Cyclometers, Odometers, Tachometers, Counters and Fine Castings.

Represented in Great Britain by Messrs. MARKT & Co., Ltd., 6 City Road, Finsbury Square, London, E. C., England.



THE CLIPPER CLIP

Its triangular shape prevents entangling and gives three times the capacity of any other Clip for attaching papers together.

Best & Cheapest. All Stationers.

CLIPPER MFG. CO., New York City

Send 10c. for sample box of 100; or 20c. for clips and desk tray.

THE "BARNES"

Positive Feed **Upright Drills**

10 to 50-inch Swing

Send for Drill Catalogue.

W. F. & JNO. BARNES CO.
(*Established* 1872)
1999 Ruby St., Rockford, Ill.

TRADE WB JC MARK

English Manufacturing Sites

The Great Eastern Railway Co. of England

offer free particulars of Land available for erection of manufactories within easy access of principal docks, coal, iron fields and industrial centers. Information on taxes, price of power, siding facilities, etc. Apply to

H. J. KETCHAM, General Agent
362 Broadway, New York



Palmer Motors

Two and Four Cycle. One, Two and Four Cylinder. Stationary and Marine. One to Twenty H. P. Catalogue FREE.

PALMER BROS., Cos Cob, Conn.

New York: 30 East 20th Street
Philadelphia: The Bourse
Boston: 85 Union Street
Portland, Me.: Portland Pier
Seattle, Wash.: Colman Dock
Vancouver, B. C.: 1600 Powell St.

GOES LIKE SIXTY
SELLS LIKE SIXTY
SELLS FOR SIXTY

$60 GILSON GASOLENE ENGINE

For Pumping, Cream Separators, Churns, Wash Machines, etc. FREE TRIAL

Ask for catalog—all sizes

GILSON MFG. CO. 308 Park St. Port Washington, Wis.

HANDY FOR THE POCKET

A three-fold best quality spring-tempered Steel Rule ¾-in. wide, 4-inch joints, one foot long. 25c. each. In metal bound leather case, 30c. Nickel plated, 10c. extra. Two feet long, 6-inch joints, four-fold, same width, 40 cents.



Guaranteed for accuracy and reliability, just the tool for all mechanics everywhere.

Send for 232-page catalog No. 18-B

THE L. S. STARRETT CO., Athol, Mass., U.S.A.



THE BARKER MOTOR

has from the first shown itself to be of superior design. Mechanical ideas of proven worth, combined with the best materials and careful attention to details make it

THE LEADER OF ITS CLASS.

C. L. BARKER, NORWALK, CONN.



ROYAL ENGINE

A simple, compact motor of strong, rigid construction, comprising the latest desirable features in gas engineering. 2½ to 15 horse power.

ROYAL EQUIPMENT CO.
145 Housatonic Ave., Bridgeport, Conn.

Wizard Repeating **LIQUID PISTOL**



Will stop the most vicious dog (or man) without permanent injury. Perfectly safe to carry without danger of leakage. Fires and recharges by pulling the trigger. Loads from any Liquid. No cartridges required. Over six shots in one loading. All dealers, or by mail, 50c. Rubber-covered Holster, 10c. With Pistol, 55c. Money-order or U. S. stamps. No coins.

PARKER, STEARNS & CO., 226 South Street, Dept. G, New York

THE MOVING PICTURE WORLD

ALL THE NEWS OF MOTION PICTURES

Lecture and song slides every week in the leading journal of the trade.

Best Medium for Advertisers

10c per copy, $2 per year.

MOVING PICTURE WORLD
125 E. 23d St., New York City

THE CATSKILL WATER SUPPLY.

(*Continued from page 396.*)

in height and 17½ feet wide, which will be built partly by the cut-and-cover method and partly in tunnel. It will extend to the westerly bank of the Hudson River, which will be reached at a point between Cornwall and West Point. Originally it was the intention to carry the aqueduct below the Hudson River at New Hamburg; but the preliminary borings at this and other sites proved that it would be difficult to find a rock sufficiently clean from fissures and other imperfections. An examination of various sites by geologists led to the ultimate selection of the crossing near Cornwall, where it was believed that a thoroughly sound and suitable rock would be found at a depth not too prohibitive. The aqueduct passes through the mountains and reaches the westerly shore of the Hudson River at an elevation of 400 feet above tide level. Here a vertical shaft will be sunk to a depth of probably not less than 700 feet below the river surface, or 1,100 feet below the level of the aqueduct. In the bottom of the shaft a tunnel will be driven horizontally beneath the river to connect with another vertical shaft of practically equal depth on the easterly bank of the river. From this point it will be constructed through the mountains until it reaches the new Croton reservoir. Here connections will be made to enable the water to be drawn directly from the Ashokan reservoir into the Croton reservoir, with a view to augmenting the Croton supply until such time as the aqueduct from Ashokan to New York city shall have been completed.

From the Croton reservoir the aqueduct will be continued south to Kensico reservoir, which will be enlarged to include Rye Pond and will form an auxiliary storage reservoir at an elevation of 355 feet above mean tide, capable of containing 25 billion gallons, or sufficient to supply the city at the rate of 500 million gallons per day for a period of fifty days. About four miles south of Kensico, at Scarsdale, there will be built a large filtering plant, and at Hillview, six miles to the south of this, will be another storage reservoir. With these two auxiliaries or emergency reservoirs provided, the city will be secured against any sudden interruption of its supply through failure of the 69 miles of aqueduct lying to the north of them. By the construction of a tunnel of 200 million gallons daily capacity below the East River, Brooklyn and Staten Island will be provided with a supply of 100 million gallons daily, and this aqueduct will terminate in a large reservoir to be constructed in Forest Park. From the point where this tunnel reaches the shores of Long Island, a line of 20 million gallons capacity will be built through Brooklyn and below the Narrows for the supply of Staten Island.

TUNNELS AND SUBWAYS.

(*Continued from page 405.*)

the shield it was customary to allow the silt, etc., to pass into the interior of the tunnel as the shield was advanced, and take it away in cars. The Hudson Companies' engineers decided, however, to try the plan of pushing the shield ahead by displacement; that is to say, they closed the doors in the front face of the shield, and tried the experiment of pushing the shield bodily through the silt, causing the latter to flow over and around the tube by displacement. The plan succeeded beyond expectations, and the later work was all done by this method.

One of our illustrations shows the way in which the engineers overcame a serious obstacle, in the shape of a ledge of rock, which projected from the river bottom and covered the lower half of the path through which the tunnel was to be driven. To meet the emergency, a heavy iron working roof was built in front of the shield, and under this the workmen were enabled to set up their

Engineering News

Established 1874

The Leading Engineering Paper in the World

Devoted to the interests of Civil, Mechanical, Mining and Electrical Engineers. **100 to 125 Pages,** 9 x 13 inches, weekly, amply illustrated with drawings and photographs. Each number contains the most important information regarding engineering matters the world over.

Send 10 Cents for Sample Copy

THE ENGINEERING NEWS PUBLISHING CO.
220 Broadway, New York City



GAS ENGINE GENERATOR

STEADY LIGHT FROM AN ORDINARY GAS OR GASOLINE ENGINE

Not a makeshift, but a specially designed machine with bearings amply heavy to support balance wheel without a third bearing. Write for Bulletin 152

ROCHESTER ELECTRIC MOTOR CO.
10-12 Frank St., ROCHESTER, N. Y.



The Cushman

The "MOTOR OF MERIT"

Honestly Built
Honestly Sold
2, 4, 8, 14 H.P.

They are made for the man who wants the best.

Cushman Motor Co.
2026 N. St., Lincoln, Nebr., U.S.A.

TYPEWRITERS

ALL MAKES REBUILT at ¼ to ⅓ manufacturers' prices. Rented anywhere or sold on 3 months' approval. Write for our money back guarantee; also Catalogue and Special Price List.

ROCKWELL-BARNES CO., 516 Baldwin Bldg., Chicago, Ill.

Convert Your Bicycle Into a Motor-Cycle

with one of our Attachable Outfits. A full line of Finished Motors: also rough casting for Bicycle, Auto, Marine or Stationary. Send stamp for catalog

STEFFEY MFG. CO., 2941 West Girard Ave., Philadelphia, Pa.

Had You Thought of Giving This Book as a Christmas Present?



Nothing Could Speak More Eloquently of the Affection of the Giver Than Heart Throbs.

Nothing like this book ever has appeared before in any language.

Men have *written* things that appealed to them, and perhaps these writings have appealed to the people and perhaps they have not.

Others have *selected* things that appealed to them, and perhaps these writings have appealed to the people and perhaps they have not.

But this book was made up by the people themselves!

In the truest sense HEART THROBS is a book of the people, by the people and for the people.

In response to an offer of $10,000 in prizes, more than 50,000 of what Lincoln called "the plain people of America" sent to the publishers selections of poems, stories and anecdotes that had comforted them in affliction, cheered them in adversity, inspired them with nobler ideas of living, gave them new heart and courage to face the battle of life, or brightened a gloomy day with wholesome good cheer, humor, wit and hearty laughter, and it is these prize selections that make up HEART THROBS, the book.

Just think of it! Here are hundreds of selections that, beyond question, are dear to the hearts of thousands of the best people whom Lincoln loved. Often clipped or culled by toil-stiffened fingers and age trembling hands, yellow with years of preservation, soiled by frequent handling, stained with tears, scented with lavender, rose and orris, these contributions came in, each self-proven to be a veritable heart's treasure-trove.

Heart throbs of happiness! Heart throbs of courage! Heart throbs of righteousness! Heart throbs of tender, beautiful and exquisite sentiment—they are all here for you.

It is a great and good book, and a wonderful book.

It is a book for you to give to every friend and loved one, especially those who need to be comforted and inspired anew.

And it is a book for you yourself to keep by you always.

Most books you cast aside as soon as you finish reading them—they can give you pleasure for only a short while. But this is a book that will mean more and more to you as the years go by. It will be a sympathetic friend and kind helper whenever the skies become overcast.

The Most Remarkable Book of the Age!
A Wonderful and Extraordinary Book!

That's the only way HEART THROBS can be described. The usual book of selections, mark you, is made up of things that a few "high-browed" scholars have thought that the people *ought* to like. But the selections in HEART THROBS are those that the people themselves say they *actually do* like. Do you see the difference? Do you see how this makes HEART THROBS an absolutely unique book, one that appeals to people in every walk of life.

Nearly 500 pages, Handsomely bound in cloth, gold, illuminated cover, postpaid, **$1.50**

Edition de luxe, full Morocco and gold binding, postpaid..... **$3.00**

At All Bookstores or Direct from Publishers, Using the Coupon

Money Returned if Not Entirely Satisfactory

CHAPPLE PUBLISHING CO., BOSTON, MASS.

GENTLEMEN: Enclosed find $..... for which please send me "Heart Throbs."

Name .....

Address .....

© 1908 SCIENTIFIC AMERICAN, INC

THE YOUTH'S COMPANION

For 1909

The Best Christmas Present for $1.75

There never was a household in which a Christmas Present of a year's subscription for The Youth's Companion did not bring unfeigned pleasure. If it is given to one of the younger members of the family the older ones will have a share in it. What other present costing so little is so certain to be appreciated? The 1909 issues will contain

50 ***STAR ARTICLES***—*Contributions to Useful Knowledge, by Famous Men and Women.*

250 ***CAPITAL STORIES***—*Serial Stories, Stories of Character, Adventure and Heroism.*

1000 ***UP-TO-DATE NOTES*** *on Current Events and Discoveries in Nature and Science.*

2000 ***ONE-MINUTE STORIES***—*Anecdotes, Miscellany. Timely Editorials, Children's Page, etc.*

AS MUCH READING IN THE YEAR AS WOULD FILL TWENTY 400-PAGE NOVELS OR BOOKS OF HISTORY, TRAVEL OR BIOGRAPHY ORDINARILY COSTING $1.50 EACH.

Send for Free Sample Copies of the Paper and Illustrated Announcement for 1909.

Christmas Present Coupon

Cut out at once and send this slip (or mention this publication) with $1.75 for the fifty-two issues of 1909 and you will receive

GIFT 1. **All the issues of the paper for the remaining weeks of 1908, including the Beautiful Holiday Numbers; also**

GIFT 2. **The Companion Calendar for 1909, "In Grandmother's Garden"—a panel picture, 8 x 24 inches, in 13 colors.**

Then The Youth's Companion for the 52 issues of 1909—a library in itself. HP 127

THE YOUTH'S COMPANION, BOSTON, MASSACHUSETTS.

© 1908 SCIENTIFIC AMERICAN, INC

"R.-S." Motorcycle

Single and Twin-cylinder Motorcycles
Tandems, Tricycles, Tri-cars, Delivery Vans
Standard in every essential:
ENDURANCE SPEED ECONOMY SAFETY



The Absolute Standard

The first and only real Mechanical Intake Valve Motorcycle in America. Thousands in successful use. The only Motorcycle to climb Pike's Peak.

Hundreds of testimonials showing "R.-S." achievements in racing, record making, hill climbing and endurance tests sent *free* with illustrated catalogue, on request to Dept. S.

Reading Standard Co., Reading, Penna.
Makers: The Renowned Reading-Standard Bicycle

GOKEY'S HAND MADE STORM SHOE

Engineer's and Surveyor's Boots

If you want a good waterproof storm shoe, get Gokey's. It is waterproofed like the old Indian treated his moccasins. Gokey makes every pair by-hand and to-order. He has the largest and best equipped factory in the world for hand-made shoes.

Gokey uses "Moose-Calf" uppers and Rock-Oak soles—these shoes wear like iron. Gokey makes them fit—takes care of tender feet, too. Latest styles for all outdoor uses.

Write for "Gokey's Shoe Book"

8 oz. can Waterproofing, 35c.

Wm. N. Gokey Shoe Co.
19th Street
JAMESTOWN, N. Y.



Paradox Gas Engine

A real gas engine for $2.50; delivered prepaid in U. S. or Canada $3.00. Attach rubber tube to ordinary gas burner and light at D. *Not* for natural gas.

A Great Toy

Ask toy dealers, or send for circular to
Paradox Gas Engine Co.
Hartford, Conn.

ERNEST L. RANSOME
CONSULTING CONCRETE ENGINEER
11 Broadway New York City

Mason's New Patent Whip Hoists

FOR OUTRIGGER AND INSIDE HOISTING

Faster than elevators; also hoist direct from teams, saving handling; also electric and power elevators, carriage and hand power elevators. Mason's patent friction pulleys and friction clutch couplings. Manufactured by

VOLNEY W. MASON & COMPANY, Inc.
Providence, R. I., U. S. A.

drills and blast out the obstruction. At the point of connection of the tunnel tubes with the Subway tubes running along the Jersey shore, it became necessary to work out the difficult problem of operating the trains to their various destinations without incurring dangerous crossovers on tracks running in opposite directions. The difficulty was solved by running the pairs of tunnels at such junction one above the other, and arranging the crossovers within huge double-deck caissons of the type shown in the illustration of this work. These caissons, which are truly mammoth affairs, 45 feet wide, 45 feet deep, and 106½ feet long, bigger than anything of the kind heretofore constructed, are built of reinforced concrete. The walls were first sunk to the desired depth, the necessary openings being left for connection with the tunnel tubes. Then the floor, the intermediate deck, and the roof were built, leaving the huge box-like structure ready for connection with the tubes and the laying of the tracks. The construction is clearly shown in our sectional view of the same.

The plans of the Pennsylvania Railroad Company for establishing a large terminal station for their system in the center of Manhattan Island, and connecting it with their trunk line to the West and the extensive system of roads of the Long Island Railroad Company to the East, has involved the construction of subaqueous tunnels of even greater importance than those of the Hudson Companies above referred to. Access to Manhattan Island is obtained by two single-track tubes, and to Long Island by four such tubes. As compared with the Hudson Companies' tunnels, those of the Pennsylvania Company are much larger, heavier, and more expensive to build. It was considered at the very outset that special strength and solidity would be necessary to safely carry the heavy transcontinental trains of Pullman cars. Accordingly, the tubes were made of an external diameter of 23 feet; and the segments were cast with an unusually heavy shell and deep flanges amply provided with bracing. The interior of the tube is lined with no less than two feet of concrete; and, in addition to this, the concrete is carried up parallel with the sides of the cars to the height of the window sills, where a broad shelf, wide enough to permit the passengers to walk in case of a breakdown, is provided. This shelf is formed integrally with the concrete lining of the tunnel. In the preliminary investigation of the problem, it was considered possible that the impact of the heavy trains upon the floor of the tunnel would tend to cause some settlement of the tubes in the silt in which they had

XMAS GIFTS **Diamonds** On Credit

For Christmas Presents the Loftis System is a great convenience. It enables you to make beautiful and valuable gifts without the outlay of much money. A small cash payment and you can give a "loved one" your choice of the finest diamonds, watches and other high-grade jewelry. MAKE YOUR SELECTIONS NOW from our Christmas catalog. We will send them for your inspection. If satisfied, pay one-fifth on delivery; balance in 8 monthly payments. Write for Catalog Today.

LOFTIS BROS. & CO. Old Reliable, Original Diamond and Watch Credit House Dept. M 160, 92 State St., Chicago, Ill.

The Independent

A WEEKLY MAGAZINE OF CURRENT EVENTS

Hon. William H. Taft

Among the special features in THE INDEPENDENT for 1909 will be a series of articles on our American Universities written by Dr. E. E. Slosson after a personal tour of inspection. Also a series of articles by John Barrett, Director of the Bureau of American Republics on Business Opportunities in South America.

Count Leo Tolstoy

The Sixtieth Anniversary

THE INDEPENDENT was founded in 1848 and our issue for December 10, 1908, celebrates our Sixtieth Anniversary. Editors and friends contribute to tell the dramatic and varied history of the magazine in that number.

Hon. Justin McCarthy

Character of The Independent

THE INDEPENDENT is an illustrated WEEKLY magazine. Every issue contains an eight-page summary of the news of the week thruout the world, followed by illustrated articles and editorials on subjects of current interest. The contributors, in addition to those whose pictures here appear, include, among others, Luther Burbank, Alfred Austin, Bernard Shaw, Charles M. Sheldon, Andrew Carnegie and Edward Everett Hale. To read THE INDEPENDENT is to keep informed of the best that is thought and done the world over!

Hon. James Bryce

Copyright 1904 E. Chickering

Special Offer to New Subscribers

On receipt of two dollars, the regular yearly subscription price, we will enter your name on our list fourteen months from the time your order is received. Remember that THE INDEPENDENT comes fifty-two times a year, and in this way you will get over sixty copies for about three cents each.

THE INDEPENDENT
130 FULTON STREET, NEW YORK

The History of Elevators

Tells the story of the phenomenal development of Manhattan Island. The upper section of the double page picture in the center of this magazine shows the types of buildings used before commercial architecture had been appreciably affected by the elevator, there being then, with less than 1,000 elevators in the city, no high speed lifts for both the passenger and freight service such as characterize the elevator plants of today, with over 21,000 elevators in service in the borough. The contrast between the four and five story buildings of the earlier period with the skyscrapers of today is striking, both architecturally and as an example of the remarkable results that have been accomplished, for modern commercialism, in one line of engineering since the pioneer efforts of Elisha G. Otis towards the present end.

OTIS ELEVATOR COMPANY

© 1908 SCIENTIFIC AMERICAN, INC

Jaeger
SANITARY GOODS

Unrivalled
for its wholesome
effects on the body.

The Wool keeps you warm,
The porosity keeps you fresh,
The elasticity keeps you
snug and trim.

Explanatory Booklet and Samples Free.

DR. JAEGER'S S. W. S. CO.'S OWN STORES:
New York, 306 Fifth Ave., 22 Maiden Lane;
Brooklyn, 504 Fulton St.; Boston, 228 Boylston St.;
Phila., 1516 Chestnut St.; Chicago, 82 State St.
Agents in all Principal Cities.

ELECTRIC ENGINE
With Battery
all ready to run
FREE



This is a wonderful engine. It runs either backward or forward. 3,000 revolutions a minute or as slow as you wish. Will run all sorts of mechanical toys. Every boy wants one of these electric engines and I will give you one if you will do a few minutes easy work for me. Write me today and I will send you full particulars.
A. M. Piper, C, 644 Popular Bldg., Des Moines, Ia



SEXTANT
POCKET SIZE
Not a toy. Gives accurate results in Surveying, Navigation, etc. Invaluable to those interested in engineering.
Price $1.00
L. DUERDEN, - Port Washington, L. I., N. Y.

BABBITT METALS.—SIX IMPORTANT formulas. SCIENTIFIC AMERICAN SUPPLEMENT 1123. Price 10 cents. For sale by Munn & Co. and all newsdealers. Send for catalogue.

"Porox" Ignitor Storage
BATTERIES
High Capacity. Light Weight.
Proved as the best for both ignition and light. No loss of current. It stores and returns the power to your machine. You can see and examine the interior without exposure and digging, because it is made up in transparent celluloid jars. No danger of breakage like hard rubber. Plates and jars are guaranteed for one year.
Send for catalog.
Albert Muller, 145 West 49th St., New York

Wanted, A Specialty
Wanted to manufacture a specialty that can be cast in Brass or Aluminum—either on a royalty basis or will purchase patent.
THE IDEAL BRONZE CO., Cleveland, Ohio

GASOLINE ENGINES
Stationary and marine; pumping engines complete; electric light engines complete; gasoline locomotives. Send for catalogs.
TERMAAT & MONAHAN CO.
OshKosh - - - Wisconsin

Is Your Patent For Sale?
or do you wish to enlist capital or obtain a partner? If so, we have something interesting to say to you whereby you should be able to reach the proper parties at small expense. For full information address
Business Dept. Scientific American
361 Broadway, New York City

been driven; and, as a provision against this, the original plans provided for sinking hollow cast-iron piles through the floor of the tunnel to bedrock, and laying the tracks upon a system of longitudinal girders within the tunnel, which would serve to transfer the trainloads directly to the piles, and so relieve the tubes themselves from all stresses due to live loads. These piles were to be 27 inches in outside diameter, with a shell 1½ inches in thickness. After the tubes had been driven, the satisfactory behavior of the Hudson Companies' tubes, which were built without any pile supports and have failed to show any settlement after many months of operation, convinced the engineers that the Pennsylvania tubes would be sufficiently stable without the supporting piles; and, consequently, this feature has been omitted. The tubes were driven by the shield method, and the work was pushed through without developing any problems of a serious or unusual character. The same may be said of the building of the tunnels across Manhattan Island, where the work consisted for the most part of straight rock excavation. With a view to accommodating the heavy future increase in suburban traffic to Long Island, the company determined to build four separate tubes beneath the East River. Because of the difficult character of the material encountered, the work on these tunnels has been somewhat protracted, many blowouts having developed, necessitating the construction of a false bottom to the river above the heading of the tubes by dumping in many thousand cubic yards of material from scows. All obstacles, however, have been overcome, and the whole of this vast tunnel system will have been completed before another twelvemonth has gone by. The total length of the run in tunnel from the portal in Jersey City to the portal on Long Island is 5.3 miles. The total length of single-track tube tunnels under the two rivers is 6.8 miles, and the total length of single-track tunnel under the land is also 6.8 miles. The total length of track in tunnels exclusive of the yard tracks and the station will be 16½ miles.

Contemporaneously with the execution of the above work, the financial interests which are responsible for the operation of New York city's subways were engaged in constructing a twin-tube tunnel below Forty-second Street and the East River from the Grand Central Station, Manhattan, to Long Island City. The tubes are similar in dimensions and general construction to those which form the connecting link at the Battery between the Manhattan and Brooklyn Subway systems. The tunnel was built under an old franchise granted many years ago, and it has been offered for purchase by the city at a price of $7,000,000.

NEW GRAND CENTRAL TERMINAL STATION.

(*Continued from page 412.*)

trolley system consists, for each track, of two steel messenger wires below which is carried, by means of triangles of steel tubing, the ⅜-inch copper trolley wire. In the early days of the operation of the system, difficulties developed, due to the hammering of the collector shoes as they passed the points of suspension of the wire at the apex of the triangles. This was cleverly overcome by suspending a second wire below the first by means of clips attached to the upper wire midway between its points of suspension from the triangle. The arrangement has provided a system which combines great stiffness with uniform flexibility of the trolley wires; and the troubles of sparking, wear, and breakage have been practically eliminated. The electric locomotives, which because of their short wheel base were found to sway heavily at high speed, have later been provided with end trucks of ingenious design, which have completely eliminated the trouble, and rendered these locomotives as steady in their running as a Pullman car. The whole of this work was done by the

S & W
STONE & WEBSTER ENGINEERING CORPORATION
BOSTON

THE Stone & Webster Engineering Corporation draws upon the broadest experience of its kind existing in a single organization—twenty years of the actual running of electrical utilities.

Forty properties, serving important communities with light, heat, power and transportation, are managed by the organization developed by Stone & Webster. *The Engineering, Constructing and Purchasing Arms* of this organization constitute the Stone & Webster Engineering Corporation.

Its work is backed by the experience accumulated in the operation and development of these forty properties.

We are prepared to design and to construct Water Powers, Transmissions, Steam Electric Plants, Electric Railways and Buildings, and to Electrify Steam Railroads.



Herring-Hall-Marvin Safe Co.
400 BROADWAY, N. Y.
Chicago, Ill.; Cincinnati, Ohio; St. Louis, Mo.; San Francisco, Cal.; Seattle, Wash.; Portland, Oregon

Agencies in all principal cities of America and foreign countries

America's Greatest Safe and Vault Builders

Our large Engineering Department is at your disposal for special designs and specifications free of cost.

70 YEARS IN BUSINESS

Builders of over 470,000 Fireproof Safes
Builders of over 6,000 Bank Vaults

© 1908 SCIENTIFIC AMERICAN, INC

POWER REQUISITES

Get the engine that runs reliably, requires least attention and is a dependable starter.
The simple, powerful

I. H. C. GASOLINE ENGINES

meet the requirements. They are especially adapted to all mechanical purposes—a style and size for every service.



Vertical, 2, 3 and 25-H. P.
Horizontal, (portable and stationary) 4, 6, 8, 10, 12, 15 and 20-H. P.
Air Cooled, 1 and 2-H. P.
Call on I. H. C. Agents or write for catalog.

INTERNATIONAL HARVESTER CO. OF AMERICA
(Incorporated)
15 Harvester Bldg., Chicago, U. S. A.

IF You Knew

what our engine would save you in time—work—money—you'd find out **now** about our **big 30-day Free Trial Offer** on the

Waterloo Boy



the 5-year guaranteed gasoline engine

Write today for free catalogue and our **big special offer.**

Waterloo Gasoline Engine Company
Dept 19
Waterloo, Iowa.

THE "BEST" LIGHT

is a portable 100 candle power light costing only two cents per week. Makes and burns its own gas. Brighter than electricity or acetylene and cheaper than kerosene. **No Dirt. No Grease. No Odor.** Over 100 styles. Lighted instantly with a match. Every lamp warranted. **Agents Wanted Everywhere.**

THE "BEST" LICHT CO.
87 E. 5th St., Canton, O.
Owners of Original Patents.



MOTORS FOR SALE.—Two 40 H. P. variable speed 220 volt Jenny motors. Complete with electric automatic control. Reason for selling, too small. Adapted especially for printing press work or heavy machinery. Address Purchasing Agent, Post-Dispatch, St. Louis, Mo.

NEW SAFETY AIR COMPRESSOR
For Motor Boats.
Safest, Best, Cheapest
Lest ye forget, write now to
CHAS. H. MARTIN, Manufacturer, NORWOOD, N. Y.

Butterfield & Co.
DERBYLINE, VERMONT
Taps, Dies, Screw Plates, Reamers, etc.
Quality Unsurpassed
Reputation Established

HOW Manufacturers Can Increase Their Business

Read carefully, every week, the

Classified Advertising Column

in the

SCIENTIFIC AMERICAN

Some week you will be likely to find an inquiry for something that you manufacture or deal in. A prompt reply may bring an order.

Watch it Carefully

Westinghouse Company; and both they and the New Haven Railroad Company are to be congratulated on having overcome, in spite of many initial discouragements, the inevitable difficulties attending the execution of pioneer work, on such a vast scale and under the stress of traffic of one of the busiest four-track systems in the world.

In closing it should be mentioned that the results of operation of these two systems are claimed by the companies to have been highly satisfactory. The number of train movements in the yard has been greatly reduced, the Park Avenue tunnel has been robbed of its terrors, and even to-day, while the work of excavating the yard is in progress, the trains are being operated at this terminal with a regularity and dispatch which has never been surpassed in the early history of the road.

PATENT CAUSES

INVENTORS are invited to communicate with **Munn & Co., 361 Broadway, New York,** or **625 F Street, Washington, D. C.,** in regard to securing valid patent protection for their **inventions. Trade-Marks** and **Copyrights** registered. **Design Patents** and **Foreign Patents** secured.

We undertake all **Patent, Trade-Mark** and **Copyright Practice,** both before the **Patent Office** and the **Courts,** and we have special facilities for handling **Infringement** and other suits in Federal and State jurisdictions.

A Free Opinion as to the probable patentability of an invention will be readily given to any inventor furnishing us with a model or sketch, and a brief description of the device in question. All communications are strictly confidential. Our **Hand-Book** on Patents will be sent free on request.

Ours is the Oldest agency for securing patents; it was established over sixty years ago.

MUNN & CO.
361 Broadway, New York City

INDEX OF INVENTIONS

For which Letters Patent of the United States were Issued for the Week Ending November 24, 1908.

AND EACH BEARING THAT DATE

[See note at end of list about copies of these patents.]

Agitating and aerating apparatus, L. C. Trent	905,025
Air brake system angle cock, W. Bernerd	904,502
Amusement device, Hamilton & Mellre	904,953
Animal trap, W. Sebelin	905,006
Armor exploding projectile, A. Wratzke	905,042
Ash handling apparatus, C. G. Armstrong	904,916
Atomizer, H. H. Mallory	905,087
Atomizer, invertible, T. A. De Vilbiss	904,515
Auger, J. Moore	904,796
Automobile canopy, E. T. Robinson	905,001
Automobile transmission gear and casing, E. J. Gulick	904,774
Automobile transmission mechanism, M. O. Reeves	904,723
Automobiles and like vehicles, generation, control, and transmission of electric energy, particularly for use on, A. H. Midgley	904,794
Autosleigh, C. W. Dennis	905,058
Axle, B. W. Berry	904,672
Bag holder, W. L. Herrick	904,695
Band, adjustable, H. Julich	904,700
Bandages, putting up antiseptic, J. E. Lee	905,082
Barrel packing machine, Vogt & Storck	905,017
Battery grid, Post & Morley	904,645
Bed, invalid's, E. A. Wible	904,587
Bedstead corner fastening, G. A. Carlson	904,681
Belt fastener, J. H. Woolliscroft	904,910
Belt thrower, D. A. Roderick	904,648
Beverages, making fermented, M. Wallerstein	905,029
Binder, loose leaf, O. Kellner, Jr	904,618
Bit brace, J. P. Bartholomew	904,501
Blower, H. E. Parson	904,804
Blowing engine and the like, C. N. Scott	905,108
Book, loose leaf, H. E. Hawkins	904,777
Bottle case or crate, S. Becker	904,829
Bottle corking machine, Schlosser & Fisher	905,005
Bottle or other receptable and stopper or cover for such receptacles, H. Marles	904,705
Bottle stoppering machine, W. S. Dorman	904,768
Box, E. A. G. Bierwith	904,674
Box saw guide, miter, C. H. Fox	905,067
Brake, Mullen & Brennan	904,711
Brake, S. J. Oakes	904,983
Brake indicator, air, O. R. Snyder	904,568
Brake mechanism, F. H. Osborn	904,890
Brake setting mechanism, W. A. Rideout, Sr.	904,999
Bread cutter, R. Anderson	904,593
Brick kiln, W. Rennie	904,994
Brick yard dump, C. J. Anderson	905,043
Brush, J. Nelson	904,800
Buckle, C. Meinhardt	904,707
Buckle, back band, R. C. Eldridge	905,062
Buckle, cross line, E. M. Dry	904,518
Building block and wall constructed thereof, W. T. Wightman	904,588
Building block mold, W. A. Boeck	904,927
Building construction, fireproof, G. C. Escher	904,856
Burnishing machine, heel, J. O'Connell	905,093
Button fastener, M. S. Mason	904,976
Button, tufting, P. Colgan	904,842
Buttonhole finishing machine, F. A. Read	905,101
Cabinet, bin, C. F. Kurz	904,622
Cabinet, lace, R. W. Irish	904,699
Cable connector, J. D. Firmin	904,522
Circulating machine operating device, W. H. Pike, Jr	904,561
Caliper gage, inside, Starrett & Adell	905,110
Camera stand, J. A. H. Hatt	904,613
Candle, sulfur, C. Stoddart	904,733
Candlestick, W. Stephens	904,732
Candy machine, G. H. Laughlin	904,704
Canned goods, apparatus for processing, R. B. Polk	904,644
Car, S. Otis, reissue	12,889
Car and other axles, for journal bearing, J. E. Muhlfeld	904,634
Car and other axles, for journal bearing, Mines & Muhlfeld	905,088
Car coupling, W. McConway	904,712
Car coupling, R. E. L. Janney, et al	905,078
Car door seal, J. F. Wing, reissue	12,883
Car fender, C. Kleymeier	904,965
Car indicator, street, J. E. Anger	904,915
Car, passenger, W. S. Twining	904,576
Car, passenger, L. T. Pyott	905,100
Car pedestal, mine, J. R. Roberts	905,000
Car, push, G. C. Wartman	905,121
Car stake, logging, J. R. Dodge	904,493

Free Our new 48-page catalogue of books, just published, in which will be found complete descriptions of the following

Valuable and Important Scientific Books

AGRICULTURE.—The New Agriculture. By T. Byard Collins. 12mo.; 374 pages; 106 illustrations. **$2.00**

A popular outline of the many changes which are revolutionizing the methods of farming, and the habits of farm life. It is one of the most practical treatises on the subject which has ever been issued.

ALCOHOL.—Industrial Alcohol. Its Manufacture and Uses. By John K. Brachvogel. 8vo.; 528 pages; 107 illustrations. **$4.00**

A practical treatise based on Dr. Max Maercker's "Introduction to Distillation," as revised by Drs. Delbuck and Lange, comprising raw material, mashing and yeast preparation, fermentation, distillation, rectification and purification of alcohol, alcoholometry, the value and significance of a tax-free alcohol, methods of denaturing, its utilization for light, heat, and power production, a statistical review, and the United States law.

AMATEUR MECHANICS.—Home Mechanics for Amateurs. By George M. Hopkins. 12mo.; 370 pages; 326 illustrations. **$1.50**

This is a thoroughly practical book by the most noted amateur experimenter in America. It appeals to the boy as well as the more mature amateur. Holidays and evenings can be profitably occupied by making useful articles for the home or in the building of small engines or motors or scientific instruments.

AMUSEMENTS.—The Scientific American Boy. By A. Russell Bond. 12mo.; 317 pages; 340 illustrations. **$2.00**

This is a story of outdoor boy life, suggesting a large number of diversions which, aside from affording entertainment, will stimulate in boys the creative spirit. In each instance complete practical instructions are given for building the various articles.

DIES.—Their Construction and Use for the Modern Working of Sheet Metals. By Joseph V. Woodworth. 8vo.; 384 pages; 505 illustrations. **$3.00**

A most useful book, and one which should be in the hands of all engaged in the press working of metals; treating on the designing, constructing, and use of tools, fixtures and devices, together with the manner in which they should be used in the power press, for the cheap and rapid production of sheet metal articles.

ELECTRICITY.—Electrician's Handy Book. By T. O'Conor Sloane. 761 pages; 556 illustrations. Hansomely bound in red leather, pocket-book style. **$3.50**

This work is intended for the practising electrician who has to make things go. Although the principles of electricity and magnetism are treated, the greater part of the book is devoted to practical handling of machinery, details of construction, and computations such as will be encountered in every-day practice.

GAS ENGINES.—Modern Gas Engines and Producer Gas Plants. By R. E. Mathot. 8vo.; 314 pages; 152 illustrations. ..**$2.50**

A practical treatise setting forth the principles of gas engines and producer design, the selection and installation of an engine, conditions of perfect operation, producer gas engines and their possibilities, the care of gas engines and producer gas plants, with a chapter on volatile hydrocarbon, and oil engines.

GAS ENGINES.—Gas, Gasoline, and Oil Engines. Including Producer Gas Plants. By Gardner D. Hiscox. 8vo.; 442 pages; 351 illustrations. **$2.50**

A complete book on the subject for gas engine owners, gas engineers, and intending purchasers of gas engines, treating fully on the construction, installation, operation, and maintenance of gas, gasoline, kerosene, and crude petroleum engines, with special information on producer and suction gases.

GAS ENGINES.—Gas Engine Construction. By H. V. A. Parsell and A. J. Weed. 8vo.; 304 pages; 145 illustrations. ..**$2.50**

A practical treatise describing the theory and principles of the action of gas engines of various types, and the design and construction of a half-horse-power gas engine, with illustrations of the work in actual progress, together with the dimensioned working drawings giving clearly the sizes of the various details.

HEATING.—Practical Steam and Hot Water Heating and Ventilation. By Alfred G. King. 8vo.; 402 pages; 304 illustrations. **$3.00**

An original and exhaustive treatise, prepared for the use of all engaged in the business of steam, hot water heating, and ventilation. The standard and latest book published. Describes all of the principal systems of steam, hot water, vacuum, vapor, and vacuum-vapor heating, together with the new accelerated systems of hot water circulation, including chapters on up-to-date methods of ventilation.

HYDRAULICS.—Hydraulic Engineering. By Gardner D. Hiscox. 8vo.; 315 pages; 305 illustrations. **$4.00**

A practical work treating on the properties, power, and resources of water for all purposes, including the measurement of streams, the flow of water in pipes or conduits; the horse-power of falling water; turbine and impact water wheels; wave motors; centrifugal, reciprocating, and air-lift pumps, etc.

INDUCTION COILS.—The Design and Construction of Induction Coils. By A. Frederick Collins. 8vo.; 290 pages; 140 illustrations. **$3.00**

This work gives in minute details full practical directions for making eight different sizes of coils, varying from a small one giving a ½-inch spark to a large one giving 12-inch sparks. The dimensions of each and every part down to the smallest screw are given, and the descriptions are written in language easily comprehended.

LATHE.—Modern American Lathe Practice. By Oscar E. Perrigo. 8vo.; 424 pages; 314 illustrations. **$2.50**

A new book describing and illustrating the very latest practice in lathe and boring mill operations, as well as the construction of and latest developments in the manufacture of these important classes of machine tools.

MAGIC.—Magic, Stage Illusions, and Scientific Diversions. Including Trick Photography. Compiled and edited by Albert A. Hopkins. 8vo.; 568 pages; 420 illustrations. **$2.50**

This very interesting volume is acknowledged to be the standard work on magic. It appeals to the professional and amateur alike. The illusions are all explained in detail, showing exactly how the tricks are performed.

MECHANICAL MOVEMENTS.—Mechanical Movements, Powers, and Devices. By Gardner D. Hiscox. 8vo.; 403 pages; 1,800 illustrations. **$3.00**

This is a collection of different mechanical motions and appliances, accompanied by appropriate text, making it a book of great value to the inventor, the draftsman, and to all readers with mechanical tastes.

MECHANICAL APPLIANCES.—Mechanical Appliances, Mechanical Movements, and Novelties of Construction. By Gardner D. Hiscox. 8vo.; 396 pages; 970 illustrations. **$3.00**

This book, while complete in itself, is in fact a continuation of the author's "Mechanical Movements, Powers, and Devices." The author presents to the reader information regarding nearly all conceivable devices for producing motion or accomplishing mechanical results.

SPECIAL OFFER: These two volumes sell for $3 each, but when they are ordered at one time from us, we send them prepaid to any address in the world, on receipt of $5.

PATENTS.—Practical Pointers for Patentees. By F. A. Cresee. 12mo.; 144 pages. **$1.00**

Containing valuable information and advice on the sale of patents and elucidation of the best methods employed by the most successful inventors in handling their inventions. It gives exactly that information and advice about handling patents that should be possessed by every inventor who would achieve success.

PHYSICS.—Experimental Science. Elementary, Practical, and Experimental Physics. By George M. Hopkins. In two volumes. 8vo.; 1,105 pages; 918 illustrations. Cloth, **$5.00.** Half morocco, ... **$7.00**

This book treats on the various topics of physics in a popular way and describes with rare clearness and in detail the apparatus used, and explains the experiments in full, so that teachers, students, and others interested in physics may readily make the apparatus without great expense and perform the experiments without difficulty.

PLUMBING.—Modern Plumbing Illustrated. By R. M. Starbuck. 392 pages; 10¼ x 7½; 55 full-page engravings. **$4.00**

A comprehensive and up-to-date work illustrating and describing the drainage and ventilation of dwellings, apartments, and public buildings, etc. The very latest and most approved method in all branches of sanitary installation are given.

PUNCHES.—Punches, Dies, and Tools for Manufacturing in Presses. By Joseph V. Woodworth. 8vo.; 483 pages; 702 illustrations. **$4.00**

This work is a companion volume to the author's other work entitled "Dies, Their Construction and Use." It might well be termed an encyclopedia on die making, punch making, die sinking, and sheet metal working.

RECEIPTS.—The Scientific American Cyclopedia of Receipts, Notes and Queries. Edited by Albert A. Hopkins. Containing 15,000 selected formulas. 8vo.; 734 pages. Cloth, **$5.00.** Sheep, **$6.00.** Half morocco, ... **$6.50**

Over 15,000 selected receipts are here collected, nearly every branch of the useful arts being represented. The alphabetical arrangement with abundant cross references makes it an easy work to consult. It has been used with equal success by chemists, technologists, and those unfamiliar with the arts, and is a book which is useful in the laboratory, factory, or home.

REFERENCE BOOK.—Scientific American Reference Book. Compiled by Albert A. Hopkins and A. Russell Bond. Containing 50,000 facts. 12mo.; 516 pages; illustrated. **$1.50**

This book deals with matters of interest to everybody. It contains 50,000 facts, and is much more complete and more exhaustive than anything of the kind which has ever been attempted. It is indispensable to every family and business man. It is a book for every-day reference—more useful than an encyclopedia, because you will find what you want in an instant in a more condensed form.

STEAM ENGINE.—Modern Steam Engineering in Theory and Practice. By Gardner D. Hiscox. 8vo.; 487 pages; 405 illustrations. **$3.00**

This is a complete and practical work issued for stationary engineers and firemen, dealing with the care and management of boilers, engines, pumps, superheated steam, refrigerating machinery, dynamos, motors, elevators, air compressors, and all other branches with which the modern engineer must be familiar.

TELEPHONE.—Telephone Construction, Installation, Wiring, Operation, and Maintenance. By W. H. Radcliffe and H. C. Cushing, Jr. 16mo.; 171 pages; 125 illustrations. **$1.00**

A practical book intended for electricians, wiremen, engineers, contractors, architects, and others interested in the installation of telephone exchanges in accordance with standard practice. Intricate mathematics are avoided, and all apparatus, circuits, and systems are thoroughly described. Selected wiring tables, which are very helpful, are also included.

TOOLS.—American Tool Making and Interchangeable Manufacturing. By Joseph V. Woodworth. 8vo.; 535 pages; 601 illustrations. **$4.00**

A complete practical treatise containing a valuable collection of drawings and descriptions of devices, the results of the author's own experience.

TOOLS.—Modern Machine Shop Tools. By W. H. Vandervoort. 8vo.; 552 pages; 673 illustrations. **$4.00**

A new and fully illustrated work describing in every detail the construction, operation, and manipulation of both hand and machine tools; being a work of practical instruction in all classes of machine shop practice.

WIRING.—Electric Wiring, Diagrams and Switchboards. By Newton Harrison. 12mo.; 272 pages; 105 illustrations. **$1.50**

This work is a thoroughly practical treatise on electric wiring in all its branches, beginning with the simple circuit and working up to the practical every-day problems, all being presented in a simple and intelligent manner. It is in every respect a handy, well written, instructive, comprehensive volume on wiring for the wireman, foreman, contractor, or electrician.

Any of the above books will be sent by mail or express prepaid on receipt of price.
A special circular describing them sent on application.

MUNN & CO., Publishers, 361 Broadway, New York

© 1908 SCIENTIFIC AMERICAN, INC



DR. SIMON NEWCOMB.
(Department of Astronomy.)



PRESIDENT R. S. WOODWARD,
OF CARNEGIE INSTITUTION.

FREDERICK CONVERSE BEACH.
(Editor in Chief.)



GEORGE EDWIN RINES.
(Managing Editor.)



PRESIDENT ARTHUR T. HADLEY,
OF YALE.



PRESIDENT DAVID S. JORDAN,
OF STANFORD.

HON. JOSEPH H. CHOATE.



Copyright, 1903, by J. E. Purdy
PRESIDENT BENJ. IDE WHEELER,
OF CALIFORNIA.



PROF. CASSIUS J. KEYSER,
OF COLUMBIA.
(Department of Mathematics.)



ANDREW S. DRAPER.
NEW YORK STATE COMMISSIONER OF EDUCATION.
(Department of Education.)

16 **VOLS.**

The Most Magnificent, Scholarly, Original, Practical System of Reference in Existence

THE AMERICANA

Published Under the Editorial Supervision of

The SCIENTIFIC AMERICAN

The AMERICANA, while American in its construction, is international and world-wide in its scope.

The AMERICANA is the *only* one which presents a *development* of every *department* of knowledge.

The AMERICANA contains thousands of strikingly beautiful colored plates and photogravures which embellish and illustrate the text.

"TAKEN all in all we have no hesitation in saying that this great American production, in the extent and usefulness of its contents, in its technical arrangement, in its original conception and brilliant performance, is without a peer."—*Review of Reviews.*

Some idea of the magnitude of this work may be gained from the fact that it required an investment of more than **$1,500,000** to produce it.

Over Two Thousand Special Contributors

Comprising the greatest living American and European scholars and authorities.



EDWARD EVERETT HALE.



CARDINAL GIBBONS.



PROF. J. E. CREIGHTON,
OF CORNELL.
(Department of Philosophy.)



Copyright, 1902, by J. E. Purdy
THOMAS W. HIGGINSON.

FREE ON REQUEST

No mere advertisement can convey an adequate idea of the vast interest and immense utility of the AMERICANA, or of its exceptional value and sumptuous appearance. Let us send you therefore a handsome **120-page book** containing **specimen pages, maps, full-page plates, duotones, color plates, and text illustrations,** with **portraits of celebrities,** full page photographic plates **of the most interesting and up-to-date subjects—The Americana being the best illustrated of all reference works.** With the object of making the AMERICANA quickly and widely known, before placing the work in the hands of dealers for general distribution, we will accept orders direct at a large reduction from the established price. Those interested are requested to make application immediately. The work is sold exclusively in connection with the **SCIENTIFIC AMERICAN,** and cannot be otherwise obtained.

REQUEST BLANK

SCIENTIFIC AMERICAN COMPILING DEPT.
225 FIFTH AVENUE, NEW YORK CITY

Without obligating myself to purchase I would like to receive FREE, your 120-page Book of Specimen Pages, Maps, Duotones, Color Plates, Portraits, etc., of the NEW AMERICANA, with particulars of your special advertising proposition:

Name.....

Occupation.....

Street.....

Town and State.....

CUT OUT AND MAIL TO-DAY

© 1908 SCIENTIFIC AMERICAN, INC

Floors

Roofs

Illustrating Various Uses of Clinton Electrically Welded Wire as a Reinforcing

The above cut shows Pier No. 56, Chelsea Improvements North River, New York

This pier will be occupied by the Cunard Steamship Company. Illustration shows method of securing Continuous Reinforcing across the entire building. The safest, surest and easiest way to make a reinforced floor foolproof is to use the continuous Bond of Clinton Electrically Welded Wire as a Reinforcing.



Stable for Acker, Merrall & Condit Co., West 46th Street New York City

Clinton Fireproofing System used throughout for floors and roofs.

The Continuous Bond of Clinton Electrically Welded Wire is the ONE best Reinforcing for Concrete.



Aqueduct under course of construction for the Water Department, City of Montreal, Can.

The above cut displays the method for using Clinton Electrically Welded Wire as a Reinforcing for the Aqueduct under course of construction. The Aqueduct is in general 9 feet in diameter, and is 27,000 feet in length.

CLINTON WIRE CLOTH CO., Clinton, Mass.

Ceilings

Partitions

FIREPROOFING DEPARTMENTS

ALBERT OLIVER, 1 MADISON AVENUE, NEW YORK

WASHINGTON: ROSSLYN SUPPLY CO., Colorado Bldg.
CHICAGO: CLINTON WIRE CLOTH CO., 30-32 River St.
SYRACUSE, N. Y.: PARAGON PLASTER CO.
ST. LOUIS: HUNKINS-WILLIS LIME & CEMENT CO.
SAN FRANCISCO: L. A. NORRIS, 835 Monadnock Bldg.
SEATTLE: L. A. NORRIS, 909 Alaska Building

© 1908 SCIENTIFIC AMERICAN, INC

"A PUTTING-ON TOOL"

Oxy-Acetylene Cutting and Welding Torch

Welds Cast Iron

and nearly all other metals perfectly, repairs broken machinery quickly.

Welds boilers and water and steam mains in place.

Fills blow-holes and other defects in castings.

Reduces cost and improves metal construction in many instances.



Cuts Steel

rapidly in almost any form with the Oxy-Acetylene flame.

Valuable for roughing out dies, cutting steel gearing and structural work.

Cuts 15 inch I beams in three minutes.

In use by U.S. Navy and a number of the largest industrial concerns.

Demonstration Plant

Jersey City, N. J.

Write for Information

Send for Catalogue

Repairing an Aluminum Automobile Gear Case

DAVIS-BOURNONVILLE COMPANY

GENERAL OFFICE, ROOM 1572 WEST STREET BUILDING — 90 WEST STREET, NEW YORK, U. S. A.

Car supplemental wheel, motor, M. D. Stocking 904,570
Car trolley, J. Kaufman 904,877
Car underframe, J. M. Ames 904,746
Cars and the like, apparatus for indicating the level of petrol in the petrol container of motor, F. Huttenlocher 904,874
Cars, truck for replacing derailed street, E. E. Birch 905,050
Caramel tray, F. P. Vavra 905,027
Carbureter, W. M. Carlin 904,508
Carbureter, E. J. Thompson 904,659
Carbureter, P. Spranger 905,012
Carbureter and mixer, O. R. Hukle 904,960
Carrier system, automatic, S. H. Libby, 904,788, 904,789
Cartridge trimming machine, H. J. Hurd ... 904,784
Casing perforator, L. E. Stephens 904,657
Cash register, W. R. Heinitz 905,072
Casting soil, water, and gas pipe direct from the blast furnace in permanent molds, E. A. Custer 904,759
Chain, J. V. Costello 904,846
Chair and fan attachment, rocking, J. Gavlak 904,947
Chimney and smokestack, H. Corregan 904,845
Chuck, D. A. Bruton 904,679
Churn, T. N. Brown 904,935
Circuit closing relay, J. F. Webb, Jr. 904,661
Clamp, rail, J. M. Vail 904,820
Clasp for purses and the like, safety, W. McIlroy 904,981
Clock case, W. J. Walker 904,581
Clock with alarm and music attachment, V. M. A. Bogaert 904,929
Closet flushing and ventilating means, J. J. Shtuchka 904,653
Clothes drier, H. W. Lamp 904,970
Clothes pin, I. Barmore 904,595
Clutch, J. C. & W. J. Pope 905,097
Coal separator, J. H. Walker 904,738
Coaster brake, P. W. Toohey 904,735
Cock, stop, T. E. Dwyer 904,852
Coffee pots, etc., attachment for, T. R. Gracie 904,949
Coin controlled gasometer, W. J. Hill 904,957
Collar, pyroxylin, F. A. Gudger 905,068
Collar, safety, L. Harlow 904,530
Concrete building block molding machine, De Armon & McKinney 904,513
Concrete column reinforcement, A. A. Clement 904,841
Concrete columns, metal reinforcement for reinforced, E. McClure 905,090
Concrete construction, armored, E. Coignet 905,056
Concrete construction reinforcing bar, J. V. Jenkins 904,785
Concrete construction, tension bar for, G. S. Miles 904,977
Concrete constructions, etc., device for, G. S. Miles 904,978
Concrete drain tile, mold for forming, S. L. Sheets 904,900
Conductor flexible suspension, L. Steinberger 905,014
Connector, C. T. Crocker 904,603
Control apparatus for translating devices, distance, E. Schattner 904,810
Control system, G. H. Hill 904,780
Controlling device, condition, J. I. Ayer 904,917
Copper from coagulated cellulose, eliminating, E. Crumiere 904,684
Core box, E. B. Horne 904,697
Corset, K. V. Tojetti 904,574
Cotton gin, roller, W. L. Crowson 904,939
Cotton warper, Payne & Wallace 904,719
Coupling. See Car coupling.
Cover, F. G. Lauster, Sr. 904,972
Cow milker, J. Ripczinske 904,564
Crank, adjustable, E. C. Drecoll 904,764
Cream separator, E. W. Broomall 904,600
Cross tie, railway, F. N. & H. A. Drane 904,944
Crusher and pulverizer, M. F. Williams, 904,907, 904,909
Crusher and pulverizer hammer or beater, M. F. Williams 904,908
Cuffs, etc., machine for folding blanks for, G. J. Dormandy 904,516
Culvert, J. F. White 904,586
Culvert, J. H. Schlafly 904,651
Cup plug, lubricator, A. McDonald 904,554
Curtain fixture, G. Jones 904,537
Curtain stretcher, lace, P. J. De Vries 905,059
Cutting and raveling machine, carpet, W. P. Kirkpatrick 904,964
Cutting machine, coal, G. Leichnam 904,623
Cylinder, B. Trebilcock 905,023
Cylinder type, adjustable lock of the, H. G. Voight 904,580
Damper regulator, Roberts & Holloway 904,894
Davit operating device, H. B. Firth 905,065
Dental broach and holder, C. R. Powers 904,990
Dish washing machine, Singer & Clark 904,731
Disinfectant distributer, J. O. Walker 904,739
Display case, O. F. Kurz 904,621

Keenan Building, Pittsburg, Pa. Thomas Hannah, Architect, Equipped with Mullins Fire-Proof Windows.

A Great Protection—A Great Saving

Think what the elimination of the exposure risk in the cost of fire insurance on this building would amount to. You can effect the same saving and decrease the cost of your own fire insurance besides gain certain fire protection by installing

Mullins

Fire-Proof Storm-Proof Dust-Proof

Windows

They last as long as the building itself and are the most effective fire-proof windows made. Entirely lock-seamed metal; no soldered joints in frame, sill or sash. Their perfect construction does not admit of warping or buckling, and heat contraction or expansion does not affect them in any way.

Mullins Fire-proof Windows are manufactured under supervision of Underwriters' Laboratories Inc., according to the latest specifications of the National Board of Fire Underwriters, and every window is inspected, approved and labeled with their official label. Send for descriptive catalog.

W. H. Mullins Company, 203 Franklin Street Salem, Ohio

ELECTRO MOTOR, SIMPLE, HOW TO make.—By G. M. Hopkins. Description of a small electric motor devised and constructed with a view to assisting amateurs to make a motor which might be driven with advantage by a current derived from a battery, and which would have sufficient power to operate a foot lathe or any machine requiring not over one man power. With 11 figures. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. 641. Price 10 cents. To be had at this office and from all newsdealers.



GENERATING UNITS FOR LIGHTING AND POWER PURPOSES

10 K. W. TO 500 K. W. DIRECT CURRENT
15 TO 1500 H. P.

Ask for Bulletin 19

RIDGWAY DYNAMO & ENGINE COMPANY
Ridgway, Pa.

Display stand, H. R. Cropp 904,758
Door operating mechanism, J. G. Bower 904,675
Door operating mechanism, G. C. Cherbonnier 905,123
Doors, cupboards, etc., lock for, H. J. Cowell 904,683
Draw bar, E. Rolin 904,727
Draw bar, W. Graham 904,865
Drill rest, adjustable, J. F. Parker 905,095
Drum controller, H. J. Wigand 904,906
Dust pan, Babbitt & Hanchett 904,500
Dye and making same, yellow-olive, E. Saul 904,809
Dyestuff and making same, violet vat, A. Grob 904,867
Ear protector, R. McWilliams 904,715
Egg and other beater, H. P. Wells 905,036
Elastic webbing, embossing, H. H. Allison 904,912
Electric current bathing tub, F. Braun 904,677
Electric drill controller, Duntley & Kinman. 904,851
Electric float, stream power, W. J. Pattosien 904,892
Electric heating device, Ayer & Gale 905,045
Electric lighting device, J. T. Fisk 904,524
Electric machines, current collecting apparatus for dynamo, J. E. Noeggerath 904,801
Electric machine voltage regulator, dynamo, G. S. Neeley 904,887
Electric motor control system, A. C. Eastwood 904,765
Electric railway line interrupter, A. Thode. 904,902
Electric signs, electric lamp receptacle for, F. W. Ruby 904,728
Electric traction elevator, D. C. Suplee 905,114
Electric welding, L. S. Lachman, 904,540, 904,881, 904,882
Electric welding rotary converter, A. M. Hoffman 904,782
Electric wire outlet box, J. Fountain, Jr. ... 905,066
Electrical conductor support, J. S. Allen ... 904,592
Electrical distribution system, C. D. Haskins 904,776
Electrical distribution system, W. L. Bliss. 904,925
Electrical interrupter, Sutton & Steele 905,115
Electromagnet, G. W. Henry 904,871
Ellipsograph, C. Schreiber 905,107
Embroidering frame, N. B. Noble 904,716
Embroidering machine, R. Loeb 904,626
Emergency brake, F. B. Corey 904,844
End gate, wagon, R. L. Templeman 904,818
Engine balance valve, steam, F. J. Meanley. 904,631
Engine governor, marine, A. H. Zientarski. 904,667
Engine starting mechanism, internal combustion, Holden & Elphinstone 904,616
Engines, carbureter for internal combustion, G. Enrico 904,855
Engines, device for reversing the direction of rotation of internal combustion, L. Le Pontois 904,624, 904,625
Engines, means for connecting and disconnecting, S. S. Smith 905,011
Envelop, W. J. Bernthold 904,750, 904,751
Exercising machine, O. K. Sletto 904,815
Explosive motor, compound, S. A. Reeve 904,807
Explosives, apparatus for distilling off and recovering the solvent used in the manufacture of, W. Nikolsky 904,636
Eyeleting machine, Glass & Bean 905,124
Fabric. See Wire bed bottom fabric.
Fabric, textile, G. P. Schlemmer 905,106
Fabrics, manufacture of multicolored, M. Bohler 904,752
Fan, ceiling, F. P. McBerty 905,089
Fanning mill, W. Milbrath 904,885
Faucet, C. J. Paulson 904,559
Feed-capping machine, automatic, G. Kirkegaard 904,879
Fence, G. A. Masters 904,630
Fertilizer distributer, C. O. Morgan 904,797
File cases, device for handling, Nicholson & Warfield 904,888
File, combined temporary binder and arch, P. MacGregor 904,628
Filter, W. L. Imlay 904,698
Filter plate lock, W. J. Ruff 904,649
Filter, water, H. Brunner 904,678
Finishing machine, silk thread, E. Pohl 904,893
Fire alarm box alarm device, Nicholson & Warfield 904,889
Fire alarm, burglar alarm, and telephone system, automatic, Milliken & Cole 904,550
Fire alarm circuits, circuit closer for, W. W. Katterjohn 904,786
Firearm, automatic, C. L. H. Prinke 904,646
Firearm sighting apparatus, M. Klingler 904,880
Fireproof structure, A. L. A. Himmelwright 904,535
Floor pocket receptacle and plug, F. J. Russell 904,898
Floor scraper, J. Miotke 904,709
Flooring, device for laying parquet, F. Wellan 904,823
Fly catcher, C. A. Arents 904,668
Fly catcher, C. A. Arents, reissue 12,884
Fruit box, W. R. Stokely 904,571

THE 1909 LINE OF

LAMBERT

FRICTION-DRIVE CARS

WILL INCLUDE

$800 Runabout
$1250 5-passenger Touring Car
$1750 5-passenger Touring Car
$2000 7-passenger Touring Car

Every car a bargain in its class. All have THE SUPERB FRICTION-DRIVE, concerning which the Scientific American said in its issue of Nov. 9th, 1907: "Its cost of maintenance is extremely low, while its reliability is very great."

☞ Don't buy a gear-drive car until you investigate the Lambert

Literature on request

Buckeye Mfg. Co., Anderson, Ind.



LEARN TO DRAW

Big money easily made. $20 to $100 a week. Pleasant, refined, fascinating work for men, women, boys and girls. We guarantee proficiency or discourage enrollment.

Illustrating, Cartooning, Commercial Designing taught by artists trained in American and European Schools. Instruction adapted to each student's needs. Advisory Board of world's best artists approves lessons.

Qualify At Home in Spare Time!

Test Work Sent FREE to ascertain individual talents and needs. State *course* wanted. You assume no obligation. *Mechanical, Architectural* and *Sheet Metal Pattern Drafting* also taught successfully.

ACME School of Drawing, 1573 South St., Kalamazoo, Mich.
If interested, ask about The ACME Resident School in Kalamazoo.

STEAM TURBINES.—THEIR CONSTRUCTION, Operation and Commercial Application. SCIENTIFIC AMERICAN SUPPLEMENTS 1306, 1307, 1308, 1422, 1400, 1447, 1370, 1372. The articles have all been prepared by experts in steam engineering. Price 10 cents each, by mail. Munn & Co., 361 Broadway, New York City, and all newsdealers

STUDY LAW

Leading Law School in Correspondence Instruction. Established 1892.

Prepares for the bar. Three Courses: College, Post-Graduate and Business Law. Method of instruction combines theory and practice. Approved by the bench and bar.

Classes begin each month. Send for catalog giving rules for admission to the bar of the several States.

Chicago Correspondence School of Law
506 Reaper Block, Chicago

© 1908 SCIENTIFIC AMERICAN, INC



The Perfect Edge

A razor may cut a hair and yet not give a smooth shave. An edge produced by a few strokes on a Torrey Strop just before shaving not only cuts the beard smoothly but leaves the skin cool and unroughed. The secret is in the

Torrey Strops

They are better than others—the Torrey way gives the quality. Our free catalogue tells all about them. If not at dealer's, sent postpaid for 50c, 75c, $1.00, $1.50, $2.00 and $2.50. If you don't like them it's money back.

Torrey's Oil-Edge Dressing keeps any strop soft. 15c at dealer's, or by mail.

Torrey Razors are the finest razors made.

J. R. TORREY & CO., Dept. G, Worcester, Mass



Beaver Board

The Modern Wall and Ceiling Material

Made of pure wood fibre. Light and strong. Non-conductor of cold. A sound deadener. Nails direct to studding.

Takes Place of Both Lath and Plaster

Eliminates unsanitary wall paper. Susceptible to artistic decoration. Descriptive booklet and sample free. Write today.

The Beaver Manufacturing Co., 238 Perry St., Buffalo, N. Y.

Tobacco Flavor
Not Pipe Odor

Turco-American Glass Pipe

Smokes cool and sweet and clean. It has two bowls. An inner one of fine meerschaum, from which the smoke is drawn through vents into an outer one of tough, annealed, non-absorbent glass. Here the moisture and nicotine collect and remain. *That's why only cool, clean smoke reaches the mouth—why the pipe never bites*

Every grain of tobacco burns to a white ash. No wet residue to throw away and the last whiff is as sweet as the first. Easily cleaned and leaves no offensive smell in rooms or clothes. Send for one. Smoke it a week and if not satisfied money will be refunded.

Pipe with handsome, durable case, $2.00. Without case, $1.50. Postpaid. State preference for straight or curved stem.

Send for FREE Booklet "History of Smoking."

Turco-American Pipe Co., 372 South Ave., Rochester, N. Y.



"HOW TO REMEMBER"
Sent Free to Readers of this Publication

Stop Forgetting

Youare no greater intellectually than your memory. Easy, inexpensive. Increases income; gives ready memory for faces, names, business details, studies, conversation; develops will, public speaking, personality. Send today for Free Booklet. Address

DICKSON MEMORY SCHOOL, 700 Auditorium Bldg., Chicago

CLOVER LEAF ALTON 1909 BIRDLAND CALENDAR

(Sequel to the Famous Fencing Girl)

FOUR FLYERS

Graceful poses from life; in 13 colors. Size 10x15 inches, suitable for framing.

"THE ONLY WAY"

to own one of these gorgeous calendars is to send 25 cents and the name of this publication to GEO. J. CHARLTON, General Passenger Agent, Toledo, St. Louis & Western and Chicago & Alton Railroads, 704 Railway Exchange, CHICAGO, ILL.

Perfect Passenger Service between Toledo, Chicago, St. Louis and Kansas City.

Fuel feed, automatic, E. G. Ofeldt	904,984
Furnace muffle, electric, Hammond & Savin.	904,529
Furnaces, charging blast, H. D. Williams, et al	905,125
Furnaces, means for attaching stirring arms to shafts in mechanical roasting, W. Troeller	904,819
Furniture support, swinging, W. H. Virgie	904,578
Fuse attachment, safety, W. J. Boemper	904,928
Fuse plug, electrical, H. E. Bradley	904,832
Gang machine, A. O. Thomas	904,734
Garment, combined, M. Tartikoff	905,021
Gas box attachment, F. E. Brickner	904,933
Gas burner, H. A. Giller	904,772
Gas cut off, J. F. Wells	904,662
Gas engine, E. A. Nelson	904,556
Gas producer feeding apparatus, J. A. Swinwell	905,117
Gas producer feeding mechanism, W. B. Hughes	904,873
Gate, E. J. A. Rice	904,647
Gate, G. J. Gintert	904,862
Gate opening and closing device, S. P. King	904,963
Gear-cutting machine cutter head, E. J. Lees	905,084
Gearing, E. B. Zook	904,744
Gearing, J. J. Bowes, Jr	904,931
Gearing, awning, E. Rosenberg	905,002
Glass case, tourist's, J. M. Faehrmann	905,063
Glass, crate for sheet, H. O. Hemmick	904,694
Glass molding apparatus, automatic, F. J. Mackin	904,975
Glassware, manufacturing, F. L. Arbogast	905,044
Go-cart, folding, R. G. Ledig	904,542
Gold from crushed ores, apparatus for the extraction of, T. E. Beaumont	905,048
Governor, centrifugal, H. C. Clay	904,602
Grain scourer, T. Grose	904,950
Grapple, C. L. Simmons	905,010
Grinding machine, universal, F. Stutzman	904,817
Grinding mill, W. R. Cunningham	904,686
Grinding mill, A. A. Warner	904,905
Gun, air, W. J. Burrows	904,507
Gun chain rammer, O. Knoch	904,966
Gun fluid brake, recoil, F. Stock	905,112
Gun, trap, J. Ross	905,104
Gun trigger mechanism, machine, K. Heinemann	905,071
Guns, pneumatic recuperator for recoil, N. Koch	904,967
Hair ribbon holder, M. L. Schwab	904,566
Hame and trace connector, Brents & Gunn	904,932
Hammer, power, J. W. Keeley	904,701
Hand bag, T. R. Weidemann	905,034
Handle, W. H. Kepple	904,619
Harmonica, A. W. Anderson	904,914
Harness, W. J. Holder	904,696
Harrow, J. M. & W. J. Glick	904,864
Harrow attachment, J. F. Brownlee	904,754
Hatchway, E. Wold	905,041
Haulage system, P. A. Degener	904,514
Heater, Plank & Fulghum	904,642
Heating appliance, W. B. Brind	904,833
Heating system, vacuum, J. L. Welshans	905,037
Hinge, door, V. Kiple	904,620
Hinge, gate, G. B. Manlove	904,791
Hoisting mechanism, C. G. Palmer	904,717
Holder, C. C. Williams	905,038
Hook. See Molding flask sand hook.	
Horse detacher, D. A. Brunett	904,505
Horse detacher, J. Worrell	904,666
Horse releaser, G. W. Morter	904,552
Horses and other animals, safety bit for, G. Ciammaichella	904,682
Hose rack, H. Gibbs	904,527
Hose supporter, V. Price	905,099
Hub, spindle, and axle arm, W. E. Baxter	904,921
Hydrocarbon burner, E. J. Achee	904,911
Hydrocarbon motor, A. A. Low	904,544
Ice cutting apparatus, plate, P. F. Stein	904,569
Igniting device, self, O. M. Muller	904,886
Incandescent illuminant, O. M. Thowless	905,119
Incubator, J. A. Britton	904,599
Incubator heater, H. E. Keller	904,702
Index drawer, card, E. M. Olson	904,638
Indicating and recording instrument, W. F. Howe	904,783
Ink well, J. I. Woodruff	904,664
Insulating material, G. H. Rupley	904,808
Internal combustion engine, E. Rathbun	904,562
Internal combustion engine, J. Hutchings	904,961
Internal combustion motor, M. Berliet	904,671
Internal combustion rotary engine, H. Lee	904,974
Iron, thill, F. A. Strodel	905,113
Ironing board, H. W. Vance	904,736
Jewelry component, J. C. & J. A. Doran, reissue	12,888
Journal box, L. G. Woods	904,665
Key holder, J. F. Stewart	905,015
Keyboard, auxiliary transposing, G. G. Scurfield	904,730
Ladder, sectional, H. M. Ackley	904,591
Lamp, brazier's, J. A. Shores	905,009
Lamp burner, A. L. Edwards	905,061
Lamp, electric incandescent, F. W. Erickson	904,609
Lamp electrode, arc, Hatfield & Lewis	904,532
Lamp for stereopticons, etc., arc, H. F. Patton	904,640
Lamp reducer, C. Wirt	904,826
Lamps, shade roller for incandescent, J. Weber	904,821
Land roller, H. P. A. Andersen	904,913
Lather rubber, R. & R. W. Sampson	904,650
Leather splitting machine, flexible roll, Stehling & Brenner	905,111
Ledger plate and knife guard, S. F. Martin	904,547
Leveler and scraper, T. W. Clark	904,840
Lifting jack, S. B. Minnich	904,551
Lightning rod, G. R. Kress	904,969
Linen, appliance for washing, F. L. Bartelt	904,828
Liquid yeast mixtures for bread, preparing, W. J. Temple	904,573
Lock, J. R. Fletcher	904,860
Lock, S. Popky	905,098
Locomotive exhaust apparatus, G. J. Hatz	904,614
Locomotives, adjusting mechanism for the journal boxes of, J. Conlin	904,938
Log turner, C. D. Scott	904,652
Logging apparatus, T. W. Tiley	905,022
Loom, weft replenishing, N. Demers, reissue	12,887
Lubricator, J. P. Johnson	904,962
Lubricator, J. J. Costello, Jr	905,057
Machine support, W. Wenzel	904,585
Mail bag catching and delivering apparatus, J. E. Boyle	904,676
Mail bag support, W. H. Tell	904,658
Mail catcher, W. D. Walton	905,030
Mail delivery cabinet and heater, combined rural, J. W. Walker	904,740
Match box, O. A. Garland	904,691
Match box, J. A. Edes	904,766
Match box holder, W. J. Jones	905,081
Match safe, J. E. Hill	904,872
Matrix and holder therefor, W. E. Chalfant	904,510
Matrix corner chamfering machine, H. A. Reynolds	904,996
Matrix notch chamfering machine, H. A. Reynolds	904,995
Measuring instrument, F. H. Pierpont	904,560
Measuring instrument, combined, W. R. Chynoweth	905,054
Measuring rod, H. Boeck	904,830
Metal nut, wrought, F. A. Neider	904,555
Metal-working machine, F. E. Bocorselski	904,926
Metals, making homogeneous bodies from tantalum metal or other refractory, W. von Bolton	904,831
Metallic compounds and producing carbids, smelting, E. F. Price	904,991
Mine roof support, F. C. Keighley	904,878
Mirrors and other articles of glass, ornamentation of, T. Archer	904,594
Mixer, A. E. McNitt	905,092
Molding flask sand hook, A. Kolvoord	904,787
Molding press, hydraulic, P. Bonvillain, reissue	12,885
Motor wheel, cycle, J. E. Perillard	904,721
Mud guard, W. D. Snowman	904,654
Multiply material, apparatus for forming, J. J. Hinde	905,076
Multispindle machine, G. O. Gridley	904,866
Music leaf turner, W. J. Thillen	904,901
Nailing machine attachment, P. L. Billingsley	904,503
Necktie, D. C. Mitchell	904,710
Needle, vaccinating, C. H. Higgins	904,779
Net, D. H. Saunders	904,899
Newspaper holding device, J. K. Morris	904,979
Nozzle, spray, A. S. Washburn	905,032
Nozzle tip, W. E. Bideker	904,673

CYCLOPEDIA OF CIVIL ENGINEERING

8 VOLUMES—page size 7x10 inches - nearly 4,000 pages —3,000 illustrations, diagrams, plates, formulas, etc. Bound in HALF RED MOROCCO.

THIS Cyclopedia is the only complete, comprehensive and authoritative work published, covering the entire field of Civil Engineering and all branches connected with it. It thoroughly covers every detail from plane surveying, plotting and topography to the most advanced work in theory, design and construction of bridges.

FREE FIVE DAY OFFER

Without deposit, we will send a set to you by prepaid express for 5 days' FREE examination if you mention the name of your employer and occupation or send business card. If you wish to keep the books, pay $2.00 within 5 days and $2.00 a month until you have paid the specia $24.00 price; otherwise notify us to send for them at our expense. Regular price is $48.00.

If you order promptly, we will include FREE for one year, as a monthly supplement, the

TECHNICAL WORLD MAGAZINE

A popular magazine with a technical turn containing the latest discussion on timely topics in Science, Invention, Discovery and Industry, also the best Fiction, Biography, Travel and Humor, in fact, the best of everything. Illustrated with scores of interesting photographs.

Brief List of Contents

Plane Surveying—Mechanical Drawing—Plotting and Topography—Railroad Engineering—Statics—Strength of Materials—Roof Trusses and Mill Building Construction—Cost Analysis in relation to Engineering—Masonry and Reinforced Concrete—Steel Construction—Practical Problems in Construction—Bridge Engineering—Highway Construction—Hydraulics—Water Supply—Irrigation Engineering—Water Power Development—Sewers and Drains—House Drainage and Sanitation—River and Harbor Improvements.

AMERICAN SCHOOL OF CORRESPONDENCE
CHICAGO, U. S. A.
Mention Sci. Am., 12-5-08

Running a Car by Ear

The trained ear of the experienced automobilist instantly detects the superiority of MOBILOIL in the even, contented "pur-r" of the engine that tells the story of perfect lubrication. No matter what the type of gasoline engine or season of the year, MOBILOIL invariably gives perfect lubrication under all conditions.

VACUUM
MOBILOIL

is made in five different grades, each grade meeting the particular requirements of certain automobiles.

A valuable booklet on motor lubrication will be sent free on application. Lists every automobile made, and shows grade of MOBILOIL necessary for its perfect lubrication. Contains track records and other useful information.

MOBILOIL in barrels, and in cans with patent pouring spout, is sold by all dealers. Manufactured by

VACUUM OIL COMPANY
Rochester, N. Y.

WELL DRILLING Machines

Over 70 sizes and styles, for drilling either deep or shallow wells in any kind of soil or rock. Mounted on wheels or on sills. With engines or horse powers. Strong, simple and durable. Any mechanic can operate them easily. Send for catalog.

WILLIAMS BROS., Ithaca, N. Y.



Roth Electric Motors Dynamos

Special Electric Machinery

You cannot possibly do better than to use ROTH Electrical Machinery. Ask for information.

ROTH ELECTRIC MOTORS
27 So. Clinton Street Chicago, Ill.

DO YOU WANT GOOD INFORMATION CHEAP?

Write to us and we will refer you to a SCIENTIFIC AMERICAN SUPPLEMENT that will give you the very data you need.

SCIENTIFIC AMERICAN SUPPLEMENT articles are written by men who stand foremost in modern science and industry.

Each SCIENTIFIC AMERICAN SUPPLEMENT costs only 10 cents. But the information it contains may save you hundreds of dollars.

Write for a catalogue of SUPPLEMENT articles. It costs nothing.

Act on this suggestion!

MUNN & COMPANY
361 Broadway, New York

Railroad and Ferry Terminals, Coaling Plants, Steel Piers, Bridges



ST. GEORGE TERMINAL, STATEN ISLAND
BUILT FOR THE DEPARTMENT OF DOCKS AND FERRIES BY
THE SNARE & TRIEST CO., General Contractors
Main Office: 143 Liberty Street, New York
Cuban Office: La Leal Building, Havana

© 1908 SCIENTIFIC AMERICAN, INC

Nut lock, F. Matoushek 904,548
Nut lock, J. E. Dressler..... 904,606
Nut lock, D. J. Higginbotham..... 904,956
Nut lock, automatic, J. T. Clark..... 904,937
Nut or pipe wrench, D. Stewart..... 904,816
Nuts, bleaching, W. Hills, Jr..... 905,075
Oar, bow facing, Vessot & Cornu 904,577
Ores, treating metalliferous, F. R. Carpenter 904,838
Oven, drying, C. P. Bascom 905,047
Packaging machine, R. B. Polk..... 904,643
Packing, metallic, G. D. Rollins..... 905,103
Pads, composition of matter to be used in making copying, E. O. G. Winckler..... 904,590
Pail, Berry & Ricker 904,924
Paper making machine drive, J. H. Wallace. 904,582
Paper music sheet roller, L. B. Doman..... 904,762
Pasteurizing and sterilizing apparatus, C. E. Hinman 904,615
Pasteurizing apparatus, A. A. Pindstofte.... 904,986
Petticoat, E. G. Murray 904,635
Phonograph automatic stop attachment, E. B. Hyatt 904,875
Phonograph reproducer, Dyer & Lewis..... 904,853
Phonograph reproducer, F. D. Lewis..... 904,884
Phonograph reproducer, D. Holden..... 904,959
Phonograph reproducer, P. Weber..... 905,033
Photographic camera, folding, F. A. Brownell 905,122
Pianoforte action, W. W. Wallace..... 904,904
Picker stick check, T. Boucher 904,753
Picture hanging device, G. A. Francis..... 904,690
Pin. See Clothes pin.
Pin board, E. L. Besse..... 904,598
Pipe coupling, flexible, J. Henderson..... 904,534
Planing machine side head jointer, Blood & Osteman 905,051
Planing machines, boring mills, and the like, clamping mechanism for, G. H. Benzon, Jr. 904,922
Plate casting machine, stereotype, H. F. Bechman 904,748
Plate making apparatus, pattern, P. Bonvellain, reissue 12,886
Pliers, C. Hiller 905,074
Plow, T. M. Manning 904,546
Plow, C. Marvin 904,792
Plow and sleigh, combined snow, N. A. Olsen 904,637
Plow, wheeled, W. E. Johnson 905,079
Pocket, safety, J. Sanfason..... 904,565
Polishing lead, F. Pierce 904,805
Poultry water and grain receptacle, M. L. Weldon 904,584
Power hammer, Hamilton & Pierce..... 904,528
Press folder, cotton, R. M. Jordan..... 904,617
Press for paper making, feltless wet, F. M. Chapman 905,053
Pressure gage, differential, W. J. Crowell, Jr. 904,511
Printer's composing stick, T. Draper..... 905,060
Printer's implement, W. N. Swain..... 904,572
Printer's quoin, C. L. Dingens 904,849
Printing apparatus, electrical, M. T. Weston 904,743
Printing telegraph receiver, J. Burry..... 905,126
Propelling gear and other apparatus on shipboard from air used for facilitating the propulsion, protecting, G. Quanonne 904,992
Pulley, E. W. Cunningham 904,685
Pulley, C. M. Swanson 905,019
Pulley, adjustable guide, E. Croasdale..... 904,757
Pump, air compressing, S. Dahlberg..... 904,940
Pump, centrifugal, G. Hauff 904,533
Pump, double suction, F. W. Baines..... 905,046
Pump for mine shafts, Heidecke & Lellau.. 904,870
Pump, hydraulic, J. W. Nelson..... 904,557
Pump, pressure, L. C. Trent..... 905,024
Radiator, C. E. Safford 904,729
Rail bonds, manufacture of, W. H. Williams 904,663
Rail fastener, J. A. Widner 904,824
Rail joint, B. Ohnimus 904,802
Rail joint, Schonlau & Heinrich..... 904,812
Railway alarm, automatic, N. Lang..... 904,971
Railway, overhead electric, F. M. Frederick, 904,525, 904,526
Railway safety appliance, A. M. Jones.... 905,080
Railway tie, concrete, J. F. Wellep..... 905,035
Railway tie, metal resilient, G. Mackay... 904,629
Razor, J. A. Reams, reissue 12,882
Razor frame, safety, B. Gallinek 904,861
Receptacle, M. A. Adams 904,745
Refrigerator, C. Tettenborn 905,118
Revolvers, pistols, or the like, safety lock for, J. Tambour 905,020
Riveting machine, W. T. Sears 905,109
Road roller scraper, Henn & Farquhar..... 905,073
Rock crusher, J. R. Fogg 904,946
Rope fastener, J. B. Anderson..... 904,747
Rope tie, O. Cooper 904,843
Rotary engine, C. A. Bender 904,749
Rotary engine, Hoard & Paine..... 904,781
Rotary switch, F. J. Russell 904,897
Rubber footwear, E. A. Saunders 905,105
Rubbing post, J. W. Coffman 905,055
Sash weight mold, S. Dyer 904,519
Sash weights, molding, Hoehn & Gross..... 904,958
Sash, window, Fingal & Fabrin..... 905,064
Sawhorse, O. Poitras 904,988
Sawmill dog, A. V. Wineman..... 905,040
Sawmill power set works, D. C. Prescott... 904,806
Scoop, ash, R. B. Clement..... 904,756
Scoop board, A. Lombardo 905,086
Screw propeller, C. Steiger 904,656
Seal, bottle, C. Winter 904,825
Seal lock, H. Elmblad 904,607
Semaphore mechanism, electrically operated, J. F. Webb, Jr. 904,741
Sewing machine, F. English 904,854
Sewing machine, bale or bag, A. von Hasperg 904,531
Sewing machines, feed point or awl for shoe, E. E. Currier 904,004
Shade and curtain bracket, combination, W. H. Bantly 904,920
Shade fixture, adjustable window, J. D. Perrott 904,641
Shade fixture, window, A. Holmes 904,536
Shade holder, J. H. Dale 904,761
Shears holder, H. L. Kocher 904,968
Sheet metal, rolling, C. B. Cushwa 904,605
Ship, aerial, F. Bollhorn 904,930
Shoe display form, C. F. Partridge..... 904,639
Shoe heel-and toe beating up machine, J. O'Connell 905,094
Shoe rack, W. Cartier 904,755
Shoe tree or form, S. M. Hamblin..... 904,775
Shuttle, S. Kendrick 904,538
Signal. See Train order signal.
Signal apparatus, E. B. Dalley..... 904,512
Signaling system, G. Babcock 904,918
Signaling system, electric railway, Y. Burgess 904,834
Skate tire, roller, I. Wanta 905,031
Skirt holder, H. H. West 904,742
Slicing machine, W. M. Miller..... 904,549
Smoke and dust collector, W. F. Diem.... 904,941
Snap fastener, W. B. H. Dowse 904,517
Soap and making soap, C. Ellis 904,520
Sole, ventilating, H. Otterstedt..... 904,891
Speed indicator and recorder, F. F. Uehling. 904,660
Speed indicator, synchronous, A. E. Griffin. 904,693
Spike, L. L. Sessagrant 904,814
Spoon, cutting, H. L. McCoy 904,553
Sprayer, hand, E. R. Richards..... 905,102
Stake, supporting, J. O. Ford 904,769
Stamp affixing machine, Gilbert & Tabler.. 904,948
Stamping machine, box, R. Schilling..... 904,811
Starting device, A. E. Nelson..... 904,799
Steam heating system, C. T. Ammon..... 904,499
Stirring mechanism, J. J. Stehling..... 904,655
Stone, artificial, S. W. Berglund 904,923
Stove burner, gas, J. T. Scollard 904,813
Street number indicator for houses, A. Goldbard 904,773
Surgeon's needle holder, A. F. Sether..... 905,007
Surgical appliance, M. R. Cutting..... 904,760
Suspender attachment, J. Hauser..... 904,955
Table leaf support, Tritch & McCauley..... 905,026
Tack driver, D. A. Sawyers 905,004
Talking machine sound box, A. Fischer.... 904,523
Talking machine sound box, A. Junod..... 905,082
Tank seamless lining, Burr & Gibbs..... 904,835
Telegraph repeater, L. B. Cecil..... 904,936
Telegraph system, S. D. Field 904,768
Telephone annunciator and jack, H. Tideman 904,903
Telephone system, H. G. Webster..... 904,583
Telephone system, F. W. Dunbar..... 904,850
Temperature indicating instrument, A. N. Ozias 904,558
Temporary binder, H. H. Liscom..... 904,543
Thread finishing machine, silk, D. H. Haywood 904,869



PACIFIC COAST EXTENSION—CHICAGO, MILWAUKEE & ST. PAUL RAILWAY

Business Chances in New Towns

Would you make a business investment in a prosperous new territory if you were sure of success?

There are countless openings at the present time for men with limited capital in the new towns in the Dakotas, Montana, Idaho and Washington, along the **PACIFIC COAST EXTENSION** of the

Chicago Milwaukee & St. Paul Railway

This new line is now open as far west as Butte, Montana. Within the next year the entire line will be completed and in operation to Seattle and Tacoma, Washington.

Investigate the openings. The persons who locate in this new country to engage in commercial or other lines while its development is in its infancy, will be well repaid.

DESCRIPTIVE BOOKS FREE

F. A. MILLER
General Pass. Agent
CHICAGO

GEO. A BLAIR
General Eastern Agent
381 Broadway, NEW YORK

MEDAL OF HIGHEST AWARD
JAMESTOWN EXPOSITION
Add TONE to Your Stationery in the OFFICE, BANK, SCHOOL or HOME by using only Washburne's Patent



"O.K" PAPER FASTENERS

There is genuine pleasure in their use as well as Perfect Security. Easily put on or taken off with the thumb and finger. Can be used repeatedly and *"they always work."*

Made of brass, in 3 sizes and put up in brass boxes of 100 fasteners each.

Handsome Compact. Strong. No Slipping, NEVER!

At all Stationers Send 10c for sample box of 50, assorted sizes. Illustrated booklet free.

Liberal discount to the trade.

THE O. K. MFG. CO. Dept. X Syracuse, N. Y No 1B

A Clean Shave

Your new blades all need stropping before using. Not one in ten comes sharp enough for a clean shave.

Why scrape your face with dull blades, or continue to throw away money for new ones, when the **Gaylor Automatic Stropper** will resharpen all your dull blades in a few moments, giving them a hairsplitting edge better than new. The motion is automatic, no practice required, a child can use it. It is the only stropper in the world that successfully sharpens double-edge blades.

PRICE $1.00

In case with barbers' genuine Horse Hide Strop, $2.00

Order through your dealer. Or will send postpaid on receipt of price. Be sure to state for what make of Blade. Money willingly refunded if not entirely satisfactory. Write for descriptive circular. Agents wanted.

L. B. GAYLOR, Allston, Mass.

First and Original Motor Buggy
$250 "SUCCESS" AUTOMOBILE

Practical, durable, economical and absolutely safe. A light, strong, steel-tired Auto-Buggy. Suitable for city or country use. Speed from 4 to 40 miles an hour. Our 1908 Model has an extra powerful engine, patent ball-bearing wheels; price, $275. Also 10 h. p., $400. Rubber Tires, $25.00 extra. Write for descriptive literature. Address SUCCESS AUTO-BUGGY MFG. CO., Inc., St. Louis, Mo.

Don't Throw it Away
Does Your Granite Dish or Hot Water Bag Leak

USE **MENDETS** A PATENT PATCH

They mend all leaks in all utensils—tin brass, copper, graniteware, hot water bags etc. No solder, cement or rivet. Any one can use them; fit any surface; two million in use. Send for sample pkg. 10c. Complete pkg. assorted sizes, 25c postpaid. Agents wanted. Collette Mfg. Co., Box 91 C Amsterdam, N. Y.

DO YOU LIKE TO DRAW?
That's all we want to know

Now, we will not give you any grand prize—or a lot of free stuff if you answer this ad. Nor do we claim to make you rich in a week. But if you are anxious to develop your talent with a successful cartoonist, so you can make money, send a copy of this picture, with 6 cents in stamps for portfolio of cartoons and sample lesson plate and let us explain.

The W. L. EVANS SCHOOL OF CARTOONING
842 Garfield Bldg., Cleveland, Ohio

Patent and Manufacturing Rights



on invention for clearing clogged closets, washbowls, sinks, laundry bowls, etc. Article retails for $4. One application prevents tearing out expensive plumbing and more than saves initial cost. Owner has other large businesses and cannot push this exclusively.

Article now selling. Send for booklet and full information.

Langer Mfg. Co.
202 Colonial Arcade Cleveland, Ohio

THE INTERNAL WORK OF THE Wind. By S. P. LANGLEY. A painstaking discussion by the leading authority on Aerodynamics, of a subject of value to all interested in airships. SCIENTIFIC AMERICAN SUPPLEMENTS **946** and **947**. Price 10 cents each, by mail. Munn & Company, 361 Broadway, New York City, and all newsdealers.

Architects and Builders should investigate
EVANS "CRESCENT" EXPANSION BOLTS
With Double End Grip Expansion

Constructed on new lines. Grip at both ends and on all sides. Cannot work loose. Send for catalogue and samples screwed into blocks of wood or stone.

Agencies in all large cities. Patentee and sole manufacturer
F. H. EVANS, 596-614 Kent Ave., Brooklyn, N. Y.

Why It Pays to Buy Sea Lion Leather Belting

First cost and maintenance cost of belts are two very different things. That's why you save money getting Sea Lion Belting. It costs you a trifle more to begin with, but it lasts enough longer to more than make up for the initial cost.

If you require a belt that will stand live steam, water conditions such as leaking roofs, bursting pipes or flooded wheel pits and the trying humidity of a warm climate—in fact any of the conditions that so quickly knock out an ordinary belt—

SEA LION
Guaranteed Waterproof
Leather Belting

Is the **only kind** you can afford to buy.

We cut it from the choicest oak tanned hides on the market—using only center stock. Every process in the making is done with utmost thoroughness and care. The laps are joined by our own process of cement under 3,000 lbs. hydraulic pressure to the square inch, so that you could tear the leather sooner than separate the joints by any tensile strain. We sell it under a guarantee equally as liberal to the user as we place on our **Oak Tanned Reliance Leather Belting** and that means every foot is guaranteed and that we will repair or replace any belt defective in stock or workmanship; and in addition to the above we guarantee the laps against opening up on account of either water or steam.

We are also manufacturers of Reliance, Sterling, Imperial and Dynamo brands of belting—which are just as good value for different purposes. Write us about your belt needs. We will advise you and send you a book on belting.

Chicago Belting Co.
24 So. Green St., Chicago
Branches—New Orleans, Philadelphia, Portland, Ore.

ROTARY PUMPS AND ENGINES Their Origin and Development.—An important series of papers giving a historical resume of the rotary pump and engine from 1588 and illustrated with clear drawings showing the construction of various forms of pumps and engines. 38 illustrations. Contained in SUPPLEMENTS **1109, 1110, 1111.** Price 10 cents each. For sale by Munn & Co. and all newsdealers.

The INVENTOR'S UNIVERSAL EDUCATOR

TELLS ALL ABOUT PATENTS, HOW TO SECURE THEM. HAS

600 MECHANICAL MOVEMENTS also 50 PERPETUAL MOTIONS

Every inventor should have a copy. Price **$1.00** by mail.

F. Dietrich · Ouray Bldg. Washington, D. C.

© 1908 SCIENTIFIC AMERICAN, INC

Classified Advertisements

Advertising in this column is 75 cents a line. No less than four nor more than ten lines accepted. Count seven words to the line. All orders must be accompanied by a remittance. Further information sent on request.

READ THIS COLUMN CAREFULLY.—You will find inquiries for certain classes of articles numbered in consecu ive order. If you manufacture these goods write us at once and we will send you the name and address of the party desiring the information. There is no charge for this service. **In every case it is necessary to give the number of the inquiry.** Where manufacturers do not respond promptly the inquiry may be repeated.

MUNN & CO.

BUSINESS OPPORTUNITIES.

WANTED.—Man with small capital to take charge of territory for merchandising business; write for particulars. Pope Automatic Merchandising Company, Corn Exchange Bank Building, Chicago.

Inquiry No. 8687.—Wanted to buy motor plows.

BUSINESS BOOK FREE. Tells how you can secure the actual working plans, the money-making systems, schemes and short cuts of 112 great, big business men—to increase your salary—to boost your profits. Book is free. System, Dept. 177-4 Wabash Ave., Chicago.

Inquiry No. 8735.—For parties making a still for the purpose of extracting alcohol from saw-dust.

CAPITAL WANTED to manufacture automobile and marine engine accessory of established reputation. A competent engineer has machinery and contracts pending to the value of $50,000 subject to possibilities of delivery. Sales guaranteed. Exceptional opportunity for one or more parties having $5,000 or less to invest. Address C. F. W., Room 508, 1276 Broadway, New York.

PATENTS FOR SALE.

FOR SALE.—Turner fireproof shutter, U.S. Patent No. 896,176. A device constructed of two thicknesses of galvanized sheet steel, corrugated and built over a tee-iron frame. Light, durable, attractive and cheap, and easy to manufacture. Eagle Cornice and Sheet Metal Works, Tampa, Florida.

Inquiry No. 8779.—For parties manufacturing gas, gasoline, steam engines and boilers; also packing and mineral wool, steam supplies, iron and lead pipe, power transmission machinery and steam fitters' tools.

FOR SALE.—Patent No. 891,096.—A machine for separating ground peas from the vines. For information address William S. Pope, Sneads, Florida.

Inquiry No. 8787.—For parties who manufacture cat-gut.

FOR SALE.—Complete shipping tag, wire or string fastening attached, always ready; also roof scaffold bracket, secure without nails. G. C. Carman, St John, N.B.

Inquiry No. 8842.—Wanted to buy annealed glass.

FOREIGN PATENTS for meritorious and valuable inventions negotiated upon a contingent basis. Absolutely no fees accepted. References given and required. L. Henry, 141 Broadway, New York.

Inquiry No. 8844.—Wanted to buy inkstands.

PATENTS WANTED.

WANTED.—Information regarding good patent which would be money maker. Only inventor, who wishes to sell outright or on royalty basis, need answer. Give price and brief description. L, Darbyshire, Box 390 A, Rochester, N. Y.

Inquiry No. 8846.—Wanted to buy an electric butcher hand saw.

HELP WANTED.

LOCAL REPRESENTATIVE WANTED.—Splendid income assured right man to act as our representative after learning our business thoroughly by mail. Former experience unnecessary. All we require is honesty, ability, ambition, and willingness to learn a lucrative business. No soliciting or traveling. This is an exceptional opportunity for a man in your section to get into a big paying business without capital and become independent for life. Write at once for full particulars. Address The National Co-operative Real Estate Company, Dept. 378, Washington, D. C.

Inquiry No. 8847.—Wanted laundry tubs.

MEN WANTED QUICKLY by big Chicago mail order house to distribute catalogues, advertise, etc. $25 a week. $60 expense allowance first month. No experience required. Manager, Dept. 73, 385 Wabash Ave., Chicago.

Inquiry No. 8848.—Wanted to buy rust proof metal for parts of wash tubs.

FOR SALE.

A GRAY IRON FOUNDRY, fully equipped and in operation, on account of the death of the managing partner, is for sale. The foundry is 50 x 150 ft., solid brick walls and iron truss roof, bay on the east side, 15 x 24 ft., used for core room, an addition on the west side 30 x 80 ft. with brick walls, partitioned off for cupola room, motor room, cleaning and shipping room. A brick pattern house, 30 x 50 ft., a frame office, 4 acres of land and a side track, located on the Soo Line, Minneapolis, Minn. For particulars address Mr. W. L. Chapin, attorney for the administratrix, New York Life Bldg., St. Paul, Minn.

Inquiry No. 8849.—Wanted addresses of Canadian makers of rifle sights.

LISTS OF MANUFACTURERS.

COMPLETE LISTS of manufacturers in all lines supplied at short notice at moderate rates. Small and special lists compiled to order at various prices. Estimates should be obtained in advance. Address Munn & Co., List Department, Box 773, New York.

Inquiry No. 8850.—Wanted to buy machinery for making canvas gloves or mitts.

A LIST OF 1,500 mining and consulting engineers on cards. A very valuable list for circularizing, etc. Price $15.00. Address Munn & Co., List Department, Box 773, New York.

Inquiry No. 8851.—Wanted to buy machine for weaving wooden lath and wire together.

MISCELLANEOUS.

UNITARIAN LITERATURE, including sermons and weekly publications, sent free, on application to Miss Peck, 106 George Street, Providence, R. I,

Inquiry No. 8852.—Wanted to have made a concave brass or copper reflector with focus of four or five feet.

Inquiry No. 8856.—Wanted a machine or grinder for reducing soft wood refuse to a fine dust.

Inquiry No. 8858.—Wanted to buy comb cleaning machine.

Inquiry No. 8859.—Wanted to buy steel gray paint suitable for gasoline engines.

Inquiry No. 8860.—Wanted to buy machinery for grinding, washing and drying gum chicle.

Inquiry No. 8862.—Wanted to buy a feather pillow ventilator.

Inquiry No. 8863.—Wanted to buy machine to separate pecan nuts into sizes and dust the dirt off.

Inquiry No. 8864.—Wanted manufacturers of mechanical novelties.

Inquiry No. 8865.—Wanted to buy fireless cookers.

Inquiry No. 8867.—Wanted to buy plant for dry cleaning.

Inquiry No. 8868.—Wanted to buy nickeloid for buttons.

Inquiry No. 8869.—Wanted to buy straw making machinery.

Inquiry No. 8870.—Wanted to buy incandescent kerosene burners.

Inquiry No. 8871.—Wanted to buy chimneyless kerosene burners.

Inquiry No. 8872.—Wanted to buy a ball nozzle puzzle.

Inquiry No. 8873.—Wanted to buy a portable shower bath.

Inquiry No. 8874.—For manufacturers or importers of metal known as "Kaiserium."

Inquiry No. 8875.—For makers of chain, also forged iron hinges.

Inquiry No. 8876.—Wanted to buy wood rolls 1¼ inches in diameter and 8 inches long, with iron journals ⅛ inch in diameter, suitable for wringers.

Inquiry No. 8877.—For manufacturers of convex glass for pictures.

Inquiry No. 8878.—For factory making paper out of peat.

Inquiry No. 8879.—For the manufacturers of steam air pumps such as are used on the Conrad steam cars.

Inquiry No. 8880.—For manufacturers of portable shower baths.

Inquiry No. 8881.—Wanted to buy about forty second-hand enclosed arc lamps for direct 6½ ampere current.

Inquiry No. 8882.—Wanted to buy a second-hand ½ horse power, single phase induction motor 105 volt, 60 cycle.

Inquiry No. 8883.—Wanted to buy new or second-hand complete carbide of calcium plant.

Inquiry No. 8884.—Wanted to buy second-hand "Gammeter Multigraph."

Tie making machine, wall, J. H. Rau..... 904,563
Tile molding apparatus, glass, E. D. Mooney 904,795
Tire tightener, P. & M. J. Rau..... 904,993
Tires, composition for preventing leakage of air through puncture in pneumatic, Rogers & Myers..... 904,895
Tobacco pipe, J. Monson..... 904,633
Tobacco stripper, T. P. Ford..... 904,770
Tobacco substitute, masticable, C. Ellis.... 904,521
Tool case, hand, C. Madeira..... 904,545
Tool handle wedge, J. W. Hair..... 905,069
Tool holder, C. E. Bown..... 904,504
Tool holder, H. Vogel..... 904,579
Tool, impact, C. B. Richards....904,724 to 904,726
Tool, pneumatic impact, G. L. Badger..... 904,827
Tool, punching, T. McGrath..... 904,714
Tool, staking, F. R. Cunningham..... 904,847
Tool, stone working, Greve & Richards.... 904,692
Tooth, artificial, F. D. Case..... 904,601
Toy, J. Lexow..... 905,085
Train order signal, L. H. Van Zandt..... 905,120
Transfer, J. W. Hentz..... 904,778
Transom operator, G. H. Lawrence..... 904,973
Trap, M. Engstrom..... 904,608
Trap, B. A. Martinson..... 904,706
Trench digger carrier, F. R. Batchelder, 904,596, 904,597
Trolley and telegraph pole, combination, J. Hackett..... 904,952
Trolley wheels from jumping, device to prevent, W. O. Lane..... 904,541
Truck, car, E. H. Benners..... 904,670
Truck, transfer, G. P. Baldwin..... 904,919
Tub trap, rinse, W. L. Koenig..... 904,539
Turn table, piano, Sullivan & Ring..... 905,018
Twine holder, J. M. & R. E. Pinegar..... 904,722
Typewriting machine, E. E. Barney..... 904,669
Typewriting machine, W. C. Farnum..... 904,688
Typewriting machine, J. Felbel..... 904,689
Typewriting machine, H. W. Merritt..... 904,708
Typewriting machine, H. L. Wagner..... 904,737
Typewriting machine, J. Oppenheim..... 904,803
Typewriting machine, H. C. Ferguson, 904,857 to 904,859
Typewriting machine, L. A. McKeever..... 904,982
Typewriting machine, H. H. Steele..... 905,013
Typewriting machine, J. C. McLaughlin..... 905,091
Umbrella repairing device, E. H. Stoddard.. 905,016
Urinary apparatus, V. D'Incognito..... 904,942
Valve, emergency, O. Penn..... 904,985
Valve for hydrocarbon lighting systems, M. W. Pitner..... 904,987
Valve, piston, Christman & Johnson..... 904,839
Valve stuffing box, engine, J. J. MacMulkin 904,790
Vehicle, J. K. Kendrick..... 904,703
Vehicle cushioning device, Carpenter & Kissell..... 904,837
Vehicle gear, J. D. Weekes..... 904,822
Vehicle, motor, W. Y. Donshoe..... 904,687
Vehicle, self-propelled, C. Richter..... 904,998
Vehicle transmission gear, motor, H. T. Hansen..... 904,868
Vehicle trucks, suspension of railway and tramway, E. Peckham..... 904,720
Vehicle wheel, M. Joachimi, Sr..... 904,876
Vending apparatus for cigarettes and the like, coin controlled, J. Sahlin..... 905,003
Vending machine, R. J. Morrison..... 904,798
Ventilating device, J. W. Farley..... 904,767
Ventilator, H. Shlamowitz..... 905,008
Vibratory apparatus for ear treatment, E. Meyer..... 904,632
Wagon, dumping, A. Maxwell..... 904,793
Wall, partition, W. J. Perkins..... 905,096
Washing machine tubs, wringer box or tray for, W. H. Voss..... 905,028
Watch, stem winding and setting, W. E. Porter..... 904,989
Water closet bowl, C. H. Rollins..... 904,896
Water elevator, A. Haas..... 904,951
Water heater, L. D. Lovekin..... 904,627
Water motor, J. P. & H. P. Shevlin..... 904,567
Water supply system, J. T. Lemon..... 904,883
Watermobile, P. McDermott..... 904,713
Weed cutter and puller, combined, H. S. Wimmer..... 905,039
Weighing machine, T. S. B. Parnall..... 904,718
Welding machine, electric, W. M. Fulton... 904,771
Wells, grappling bucket for cleaning, A. Burrows..... 904,680
Wheel. See Car supplemental wheel.
Wheel grinder, band, P. A. Cazes..... 904,509
Wheel guard or fender, C. T. Moss..... 904,980
Wheels, antifriction thrust bearing for, W. J. Trevessick..... 904,575
Whip snap fastener, P. E. Gold..... 904,610
Whirlpool, artificial, W. W. Devore..... 904,848
Winding, spinning, and twisting machines, bobbin and cop builder for, J. S. Berard 905,049
Wire bed bottom fabric, C. H. Halstead, 904,611, 904,612
Wire bracket or holder and insulator, I. L. Edwards..... 904,945
Wire clamp or grip, Glass & Vint..... 904,863
Wire fastener, A. W. Burbury..... 904,506
Wire stretcher, W. C. Richardson..... 904,997
Wire stretcher and wagon jack, combined, E. G. Boyes..... 905,052
Wiredrawing block, H. B. Humphrey..... 905,077
Wiredrawing machine, C. A. Carlson..... 904,836
Wood, apparatus for use in treating, S. S. Williams..... 904,589
Wrench, T. W. Harber..... 904,954
Wrench, J. G. Swallow..... 905,116
Wrench and tool holder, J. D. Heck..... 905,070
Yoke center, neck, H. H. Bromley..... 904,934

TRADE MARKS.

Abrasive materials, certain, Marshall-Wells Hardware Co..... 71,386
Beer and ale, W. Albrecht..... 71,368
Belting, machinery, New Jersey Car Spring & Rubber Co..... 71,476
Beltings, hose, and packings, E. C. Atkins & Co..... 71,464, 71,465
Bib and faucet handles, self-closing, H. Mueller Manufacturing Co..... 71,492
Blacking or dressing surfaces, preparations for, G. H. Johnson..... 71,381
Boots and shoes, leather, L. J. Evans..... 71,435
Boots and shoes, leather, United Shoe Machinery Co..... 71,456 to 71,458

ESTABLISHED 1828 — **I. P. MORRIS COMPANY** — INCORPORATED 1876
PHILADELPHIA, PA.
STEAM AND HYDRAULIC TURBINES OF SPECIAL DESIGN. CENTRIFUGAL PUMPING MACHINERY. SPECIAL HEAVY MACHINERY.
LAND AND MARINE BOILERS
BRASS AND BRONZE CASTINGS. IRON CASTINGS UP TO 50 TONS

Superb Holiday Gifts for Gentlemen
ELKIN PIPE
Formerly called "A-C" (Anti-Cancer)

Prices
Popular grade and brier nickel mounting - - $1.50
Special selected brier, solid silver mounting - - 2.50
Virgin brier (cased), solid silver mounting - - 5.00
Meerschaum (cased), solid silver mounting - - 15.00
Meerschaum (cased), solid gold mounting - - 25.00

No Saliva in Stem
No Poison in Mouth
Burnt Tongue
Absolutely Impossible
Free Cool Dry

FOR HOME USE
Extra cooler to be interserted between bowl and stem given free with each pipe.



Price $1.50 prepaid

Discounts to Old Customers
To purchasers of 1904 - - 25 per cent
" " 1905 - - 20 "
" " 1906 - - 15 "
" " 1907 - - 10 "

ELKIN PIPE COMPANY
Dept. A 1 — 25 W. 42d St., N. Y. City

Gas Engine & Power Co. and Chas. L. Seabury & Co.
(CONSOLIDATED)
MORRIS HEIGHTS, NEW YORK CITY
DESIGNERS, YACHT BUILDERS and ENGINEERS

STEAM YACHTS
STEAM BOILERS
STEAM ENGINES
NAPHTHA ENGINES



MOTOR LAUNCHES
STEAM LAUNCHES
NAPHTHA LAUNCHES
SAILING YACHTS

SPEEDWAY GASOLENE ENGINES
SHALLOW DRAUGHT BOATS A SPECIALTY
VESSEL CONSTRUCTION WOOD OR STEEL
Send 10c. Stamp for Catalogue

The National Aeronautical Magazine

Keep In Touch With Aeronautic "Doings"

Read "FLY." It deals with things higher up. Brim full of interesting articles relative to mechanical flight.
Send a dollar to Lawson & Kelley, Publishers, Betz Building, Philadelphia, for a year's subscription, which includes the November Number and a cloth-bound copy of the novel, "Born Again," Free of Charge.

DO YOU HAVE KNIVES TO GRIND, SILVER TO POLISH, SMALL TOOLS TO OPERATE, WASHING MACHINES OR WRINGERS TO RUN?
LET THE RED DEVIL
WATER MOTOR DO YOUR WORK
Attached to any water faucet will develop up to 3 Horse Power according to size of pipe and water pressure. Only perfect small motor made. Improved bucket wheel construction. **6-inch Motor** for Mechanics, Butchers, Grocers, small tools and **Washing Machine**, ¼ H. P. on ½ inch pipe, 80 lbs. water pressure. Net price **$5 cash with order.**
4-inch Motor for grinding, polishing, fans, sewing machine, Doctors, Dentists, Druggists. Net price Motor with Pulley $2.50; with emery, buffing wheel, silver polish and pulley **$3 cash with order.**
Money back for any reason. Send for illustrated catalog. Order your motor before Xmas from dealer or from us.
DIVINE WATER MOTOR CO.
DEPT 12 UTICA, N.Y.

Load your blasts with
Aetna Dynamite
And Fire with
LION FUZES
Manufactured by
The Aetna Powder Co.
143 Dearborn St.
Chicago :: ::

A Home Made Alternating Current Motor

READ SUPPLEMENT 1688 for a good, clear article by F. E. WARD, E E, on the making of a ⅛ horse power alternating current motor. The motor can be constructed by anyone of ordinary skill in the use of tools who has access to a screw-cutting lathe with a swing of 9 inches or more. The motor is designed to run on the 100 to 120 volt, 60-cycle, single-phase alternating current circuit, now in widespread use for the lighting of dwellings. The motor will drive a 16-inch brass fan, a small lathe, or a 50-watt dynamo for generating direct current for charging storage batteries, and in fact will do almost any kind of work that can be done by one-man power. Order from your newsdealer or from

MUNN & COMPANY, 361 Broadway, New York, N. Y.

© 1908 SCIENTIFIC AMERICAN, INC

Steel Structures

RIVERSIDE BRIDGE CO.

MARTINS FERRY, O.
Opposite WHEELING, WEST VA.

ENGINEERS
MANUFACTURERS
CONTRACTORS



The Dean removing scale from the tube of a water tube boiler.

STOP THOSE BOILER ROOM TROUBLES

Increased fuel bills, loosened and burned-out tubes, curtailed boiler capacity are due to scale.

The Dean Boiler Tube Cleaner

removes scale from the tubes of water tube or fire tube boilers and condensers. Loosens the scale by rapid vibration. No scale too hard or tenacious for it to remove. Cleans 10 to 30 tubes an hour. Removes the soot in the same operation. Operated by steam or air. It is the one tried, proven and perfect scale remover. In use in over 8,000 plants. References in all countries. Guaranteed to pay for itself in six months' use. Write for circular No. 130.

THE WM. B. PIERCE CO.
319 Washington Street, Buffalo, N. Y.



The Dean removing scale from the tube of a return tubular boiler.

AN AUTOMATIC TOOL

Do you remember when you first learned to write with a pen? It wasn't such an easy matter. The pen point dug into the paper and caught, and scratched, and spluttered, and daubed you all up.

Even today you have to be careful unless you use a "Cannon Ball." That is the new speed pen for busy people. It is made of an aluminum alloy, smooth as gold, but with the right resilience. It cannot corrode. It will not splutter. Writes on anything.

Samples sent on request.

A. L. SALOMON & CO.
341 Greenwich St., New York

CANNON BALL PEN

TOOLS

Of our own manufacture. Automatic Screw Drivers and Drills, Hand Drills, Breast Drills, Bench Drills, Chain Drills, Bench Lathes, Hack Saws and many other labor-saving devices.

INSTRUMENTS OF PRECISION

Micrometers, Calipers and Dividers, Steel Rules, Protractors, Precision Lathes, and other like articles whose quality we absolutely guarantee.

Catalog Free.

Goodell-Pratt Co., Greenfield, Mass.

Make Your Own Fertilizer

at Small Cost with
WILSON'S PHOSPHATE MILLS

From 1 to 40 H. P. Also **Bone Cutters**, hand and power, for the poultrymen; grit and shell mills, farm feed mills, family grist mills, scrap cake mills. Send for our catalog.

Wilson Bros., Sole Mfrs., Easton, Pa.

Boots, shoes, and slippers, F. Valdes & Co.	71,459
Butter, Watson & Aven	71,417
Cantaloups, H. H. Hawkins	71,377
Carbon paper and typewriter ribbons, Mittag & Volger	71,447
Cement, aluminium pipe, A. Wilhelm Co.	71,463
Cigarettes, cigars, and tobacco, Maspero Freres	71,493
Cigars, P. Alvarez & Ca.	71,494
Cigars, cheroots, and cigarettes, Cayey-Caguas Tobacco Co.	71,490
Cleaning and renovating apparatus and parts thereof, Electric Renovator Manufacturing Co.	71,375
Cloth, rubber, and leather shoes, National Shoemakers	71,450, 71,451
Coffee, blended, Aroma Coffee Co.	71,370
Coffee, blended, R. C. Williams & Co.	71,418
Collars, Hall, Hartwell & Co.	71,442, 71,443
Cotton piece goods, printed, Neuss, Hesslein & Co.	71,452, 71,453
Cutlery and tools, certain, Marshall-Wells Hardware Co.	71,387
Cutlery, certain, Stephen Richard Co.	71,415
Dental cream, Colgate & Co.	71,432
Dolls, rag, Bach Bros. & Katzenstein	71,372
Dyspepsia remedies, mother Seigel's Syrup Co.	71,448
Earthenware, porcelain, majolica, or clay articles, Wachtersbacher Steingutfabrik.	71,487
Foods, certain, Kahn-Beck Co.	71,382
Foods, certain, Richardson & Robbins Co.	71,412
Fruits and vegetables, canned, H. K. Fooks & Co.	71,376
Fruits, preserved, A. A. Kearns	71,383
Grease, axle, Belknap Hardware and Manufacturing Co.	71,424
Gum, chewing, C. H. Stewart	71,416
Hammers, trip, L. Mayer	71,391
Hats and caps of cloth, wool, felt, fur, and straw, Keith Brothers & Co.	71,445
Hats, felt, Fay-Gorman Co.	71,437
Hats, straw, G. George	71,440
Headlights, R. E. Dietz Co.	71,477
Hose, fabric, Eureka Fire Hose Manufacturing Co.	71,467
Hosiery, A. B. Andrews Co.	71,419 to 71,421
Hosiery, Bell Hosiery Co.	71,425
Hosiery, Burson Knitting Co.	71,429, 71,430
Hosiery, Davis Hosiery Mills	71,433
Knives and steels, butchers', F. Dick	71,573
Lamps, gas burning vehicle, R. E. Deitz Co.	71,478, 71,480
Lamps, oil burning, R. E. Dietz Co.	71,479
Laxative medicines, Wm. H. Clark	71,431
Leather and fabric gloves, Ben Strauss Co.	71,427
Liquor known as "Mezcal Tequila," Mezcal Tequila Distillery Co.	71,393
Locks and padlocks, door, Hibbard, Spencer, Bartlett & Co.	71,470
Matches, safety, J. A. Hunt	71,471, 71,472
Medicated salt for feeding to animals, B. R. Bonney	71,428
Medicines, certain, Dr. Bob Medical Co.	71,434
Metal articles, certain, Marshall-Wells Hardware Co.	71,389
Metal, babbitt, G. E. Sovereign	71,496
Milk, condensed, Mohawk Condensed Milk Co.	71,394
Non-intoxicating tonic made from malt and hops, R. L. Ihlenburg	71,378
Oil, olive, G. Ehrat	71,374
Oysters, canned, A. Booth & Co.	71,364
Pails, sheet metal, S. W. Milligan	71,475
Painters' materials, certain, A. Wilhelm Co.,	71,365 to 71,367
Pants, men's and youths', Sweet, Orr & Co.	71,454
Paper bags, Eagle Paper Co.	71,466
Paper, tarred and roofing felt, building and roofing, Maurice O'Meara Co.	71,474
Pen and pencil or lead holder, combined, F. R. Wells	71,461
Pens, fountain, Mabie, Todd & Co.	71,446
Pencils, leaf and colored, E. Faber	71,436
Perspiration absorbent, A. H. Hipple	71,444
Photographic developers and accelerators, H. S. Wellcome	71,460
Pills, laxative, Mother Seigel's Syrup Co.	71,449
Prints, certain, E. G. Soltmann	71,414
Pumps, lubricator, Phenix Lubricator Co.	71,397
Razor strops, R. W. Sunasack Co.	71,411
Remedy for diseases of the generative organs, Arent Bros. Medical Co.	71,422
Remedy for rheumatism, A. O. Fraley	71,439
Remedy for venereal diseases, Floyd Bros.	71,438
Rubber roofing, Seinscheimer Paper Co.	71,481
Rubber roofing, Hibbard, Spencer, Bartlett & Co.	71,649
Salmon, canned, A. Booth and Co.	71,488
Saws and machine knives, Simonds Manufacturing Co.	71,413
Screen like sections, certain hinged, E. O. Grover	71,468
Sheets and pillow cases, H. W. Baker Linen Co.	71,441
Sheets and sheeting, waterproof, E. A. Armstrong	71,423
Shells, loaded, Union Metallic Cartridge Co.,	71,483 to 71,486
Silks and cotton dress goods, broad, Rogers & Thompson	71,497
Silver plated knives, forks, and spoons, Marshall-Wells Hardware Co.	71,473
Soap, laundry, Procter & Gamble Co.,	71,398 to 71,410
Soap powder used for cleansing purposes, Larkin Co.	71,384
Solder, W. H. Finfrock	71,491
Sporting goods, certain, Marshall-Wells Hardware Co.	71,390
Squares, dividers, and levels, Marshall-Wells Hardware Co.	71,388
Suits, pants, and overalls, men's, Woods Manufacturing Co.	71,462
Suspenders, neckties, and scarfs, Tootle Campbell Dry Goods Co.	71,455
Syrup and molasses, compound of, refiners', Pacific Coast Syrup Co.	71,395
Tea, C. W. Antrim & Sons	71,371
Teas and coffees, W. McMurray	71,392
Toffee, Mackintosh's Toffee Co.	71,385
Toy whistles, J. F. Perey	71,396
Wagon and other vehicle springs, Indianapolis Bolster Spring Co.	71,379
Washing powder, naphtha, American Commercial Co.	71,369
Waste, J. Milton Hagy Waste Works	71,380
Whisky, straight bourbon, Rugby Distillery Co.	71,495
Whisky, straight rye, American Wine & Spirit Co.	71,489

LABELS.

"Anti-Dirt," for a scouring preparation, Anti-Dirt Co.	14,514
"Excellent Medicated Egg and Poultry Tonic," for egg and poultry food, M. N. Risser	14,513
"Farrell's Wedding Breakfast Brand Table Syrup," for a compound of corn syrup, cane syrup, and flavoring, Farrell & Co.	14,512
"Health Beer," for beer, Milwaukee-Waukesha Brewing Co.	14,511

PRINTS.

"Made to Eat Not to Keep," for candies, Huyler's	2,389
"Mosaic Back, Columbia Playing Cards," for playing cards, United States Playing Card Co.	2,391
"Purekind Salt Water Taffy," for salt water taffy, Atlantic City Candy Co.	2,390
"The Girl Question is Easily Solved," for candy, Huyler's	2,388

A printed copy of the specification and drawing of any patent in the foregoing list, or any patent in print issued since 1863, will be furnished from this office for 10 cents, provided the name and number of the patent desired and the date be given. Address Munn & Co., 361 Broadway, New York.

Canadian patents may now be obtained by the inventors for any of the inventions named in the foregoing list. For terms and further particulars address Munn & Co., 361 Broadway, New York.

DUMP CARS

WITH

TRADE LIVER MARK

ARE BEST

WRITE US

THE WM. J. OLIVER MFG. CO., Knoxville, Tenn.

Many Years of Careful Discrimination

In SELECTING itineraries,
In PROVIDING a steamer with unsurpassed facilities for cruising,
In EXTENDING to our patrons the greatest comforts and luxuries,
In ELIMINATING every feature which offered the slightest inconvenience, have made famous the

"Moltke" Orient Cruise

The S.S "Moltke" leaves New York January 28, 1909, on an 80-day cruise, visiting the
MEDITERRANEAN The HOLY LAND
The ORIENT EGYPT, Etc.
The cost is from $300 upward.

Also cruises by the twin-screw cruising S.S. "Oceana" to the
West Indies Venezuela
Spanish Main Panama Canal
Leaving Jan. 23 and Feb. 27. 30 days. $150 and up.

Send for illustrated booklet, describing these and other cruises.

Hamburg-American Line
Hamburg-American Bldg., 41-45 Broadway, New York
Boston Philadelphia Chicago St. Louis San Francisco

LET US BE YOUR FACTORY
STAMPINGS, MODELS, EXPERT WORK
THE GOOFF MACHINE AND STAMPING CO.
[illegible] Hamilton St., Cleveland, O.

INVENTORS We manufacture METAL SPECIALTIES of all kinds, to order; largest equipment; lowest prices. Send perfect sample for low estimate and best expert advice **FREE**
THE EAGLE TOOL CO., Dept. A, Cincinnati, O.

ICE MACHINES Corliss Engines, Brewers' and Bottlers' Machinery. THE VILTER MFG. CO., 899 Clinton St., Milwaukee, Wis.

SETS OF CASTINGS OF MODEL ENGINES
SEND 10c FOR 126 PAGE ILL. CATALOGUE.
ALSO TOOLS, GEAR WHEELS & PARTS OF MODELS
GOODNOW & WIGHTMAN
Removed to 183 Milk Street.

MODELS & EXPERIMENTAL WORK. Inventions developed. Special Machinery.
E. V. BAILLARD. 24 Frankfort Street. New York.

RUBBER Expert Manufacturers Fine Jobbing Work
PARKER, STEARNS & CO., 228-229 South Street, New York

DIE WORK MODELS TOOLS SPECIAL MACHINERY
NATIONAL STAMPING AND TOOL WORKS
153-159 S. Jefferson Street, Chicago, Ill.

ELECTRIC GOODS.—Big Cat. 3 cts. Want Agents. Ohio Electric Works, Cleveland, O.

HOEFT & COMPANY
Die Makers, Machinists and Machinery Builders
170 Michigan St., Chicago, U. S. A.

MOORE & CO. Special Machinery, Dies, Tools, Models, Work

MODELS & EXPERIMENTAL WORK, Gears, Dies, Tools, Novelties manufactured.
M. P. SCHELL, 1759 Union Street, San Francisco

MODELS & GEARS INVENTIONS PERFECTED UNION MODEL WORKS 193 So. CLARK St. CHICAGO.

Steel Railroad Tie of merit and readily applied to use. Pronounced good by railway officials and engineers. Rare chance for gilt-edged investing, responsible parties only. Address H. F. Rainsberger, La Porte, Ind.

Telegraphy Circular free. Wonderful automatic teacher, 5 styles $2 up. OMNIGRAPH CO., Dept. 52, 39 Cortlandt St., New York.

ASTRONOMICAL Photographs and Slides made at YERKES OBSERVATORY can be obtained from The University of Chicago Press, Chicago. 18-page catalogue sent free.

Print Your Own Cards, circulars, book, newspaper. Press $5. Larger $18. Save money. Print for others, big profit. All easy, rules sent. Write factory for press catalog, type, paper, etc.
THE PRESS CO., Meriden, Connecticut.

A WIRELESS TELEGRAPH BOY
By JOHN T. TROWBRIDGE
"An unusually good story, thoroughly up-to-date, and having to do with the escape of a young Russian revolutionist."—*Boston Globe.*
Price $1.25
HOUGHTON MIFFLIN CO., 4 Park Street, Boston

Steel Ball Machinery

for rolling hot steel, and making balls ⅛ to ¾ in. size, and other cylindrical forgings. Also the wood patterns for making the machines. Also 3 Putnam and 1 Dodge Horse Nail Machine; for sale by H. T. MARSHALL MACHINE CO., at 80 Ward St., Brockton, Mass.

What Do You Want To Buy?

We can tell you where to buy anything you want.

Write us for the addresses of manufacturers in ANY line of business.

Novelties, Special Tools, Machinery, Equipments.

New Patent LABOR-SAVING DEVICES.

MUNN & CO., Publishers of Scientific American
361 Broadway, New York, U. S. A.

© 1908 SCIENTIFIC AMERICAN, INC



THE MANUFACTURE MOULDED AND SPECIAL RUBBER GOODS OF EVERY DESCRIPTION AND CAN FURNISH ANY SPECIAL RUBBER ARTICLE TO YOUR SATISFACTION

NEW YORK BELTING & PACKING CO. Ltd.
91-93 CHAMBERS STREET,
NEW YORK

DECARBONIZER

chemically removes carbon from cylinders, piston rings and valves.

INCREASES POWER 20 PER CENT

Volatilizes carbon, in which form it passes out thru exhaust. **Injury to metal impossible.** Agents wanted in certain localities. **Sample, quart can, $1.50.** Write to-day for particulars.

General Accumulator & Battery Co
128 Second Street, Milwaukee, Wis.

LUFKIN

the trade-mark emblematic of the WORLD'S BEST MEASURING TAPES. Not much to look for, but a great deal to find. Watch for it.



Send for Catalog and Circular

of our new "Instantaneous Readings"—the greatest improvement ever made in the marking of measuring tapes. Saves time and eliminates errors.

THE LUFKIN RULE CO., Saginaw, Mich., U. S. A.
New York London, Eng. Windsor, Can.

GROBET Swiss Files

and other tools shown in catalog 27. Sent free if you mention this paper when writing.

MONTGOMERY & CO., 109 Fulton Street, New York City

Ann Arbor Lighting System
GASOLINE WIRE FEED
The most up-to-date and complete lighting system on the market. Beautiful fixtures for the home. Attractive high candle power inverted arcs for stores, halls, etc. The best proposition going for hustling agents. Write today for agents' terms and territory. Handsome catalog free.
Superior Mfg. Co.
301 Second St., Ann Arbor, Mich.

DRAPER'S

Recording Thermometer

Traces automatically a correct and continuous record in ink of the temperature on a graduated weekly chart. Made in two sizes, and standardized and fully guaranteed. Also other weather recording instruments.

THE DRAPER MFG. CO.
152 Front St., New York



CRESCENT WOOD WORKING MACHINERY

Satisfies Particular Users

Band Saws, Saw Tables, Jointers, Shapers, Borers, Swing Saws, Disk Grinders, Planers, Planer and Matcher, Band Saw Blades.

We want you to have our catalog. Send for it today.

THE CRESCENT MACHINE CO.
230 Main St. Leetonia, Ohio, U. S. A.

HELMET OIL LUBRICATES ANYTHING SEND FOR SAMPLE FREE
15-21 S. CLINTON ST.
C.H. BESLY & CO. CHICAGO, ILLINOIS, USA

No Stropping No Honing

Give Him a Gillette Safety Razor for Christmas

HE will use it, never fear! And thank you from his heart every time he shaves.

Over two million men are using the Gillette—any one of them will tell you he would not be without it for ten times its cost.

Shaving in the old way is the bane of a man's life. It means time wasted at the barber-shop—or tedious stropping and scraping with the old-fashioned razor, with the certainty of cuts and scratches if he is nervous or in a hurry. Besides, as you know, he is not always shaved when he ought to be.

The Gillette makes shaving easy. Takes only five minutes for a smooth, satisfying shave, no matter how rough the beard or tender the skin.

No stropping, no honing. Any man can use it. It is the one razor that is safe—*cannot cut his face*—and it is the only razor that can be adjusted for a light or a close shave.

A man is conservative. He takes to the Gillette like a duck to water once he gets acquainted—but, as with other improvements, it sometimes takes a woman to lead him to it.

The Gillette makes a beautiful gift, with its triple silver-plated handle, in velvet lined, full leather Standard set, as illustrated above, $5.00.

Combination sets, $6.50 to $50.00.

Send for illustrated booklet to-day.

The Gillette is on sale at all leading jewelry, drug, cutlery, hardware and sporting goods stores. If your dealer cannot supply you write to us.

New York Times Building — GILLETTE SALES CO. — Chicago Stock Exchange Building
207 Kimball Building Boston

Factories: Boston, London, Berlin, Paris, Montreal

Gillette Safety Razor

NO STROPPING NO HONING

An Ideal Xmas Gift for Lady or Gentleman

Our Famous and Popular **Non-leakable RED GEM**—the Ink Pencil—regular $2.50 value, guaranteed. Hard Rubber Holder, Iridium Point, Spring Feed. On approval to responsible people for only $1, postpaid. Address

LAUGHLIN MFG. CO. 583 Majestic Building DETROIT, MICH.



TIE IT WITH A *Pull Fastener*

String, Tape and Straps take too long to fasten. Rubber Bands rot—besides they're useless for securing a bulky package.

The **"PULL FASTENER"** does all that these old-fashioned tying appliances do—*does it quicker, better and easier.* Yet it costs no more than rubber bands, and lasts ten times longer.

A bulky parcel, clumsy bundle or dainty package are all the same to a **"PULL FASTENER."** Place around the package and pull—that's all. "Binds with a grip of steel; tied or loosened in a second."

Pull Fastener

"PULL FASTENERS" are made in cord, tape, webbing and strap form—for every purpose. Over 38 different styles, sizes and prices, from three-for-a-cent upwards. Various colors—brown, red, pink, gray, orange, white. Special sizes or styles made to order.

"PULL FASTENERS" are used and indorsed by Architects, Engineers, Government Officials, Banks, Attorneys, Prominent Manufacturers, Business and Professional men in every walk of life.

Write on your business paper for finely illustrated catalog and free samples. Representatives wanted.

THE PULL FASTENER COMPANY
306 COX BUILDING, ROCHESTER, NEW YORK

Make Your Own Cigarettes

50 Perfectly Formed Pure Smokes for 5 Cents

THE MOST USEFUL MACHINE EVER INVENTED—A USEFUL HOLIDAY GIFT

Agents wanted everywhere



Why smoke impure cigarettes when you can make them yourself and know their contents? Enjoy a smoke that will not injure your health. A fresh, pure, cigarette made in a few seconds at one-fifth the cost. Made to fit vest pocket. Thousands in use, all giving satisfaction.

Your money back if you want it.

Nickel or Gunmetal - 50 cents } Prepaid
Sterling Silver - - - $5.00 }

ESRICH MFG. CO., New York. Oct. 19, 1908.

Gentlemen—The cigarette machine received today, and, without exception it is the best little cigarette maker I ever saw—so simple and complete. CANBY STEEL, Pinehurst, N. Car.

ESRICH MFG. CO., Dept. 21, 28 E. 23d Street, New York

STAR EXPANSION BOLTS

MAKE QUICK, SECURE FASTENINGS TO MASONRY

For Wood Screws, Nos. 5 to 18 inclusive.

For Lag Screws, 5-32 to 1⅛ inches diameter.

For Machine Bolts, 3-16 to 2 inches diameter.

Write for Catalog and Samples

Star Expansion Bolt Co.
BAYONNE, N. J.

COLD GALVANIZING.

AMERICAN PROCESS. NO ROYALTIES.
SAMPLES AND INFORMATION ON APPLICATION.



NICKEL AND Electro-Plating
Apparatus and Material
THE Hanson & Van Winkle Co.,
Newark, N. J.
28 & 30 S. Canal St. Chicago.

New British Patent Act

RESPONSIBLE manufacturing firm operating large, up-to-date brass and copper rolling mills in Birmingham, England, is open to receive proposals from owners of American Patents protected in Great Britain, for the production of any of the under-noted articles or machines:

Blanking Machines.
Cupping Machines.
Drawing Presses.
Power Stamping Machines.
Cartridge Piercing Machines.
Heading Machines.
Indenting Machines.
Bullet Machines of every description.
Cutting-off Machines.
Automatic Feeds for the whole of the above.
Machines for the Manufacture of Explosives.
Paper Tube Rolling Machine for Sporting Case Work.
Paper Tube Polishing Machines.
Rivet and Nail Machines.
Detonator Machinery.
Wire Covering Machinery.

Apply in first instance to

J. H. LAU & CO.
P. O. Box 580, New York City, New York

Your dreams

can be realized.

No matter what your position may be, if you are poorly paid and there is no prospect for anything better, the American School of Correspondence can help you. We make the way easy for the ambitious, earnest man.

We help him realize his **dreams** of the future.

During the past 15 years we have helped over 80,000 men qualify for better positions and more salary.

Fill in and mail the coupon to-day and we will send you FREE, our handsomely illustrated 200-page Bulletin of *Engineering Information* describing in detail over 60 practical home study courses including Civil, Electrical, Stationary, Locomotive, Railroad, Mechanical, and Structural Engineering, Mechanical Drawing, Ventilation, Heating and Plumbing, Sheet Metal Pattern Drafting, Architecture, Complete Carpentry, Mathematics, Textiles, College Preparatory, etc.

We help men help themselves.

American School of Correspondence
CHICAGO, U. S. A.

FREE INFORMATION COUPON
Clip and Mail To-day.

American School of Correspondence:

Please send me FREE illustrated 200-page Bulletin of engineering information. I am interested in the

COURSE IN .....

NAME .....

ADDRESS .....

OCCUPATION .....

Sci. Am., 12-5-08.

© 1908 SCIENTIFIC AMERICAN, INC